

***Standards and Specifications
For Erosion and Sediment Control
and Stormwater Management***

Prepared for **Old Dominion University**
Hampton Boulevard
Norfolk, Virginia 23529

Prepared by **VHB**
Two Columbus Center
4500 Main Street, Suite 400
Virginia Beach, Virginia 23462
757.490.0132

January 2025

Regulatory Cross-reference

The Old Dominion University Standards and Specifications for ESC and SWM have been developed consistent with 9VAC25-875-830. E. The Virginia Stormwater Management Handbook, Appendix J, which provides a list of the required content for standards and specifications is referenced below. The table below provides a cross-reference between this Standards and Specifications document and the Appendix J requirements.

Appendix J Section	Appendix Title	ODU S&S Reference Location
J.1	Standards and Specifications Entity	Page 3
J.2	Standards and Specifications Entity Type	
J.3	Standards and Specifications Agreement Information	
J.4	Certification	
J.5	Administration	
J.6	Regulated Land-Disturbing Activities	Section 3
J.7	Certified Personnel	Section 2
J.8	Review and Approval of Plans	Section 5.1
J.9	ESC Plan – Contents	Section 4.2, 5.1 and Appendix H
J.10	ESC Plan – Variances and Exceptions	Section 5.5
J.11	SWPPP Contents	Section 5.3 and Appendix C
J.12	SWM Plan – Contents	Section 4.1, 5.1 and Appendix H
J.13	Pollution Prevention Plan – Contents	Section 5.3 and Appendix C
J.14	Technical Criteria for Land Disturbing Activities	Section 4
J.15	Long-Term Maintenance of Permanent Stormwater Facilities	Section 6.5
J.16	Project Tracking and Reporting	Section 6.1, Appendix A
J.17	Monitoring, Inspections, and Enforcement	Section 6.3, Appendix B

Entity Information

Standards and Specifications Entity Information

Entity Name: Old Dominion University

Entity Address: 5255 Hampton Blvd., Spong Hall, Suite 203, Norfolk, VA 23529

Contact: Doug Alexander, Environmental Health and Safety Officer

Email: dalexand@odu.edu Phone: 757-683-5817

Alternate Contact:

Entity Type: State Agency

Standards and Specifications Agreement Information

Agreement Date: January 20, 2025

Date of previously approved agreement: April 30, 2020

Updates since previous agreement: The latest Standards and Specifications have been updated for the new Virginia Erosion and Stormwater Management Act and the latest General VPDES Permit for Discharged of Stormwater from Construction Activities that took effect on July 1, 2024.

Certifications

"I certify under penalty of law that this agreement and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and believe, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Printed Name: _____

Title: _____

Signature: _____

Date: _____

Standards and Specifications Administration

Old Dominion University (ODU), hereinafter the "S&S Entity", is responsible for administering, implementing, and complying with the standards and specifications for Erosion and Sediment Control (ESC) and Stormwater Management (SWM) set out in this agreement by following the design criteria in the Virginia Stormwater Management Handbook, Version 1.0, for applicable land disturbance activities, as described herein.

Table of Contents

<i>List of Abbreviations</i>	6
<i>Definitions</i>	7
<i>1. Introduction</i>	8
<i>2. Standards and Specifications Personnel</i>	10
<i>3. Applicability</i>	12
<i>4. Technical Criteria</i>	14
<i>5. Plan Approval and Application Process</i>	16
<i>6. Construction and Inspections</i>	19
<i>7. DEQ Oversight</i>	24

Appendix	Description
A	Land-Disturbance Activity and Project Tracking Sheet
B	ESC/SWM Inspection Report Form
C	Stormwater Pollution Prevention Plan Template
D	Non-VSMH Specifications
E	ESC and SWM Plan Approval Letter
F	Standards and Specifications Information Sheet
G	General Erosion and Sediment Control Notes
H	ESC and SWM Plan Submitter's Checklist
I	Delegation of Authority

List of Abbreviations

Title	Abbreviation
Standards and Specifications.....	S&S
Best Management Practice.....	BMP
Chesapeake Bay Preservation Area	CBPA
Clean Water Act	CWA
Construction General Permit	CGP
Virginia Department of Conservation and Recreation	DCR
Division of Engineering & Buildings	DEB
Virginia Department of Environmental Quality	DEQ
Engineer of Record	EOR
Environmental Protection Agency	EPA
Erosion and Sediment Control	ESC
Land-Disturbing Activity	LDA
Municipal Separate Storm Sewer System	MS4
Old Dominion University.....	ODU
Responsible Land Disturber	RLD
Stormwater Management	SWM
Stormwater Pollution Prevention Program	SWPPP
Total Maximum Daily Load.....	TMDL
Vanasse Hangen Brustlin.....	VHB
Virginia Administrative Code	VAC
Virginia Pollution Discharge Elimination System.....	VDPES
Virginia Erosion and Stormwater Management Act.....	VESMA
Virginia Stormwater Management Handbook	VSMH
Virginia Stormwater Management Program	VSMP
Water Quality Act	WQA

Definitions

"Applicant" means person or persons providing submission for land-disturbing projects on the Old Dominion University campus.

"Board" means the State Water Control Board.

"Certified Personnel" person or persons who hold a certificate of competence in accordance with 9VAC25-875 Part IV. issued by the board. See Section 2: Standards and Specifications Personnel for more information.

"Contractor" means the operator of the regulated land-disturbing activities.

"Department" means the Department of Environmental Quality

"Operator" means the permittee to which a local permit or state permit for regulated land-disturbing activities is issued.

"Permit" or *"VSMP authority permit"* means an approval to conduct a land-disturbing activity issued by the VSMP authority for the initiation of a land-disturbing activity after evidence of state VSMP construction general permit coverage has been provided where applicable.

"Permittee" means the person to which a local permit or Construction General Permit for regulated land-disturbing activities is issued.

"Virginia Erosion and Sediment Control Program authority" or *"VESCP authority"* means a locality that is approved by the Board to operate a Virginia Erosion and Sediment Control Program in accordance with Article 2.4 (§ 62.1-44.15:51 et seq.). Only a locality for which the Department administered a Virginia Stormwater Management Program as of July 1, 2017, is authorized to choose to operate a VESCP pursuant to Article 2.4 (§ 62.1-44.15:51 et seq.).

"Virginia Stormwater Management Program authority" or *"VSMP authority"* means an authority approved by the Board after September 13, 2011, to operate a Virginia Stormwater Management Program or the Department. An authority may include a locality; state entity, including the Department; federal entity; or, for linear projects subject to standards and specifications in accordance with subsection B of § 62.1-44.15:31, electric, natural gas, and telephone utility companies, interstate and intrastate natural gas pipeline companies, railroad companies, or authorities created pursuant to § 15.2-5102.

1. Introduction

The Standards and Specifications (S&S) Program for Old Dominion University (ODU) has been developed in accordance with §62.1-44.15:31 of the State Water Control Law and section 9VAC25-875-830 of the Virginia Administrative Code. The ODU S&S incorporates the following regulations, laws, and codes by reference:

- Virginia Erosion and Stormwater Management Act (VESMA) (§62.1-44.15:24 et seq. as amended)
- Virginia Erosion and Stormwater Management Regulations (9VAC25-875 et seq. as amended)
- Virginia Pollutant Discharge and Elimination System General Permit for Discharges of Stormwater from Construction Activities (9VAC25-880 et seq. as amended)
- Virginia Pollutant Discharge and Elimination System General Permit for Discharges of Stormwater from Small Municipal Separate Storm Sewer Systems (9VAC25-890 et seq. as amended)
- Chesapeake Bay Preservation Act (§62.1-44.15.67 et seq. as amended)
- Chesapeake Bay Preservation Act Area Designation and Management Regulations (9VAC25-830 et seq. as amended)
- Technical Bulletins, as amended, on the Virginia DEQ website at www.deq.virginia.gov/
- Memos, as amended, on the Virginia DEQ website at www.deq.virginia.gov/.

The ODU S&S shall be applicable to all land-disturbing activities on the ODU campus as described by VESMA and Virginia ESC and SWM Regulations, and shall be submitted to the Virginia Department of Environmental Quality (DEQ) every five (5) years for review and approval (9VAC25-875-830, §62.1-44.15:31.D). The Old Dominion University Director of Environmental Health and Safety shall administer and enforce the ODU S&S and will ensure that appropriate faculty and staff obtain required DEQ certifications as necessary as specified in the Virginia ESC and SWM Certification Regulations (9VAC25-875-380 through 9VAC25-875-460). Certifications are required for S&S entities that could potentially include, but are not limited to Program Administrator, Plan Reviewer, Inspector, or a combination of certifications. ODU may enter into agreements or contracts with soil and water conservation districts, adjacent localities, or other public or private entities to carry out or assist with the responsibilities of their S&S.

The purpose of the ODU S&S is to provide standard methods for guiding land-disturbing projects on the ODU campus through planning, design, approval, construction, and post-construction. The S&S describe how land-disturbing activities shall be conducted and includes the following:

- Provisions for the preparation of SWM and ESC plans that comply with locality requirements and VSMP regulations.

- Provisions for long term maintenance of SWM facilities, devices, and other post construction best management practices (BMPs). Provisions include inspection procedures and timelines.
- Provisions for ESC and SWM program administration including plan design, plan review, plan approval, construction inspections, and enforcement.
- Provisions to ensure that appropriate personnel obtain DEQ certifications for ESC and SWM.
- Means and methods to provide tracking and notification of land-disturbing activities.
- Means and methods to document plan changes and to ensure that they comply with ESC and SWM regulations.

2. Standards and Specifications Personnel

The following is a breakdown in responsibilities and titles regarding the ODU S&S for ESC and SWM. Responsibilities may be combined in terms of staffing resources only if the person responsible for the task(s) satisfies the designation of certified personnel. The Director of Environmental Health and Safety shall be the program administrator. The following titles are designated to ensure compliance with erosion and sediment control and stormwater management regulations on all ODU projects.

1. "Certified ESC Inspector" means an employee or agent of Old Dominion University who: (i) holds a certificate of competence from the Board in the area of project inspection; or, (ii) is enrolled in the Board's training program for project inspection and successfully completes such program within one year after enrollment; and (iii) shall be responsible to inspect as mandated by the VESCL&R erosion and sediment control measures to ensure proper installation in accordance with the approved plan and record the state and effectiveness of such measures in an effort to minimize site erosion and sediment control.
2. "Certified SWM Inspector" means an employee or agent of Old Dominion University who: (i) holds a certificate of competence from the Board in the classification of project inspector in the area of SWM; or, (ii) is enrolled in the Board's training program for project inspector and successfully completes such program within one year after enrollment; and, (iii) shall be responsible to inspect construction sites for SWPPP compliance.
3. "Certified ESC Plan Reviewer" means an employee or agent of Old Dominion University who: (i) holds a certificate of competence from the Board in the area of plan review; (ii) is enrolled in the Board's training program for plan review and successfully completes such program within one year after enrollment; or (iii) is licensed as a professional engineer, architect, certified landscape architect, or land surveyor pursuant to Article 1 (§ 54.1-400 et seq.) of Chapter 4 of Title 54.1 of the Code of Virginia; or (iv) is a professional soil scientist as defined in Chapter 22 (§ 54.1-2200 et seq.) of Title 54.1 of the Code of Virginia.
4. "Certified SWM Plan Reviewer" means an employee or agent of Old Dominion University who: (i) holds a certificate of competence from the Board in the classification of plan reviewer in the area of SWM; or, (ii) is enrolled in the Board's training program for plan reviewer and successfully completes such program within one year after enrollment.
5. "Certified ESC Program Administrator" means an employee or agent of Old Dominion University who: (i) holds a certificate of competence from the

Board in the area of program administration; or, (ii) is enrolled in the Board's training program for program administration and successfully completes such program within one year after enrollment. The certification for Certified ESC Program Administrator cannot be contracted out and must be fulfilled by the S&S holder.

6. "Certified SWM Program Administrator" means an employee or agent of Old Dominion University who: (i) holds a certificate of competence from the Board in the classification of program administration in the area of SWM; or, (ii) is enrolled in the Board's training program for program administration and successfully completes such program within one year after enrollment. The certification for Certified SWM Program Administrator cannot be contracted out and must be fulfilled by the S&S holder.
7. "Certified ESC Combined Administrator" means an employee or agent of Old Dominion University who: (i) holds a certificate of competence from the Board in the area of program administration, plan review and project inspection; or, (ii) is enrolled in the Board's training program for program administration, plan review and project inspection and successfully completes such program within one year after enrollment. The certification for Certified ESC Combined Program Administrator cannot be contracted out and must be fulfilled by the S&S holder.
8. "Certified SWM Combined Administrator" means an employee or agent of Old Dominion University who: (i) holds a certificate of competence from the Board in the classification of program administration, plan reviewer and project inspector in the area of SWM; or, (ii) is enrolled in the Board's training program for program administration, plan reviewer, and project inspector and successfully completes such program within one year after enrollment. The certification for Certified SWM Combined Program Administrator cannot be contracted out and must be fulfilled by the S&S holder.

Please note that any person who holds a valid and unexpired certificate of competence issued by the board in the classification of ESC or SWM, or who obtains such a certificate, and who later successfully obtains an additional certificate may surrender both certificates of competence to the board and request in writing issuance of a dual certificate showing certification in both classifications. Such a request must be made while both the ESC and SWM certificates of competence obtained are valid and unexpired.

3. Applicability

The ODU S&S shall be applicable for land-disturbing activities on the ODU campus. Depending on the type of activity, the definition of a land-disturbing activity is subject to the ESC or SWM Laws and Regulations that govern ESC and SWM. However, any project disturbing 2,500 sf or greater will be subject to the ODU S&S.

3.1 Erosion and Sediment Control

Per the VESMA (§62.1-44.15.51 et seq.), a land-disturbing activity is defined as *“any man-made change to the land surface that may result in soil erosion or has the potential to change its runoff characteristics, including the clearing, grading, excavating, transporting, and filling of land.”* In addition, a land-disturbing activity is considered to be an area greater than 10,000 square feet in size or 2,500 square feet in size that is within an area designated as a Chesapeake Bay Protection Area (CBPA).

Exceptions to the ESC definition of land-disturbing activity that may be applicable to the ODU campus as defined by ESC Law include:

- Minor landscaping, repairs, and maintenance
- Individual service connections
- Installation, maintenance, or repair of underground public utility lines. The utility must be located under hardscape surfaces and the land-disturbance must disturb only hardscaped surfaces.
- Installation of fences, posts, or poles
- Shoreline erosion control projects on tidal waters. All disturbing activities must be within regulatory and approved by local wetland boards, the Marine Resource Commission, or the United States Army Corps of Engineers.
- Emergency or life-saving repairs

3.2 Stormwater Management

Per the Virginia SWM Act (§62.1-44.15.24 et seq.) a land-disturbing activity is defined as *“a man-made change to the land surface that may result in soil erosion or has the potential to change its runoff characteristics, including construction activity such as the clearing, grading, excavating, or filling of land.”* In addition, a land-disturbing activity is considered to be an area greater than one acre in size or an area greater than 2,500 square feet in size that is within an area designated as a Chesapeake Bay Protection Area (CBPA).

Exemptions to the SWM definition of land-disturbing activity that may be applicable to the ODU campus as defined by the Virginia SWM Act include:

- Routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original construction of the project. The paving

of an existing road with a compacted or impervious surface and reestablishment of existing associated ditches and shoulders shall be deemed routine maintenance if performed in accordance with §62.1-44.15.34 et seq; and

- Conducting land-disturbing activities in response to a public emergency where the related work requires immediate authorization to avoid imminent endangerment to human health or the environment. In such situations, the VSMP authority shall be advised of the disturbance within seven days of commencing the land-disturbing activity, and compliance with the administrative requirements of subsection A is required within 30 days of commencing the land-disturbing activity.

4. Technical Criteria

4.1 Stormwater Management

An SWM plan shall be designed in accordance with the VESMA Regulations (9VAC25-875-380 through 9VAC25-875-460), and the latest edition of the Virginia Stormwater Management Handbook. The plan shall address the Construction General Permit plan requirements listed in 9VAC25-880-70 Part II.A.

Projects shall be designed per Technical Criteria Part IIB (9VAC25-875-570 et seq.) of the VESMA regulations. Water quantity (9VAC25-875-600) shall be met for channel and flood protection. The Runoff Reduction Method and Guidance Memo No. 16-2001 shall be utilized for water quality compliance and meet minimum design criteria and standards (9VAC25-875-580). Best management practices (BMPs), both structural and non-structural, shall be designed in accordance with the Virginia BMP Clearing House BMP Design Specifications (9VAC25-875-590). If water quality cannot be met on site, offsite compliance options may be utilized if the criteria in 9VAC25-875-610 is met.

If the project is considered grandfathered it shall be designed per Technical Criteria Part IIC (9VAC25-875-670 through 9VAC25-875-730 et seq.) of the VSMP regulations if the criteria in 9VAC25-875-680 is met.

4.2 Erosion and Sediment Control

An ESC control plan shall be designed in accordance with the VESMA Regulations (9VAC25-875-380 through 9VAC25-875-460), and the latest edition of the Virginia Stormwater Management Handbook. The plan shall address the Construction General Permit plan requirements listed in 9VAC25-880-70 Part II.A.2 and the minimum standards described in 9VAC25-875-560.

4.3 Non-VSMH Control Measures

The use of Virginia Stormwater Management Handbook (VSMH), along with accompanying technical documents and guidance, control measures is strongly preferred. Non-VSMH control measures, best management practices (BMP), and specifications may be included in the Standards and Specifications submission, but their use may be further reviewed and approved by the applicable DEQ Regional Office on a project-specific basis. For all non-VSMH and proprietary control measures, please include all applicable practical information including definition, purpose, conditions where practice applies, planning considerations, design criteria,

construction specifications, design tables and plates, and maintenance and inspections. Non-VSMH and proprietary control measures shall be installed per the manufacturer's instructions and with the intent of the VSMH specifications. Should non-VSMH control measures fail to effectively control soil erosion, sediment deposition, and non-agricultural runoff, then VSMH control measures shall be utilized.

5. Plan Approval and Application Process

5.1 Plan Submission and Review Process

If the land-disturbing activity disturbs more than 2,500 sf, an ESC and SWM plan shall be submitted for review. The plans shall be reviewed and recommended for approval by the ODU Director of Environmental Health and Safety or an ODU representative of the Director that satisfies the designation of certified personnel. ESC and SWM plans shall comply with ODU Standards and Specifications for ESC and SWM, the Virginia Erosion and Stormwater Act (§62.1-44 et seq.), associated ESC and SWM regulations, and the Virginia Erosion and Stormwater Management Regulation (9VAC25-875 et seq.). ODU state owned projects are located within the City of Norfolk and the locality requirements shall apply for all ESC and SWM submissions. Per 9VAC25-875-810 it shall be the responsibility of the state agency to demonstrate if the locality's VSMP authority's technical requirements are not practicable for the project under consideration. If the technical requirements are not practicable ODU shall include documentation including the reasons with the project records.

Once the plan and supporting documentation are deemed adequate, ODU or an approved representative will:

1. Stamp the plans and calculations.
2. Forward an approval letter to the project manager and EOR.
3. Review the SWPPP if general permit coverage is required.

5.2 Construction General Permit Permitting Process

Land-disturbance activities equal to or greater than one acre will require a DEQ issued, General Virginia Pollution Discharge Elimination Systems Permit (VAR 10) for Discharges of Stormwater from Construction Activities. The contractor, operator, shall obtain a Construction General Permit prior to commencement of land-disturbance.

The Contractor shall submit the following documents to DEQ:

- ESC Plan Approval Letter
- SWM Plan Approval Letter
- Registration Statement for General Permit (VAR 10)
- Construction General Permit Fee Form and applicable fee

Land-disturbance of offsite areas for support activities that include, but are not limited to borrow areas, disposal areas, and laydown areas, may be permitted by the Construction General Permit provided the provisions in 9VAC25-880-30.C and 9VAC-25-875-990 are met.

5.3 Stormwater Pollution Prevention Plan (SWPPP)

A SWPPP shall be prepared in accordance with the requirements per Part II of 9VAC25-880-70. The SWPPP must be completed prior to the submission of a registration statement and implemented for the construction activity, including any support activity, covered by the Construction General Permit. The applicant shall use the appropriate Old Dominion University SWPPP template (Appendix C) for all projects disturbing more than 2,500 sf.

5.4 Approved Plan Modifications

If modifications exceed the limitation of a BMP, revised calculations are required. If the inspector requests the change, amendments to approved plans must be reviewed by the Director of Environmental Health and Safety, a representative of the Director, or EOR. Red lines must be checked and signed off by the DEQ-Certified Inspectors. Revisions shall not be considered approved until written notice is provided. The project SWPPP will need to be updated with approved changes and amendments. If a change will increase the land disturbance to a higher permit fee, the difference in fees will be paid to the DEQ.

5.5 Variances and Exceptions

Variance requests may be submitted by the applicant during the design process to become part of the approved ESC plans per 9VAC25-875-350. All variance requests shall be submitted to ODU and reviewed for completeness and will be forwarded to DEQ for review if appropriate. Variances will not be considered approved until written approval from DEQ has been received. Variance requests shall be a letter with an explanation for the reasons the ESC technical standards cannot be met and describe how the downstream properties will be protected from erosion, sedimentation and flooding.

Exception requests may be submitted by the applicant during the design process to become part of the approved SWM plans per 9VAC25-875-170. All Exception requests shall be submitted to ODU, be reviewed for completeness, and be forwarded to DEQ for review as appropriate. Exception requests will not be considered finalized

until written approval from DEQ has been received. Exception requests shall be a letter format, with an explanation why the SWM technical standards cannot be met.

Economic hardship alone is not a sufficient reason to request a Variance or Exception from the ESC and/or SWM requirements.

6. Construction and Inspections

All contractors performing land disturbing activities on campus property are required through contract documents to follow existing ESC requirements and obtain all applicable permits before construction activity commences. The CO-7 General Conditions of the Construction Contract requires that the contractor have a DEQ-certified responsible land disturber on-site. In addition to contract language, all work performed on ODU property is required to comply with the Construction and Professional Services Manual (CPSM) published by the DEB and ODU's Design Standards.

6.1 Project Tracking for Land-Disturbing Activities

A list of completed, current or expected land-disturbing activities to occur during this S&S period are included in Appendix A. ODU is required to provide annual reporting for all ESC and SWM regulated land disturbing activities. Reporting to the DEQ will be provided October 1st each year for the previous year's activity. Reports should include the following information:

- i. Project name or project number (any associated CGP permit #).
- ii. Project location
- iii. Brief project description
- iv. Acreage of disturbance for project
- v. Project start and finish date (status)
- vi. Any variances/waivers/exemptions associated with this project.

6.2 Project E-Notification

ODU is required to notify the DEQ at least two weeks prior to initiating an ESC and SWM regulated LDA. E-notifications shall be sent to StandardsandSpecs@deq.virginia.gov (DEQ Central Office) and courtney.smith@deq.virginia.gov (DEQ Tidewater Regional Office). The following information needs to be included in the e-notification:

- i. Project name or project number (any associated CGP permit #).
- ii. Project location (including nearest intersection, latitude and longitude, access point)
- iii. On-site project manager name and contact info
- iv. Responsible Land Disturber (RLD) name and contact info.
- iv. Project description
- v. Acreage of disturbance for project
- vi. Project start and finish date
- viii. Any variances/waivers/exemptions associated with this project.

6.3 Inspections

Old Dominion University is responsible for the implementation and oversight of the S&S during construction. ODU, or ODU's representative, who is a Certified ESC or SWM inspector will perform periodic inspections for ESC and SWM for all land-disturbing activities. These inspections will occur in addition to the inspections required per the Construction General Permit (if required) and SWPPP. The Inspection Report Form provided in Appendix B shall be used for inspections and shall identify the inspector and note any issues or violations. The inspection form shall be provided to the Contractor within 48 hours of the inspection and shall note any required actions and deadlines to correct any noted violations. If a noted violation repetitively shows up on the inspection report a Notice to Comply will be issued by the ODU S&S program administrator. Subsequently, a Stop Work Order will be issued if the violations have not been corrected by the specified deadline on the Notice to Comply (Refer to ODU Enforcement below). The inspection requirements are as follows:

- a. ESC Inspection Requirements (9VAC25-875-140, § 62.1-44.15:58). Periodic inspections are required on all projects by ODU. ODU shall:
 - i. Provide for an inspection during or immediately following initial installation of erosion and sediment controls,
 - ii. At least once in every two-week period, within 48 hours following any runoff producing storm event, and
 - iii. At the completion of the project prior to the release of any performance bonds.
- b. SWM Inspection Requirements (§ 62.1-44.15:58) ODU:
 - i. Shall provide for periodic inspections of the installation of stormwater management measures at the beginning of the project and monthly during construction,
 - ii. Shall provide for inspections of SWPPPs (General information, ESC plan, SWM plan, pollution prevention plan, TMDL requirements), at the beginning of the project and at least once every four business days or at least once every five business days and no later than 24-hours following a measurable storm event.
 - iii. May require monitoring and reports from the person responsible for meeting the permit conditions to ensure compliance with the permit and to determine whether the measures required in the permit provide effective stormwater management, and
 - iv. Shall conduct such investigations and perform such other actions as are necessary to carry out the provisions of this article.
- c. The position, agency, department, or other party responsible for conducting inspections should be identified.
- d. Inspections of land disturbing activities shall be conducted by a DEQ-certified inspector (ESC and/or SWM).

ODU, or ODU's representative, shall inspect the land-disturbing activity periodically during construction for (9VAC25-875-140):

1. Compliance with the approved erosion and sediment control plan
2. Compliance with the approved stormwater management plan
3. Development, updating, and implementation of a pollution prevention plan; and
4. Development and implement of any additional control measures necessary to address a TMDL.

ODU Enforcement:

The Inspection Report Form provided in Appendix B shall be used for inspections and shall identify the inspector and note any issues or violations including violation level:

- Green - Owner Inspection showed site in compliance with S&S.
- Yellow - Owner Inspection included items of noncompliance to be addressed within the designated period.
- Red- Owner Inspection included items of noncompliance that were not corrected within the designated time frame, or the site has observed or perceived offsite sediment or pollutant discharges.
- Black- Owner Inspection included items of noncompliance that were not corrected from the red status, or the site is in significant conflict with the OSU S&S.

Site that obtains a Black status will be directed to the Director of Environmental. If the decision is made to issue a Stop Work Order, then all losses obtained from the Order will be the responsibility of the contractor.

6.4 Construction General Permit & SWPPP

The operator of the Construction General Permit (CGP) is responsible for maintaining and documentation of the SWPPP throughout construction. The operator must adhere to the requirements of 9VAC25-880-70 Part II-B. The operator can terminate the CGP coverage with DEQ in accordance with the criteria in 9VAC25-880-70. F.

6.5 Long-Term Maintenance Agreements

ODU is responsible for the long-term maintenance and inspections of the SWM facilities, and other techniques specified, to manage the quality and quantity of runoff per 9VAC25-875-130 & 140. Certified personnel shall conduct, at a minimum, annual inspections of the campus SWM facilities. ODU is responsible to ensure the following for all state maintenance agreements:

- a. Responsibility for the operation and maintenance of SWM facilities shall remain with the state entity and shall pass to any successor or owner. If

portions of the land are to be sold, legally binding arrangements shall be made to pass the basic responsibility to successors in title. These arrangements shall designate for each state project the property owner, governmental agency, or other legally established entity to be permanently responsible for maintenance.

- b. At a minimum, a SWM facility shall be inspected by the responsible state entity on an annual basis and after any storm which causes the capacity of the facility principal spillway to be exceeded.
- c. During construction of the SWM facilities, the DEQ shall make inspections on a random basis.
- d. The DEQ shall require inspections and reports from the state entity responsible for ensuring compliance with the state permit and to determine if the measures required in the state permit provide effective stormwater management.
- e. Inspection reports shall be maintained as part of the land disturbance project file.
- f. A draft maintenance agreement is required to be submitted at the time of plan submission. State maintenance agreements are required to be printed on the approved plan sheets. The following should be included:
 - i. A description of the requirements for maintenance and maintenance inspection of the SWM facilities and a recommended schedule of maintenance inspection and maintenance.
 - ii. The identification of a person or persons who will be responsible for inspections and maintenance.
 - iii. The maintenance inspection schedule and maintenance requirements should be in accordance with the Virginia BMP Clearinghouse, the Virginia SWM Handbook, the MS4 permit (if applicable) and/or the manufacturer's specifications.
 - iv. Please clearly depict the types of land cover on the site (i.e. different type of hatching for each land cover), including the acreage for each cover type. The acreage should be labeled in all the subareas and within a table that adds the land cover up by type on the sheet.
 - v. Please draw metes and bounds all the way around any conserved open space.
 - vi. Please label any conserved open space as "Runoff Reduction Compliance Forest / Open Space"
 - vii. Please include the following note on the sheet: "The Runoff Reduction Compliance Forest/Open Space area shown here shall be maintained in a forest/open space manner until such time that an amended storm water management plan is approved by the VSMP Authority."

6.6 Record Keeping

ODU is responsible for providing the following information to DEQ by October 1st every year. The information provided below shall be for the fiscal year (July 1 to June 30).

- Information on each permanent SWM facility completed during the fiscal year to include type of SWM, geographic coordinates, acres treated, and the surface waters or karst features into which the SWM facility will discharge.
- Number and type of enforcement action during the fiscal year.
- Number of variances/exceptions granted during the fiscal year.

ODU is responsible for keeping records in accordance with the following:

- Project records, including approved SWM plans, shall be kept for three years after Construction General Permit termination or project completion.
- SWM facility inspection records shall be documented and retained for at least five years from the date of inspection.
- Construction record drawings shall be maintained in perpetuity or until a stormwater management facility is removed.
- All registration statements submitted in accordance with 9VAC25-875-920 shall be documented and retained for at least three years from the date of project completion or Construction General Permit termination.
- ODU shall maintain a copy of the approved ESC plan and a record of inspections for each active land-disturbing activity.
- Approved ESC and SWM plans shall be kept on site and made available.

7. DEQ Oversight

7.1 Enforcement

SWM enforcement shall be administered by the Department and the Board where applicable in accordance with the provisions of §62.1-44.15:27.

ESC enforcement shall be administered by the Department and the Board where applicable in accordance with the provisions of §62.1-44.15:54. The Department and the Board, where applicable, shall provide project oversight and enforcement as necessary and comprehensive program compliance review and evaluation. Such standards and specifications shall be consistent with the requirements of §62.1-44.15:56 and associated regulations and the Stormwater Management Act (§62.1-44.15:24 et. seq) and associated regulations when applicable.

7.2 Complaints, Inspections and Fees

Per §62.1-44.15:31.C the Department shall perform random site inspections or inspections in response to a complaint to assure compliance with this article, the Erosion and Sediment Control Law (§62.1-44.15:51 et seq.), and regulations adopted thereunder. The Department may take enforcement actions in accordance with this article and related regulations.

Per §62.1-44.15:31. D the Department shall assess an administrative charge to cover the costs of services rendered associated with its responsibilities pursuant to this section.

Per §62.1-44.15:55. D the Board shall have the authority to enforce approved specifications and charge fees equal to the lower of (i) \$1,000 or (ii) an amount sufficient to cover the costs associated with standard and specification review and approval, projection inspections, and compliance.

7.3 Discretionary Requirements

ODU may be required to provide the following at the discretion of the DEQ:

1. Inspection reports conducted by ODU as well as complaint logs and complaint responses may be required to be submitted to DEQ.
2. ODU may be required to provide weekly e-reporting to the department's applicable regional office:
 - a. Inspection reports.
 - b. Pictures.
 - c. Complaint logs and complaint responses; and
 - d. Other compliance documents.

Appendix A: Land-Disturbance Activity and Project Tracking Sheet

Appendix B:

ESC/SWM Inspection Report Form

Appendix C: Stormwater Pollution Prevention Plan Template

Appendix D:

Non-VSMH Specifications

Appendix E:

ESC and SWM Plan Approval Letter

Appendix G: General Erosion and Sediment Control Notes

Appendix H: ESC and SWM Plan Submitter's Checklist

Appendix I:

Delegation of Authority

Appendix A: Land-Disturbance Activity and Project Tracking Sheet

Land-Disturbing Activities

<i>Project Name</i>	<i>Project Location</i>	<i>Project Description</i>	<i>Disturbed Area (acres)</i>	<i>Construction Start Date</i>	<i>Construction Completion Date</i>	<i>Variances/ Waivers/ Exemptions?</i>

Appendix B:

ESC/SWM Inspection Report Form

ESC/SWM Inspection Report

Project Information:

Project Name _____

Inspection Date/Time _____

Project No. _____

DEQ Certified Inspector _____

Project Manager _____

CGP Operator/Responsible Land Disturber _____

Weather Conditions:

Current Conditions _____

Current Temperature _____

Reason for Inspection:

Installation of ESC Measures

Two-Week Inspection

Post-Storm Event*

Project Completion

Other _____

Stage of Construction:

Installation of ESC Measures

Clearing & Grubbing

Rough Grading

Building Construction

Finish Grade

Final Stabilization

Construction of SWM Facilities

Maintenance of SWM Facilities

Other _____

*If selected, indicated date of storm event and approximate amount of rainfall.

Date _____ Rainfall ± (in) _____

Violations:

Item No.	State/Local Regulation	Violation		Description and Location of Problem/Violation. Required or Recommended Corrective Actions. Other Comments/Notes
		Initial	Repeat	

Additional Comments/Notes:

Required Corrective Action Deadline Date _____ Re-Inspection Date _____

Reports conducted by ODU or ODU's Representative will be provided to the Operator/Responsible Land Disturber within 48 hours.

Inspector's Name _____

Inspector's Signature _____ Date _____

General Inspection Checklist:

	Item	Yes	No	N/A	Comments/Notes
1	Permanent or temporary soil stabilization has been applied to denuded area?				
2	Soil stock piles and borrow areas have been stabilized or protected with sediment trapping measures?				
3	Permanent vegetation cover is stabilized?				
4	Sediment basins and traps, perimeter dikes, sediment barriers and other measures intended to trap sediment have constructed as a first step during land disturbance?				
5	Stabilization has been applied to earthen structures such as dams, dikes and diversion immediately after installation?				
6	Sediment Basins and Traps provide adequate capacity for the receiving drainage area?				
7	Cut/Fill slopes have been stabilized?				
8	Temporary/permanent channel or drain has been provided for concentrated runoff for cut/fill slopes?				
9	Adequate drainage or other protection has been provided where water seeps from a slope face?				
10	Adequate inlet protection has been provided?				
11	Adequate outlet protection and/or temporary/permanent channel lining has been provided?				

12	Adequate precautions, sediment control measures and stabilization have been performed for work in a live watercourse?				
13	A temporary vehicular stream crossing has been provided for construction vehicles crossing a live watercourse more than twice in a six-month period?				
14	All applicable federal, state and local requirements pertaining to working in or crossing live watercourses have been met?				
15	Bed and banks of a watercourse have been stabilized immediately after work of the watercourse has been completed?				
16a	No more than 500 linear feet of utility trench opened?				
16b	Excavated material has been placed on the uphill side of the utility trench?				
16c	Dewatering operations for utility trenches have been filtered through an adequate sediment trapping device?				
16d	Utility trenches have been adequately stabilized?				
17	Public roads and paved intersection near the vehicular access routes are clear of sediment?				
18	Temporary ESC measures have been removed within 30 days after final site stabilization?				
19	Downstream properties and waterways have been adequately protected from erosion and sediment deposition?				

General Checklist:

Item	Yes	No	N/A	Comments/Notes
Signed copy of the completed SWPPP on-site and accessible? Information posted for public access to the SWPPP?				
DEQ notice of cover letter is posted?				
Copy of the Construction General Permit is posted?				
Copy of the signed registration statement is posted?				
Detailed site plan available?				
Approved ESC plan or agreement in lieu of a plan?				
Description and calculations for all post-construction stormwater management measures?				
SWPPP addresses TMDLs and impaired waters?				
SWPPP is actively being updated and amended?				
SWPPP inspections are being carried out by qualified personnel and at required frequency?				
SWPPP identifies contractor that will implement, update, and maintain each control measure?				

Inspection reports summarize the full scope of inspections and are included in the SWPPP?				
Dates of major grading activities are being recorded?				
Dates of construction activities temporarily or permanently ceasing on a portion of the site being recorded?				
Replaced or modified controls where periodic inspections or other information have indicated that the controls have been used inappropriately or incorrectly and were modified have been documented?				
Record of areas that have reached final stabilization?				
Record of all properties that are no longer under the legal control of the operator and the dates which the operator no longer had legal control over each property?				
Dates of any prohibited discharges, the discharge volume released, and what actions were taken to minimize the impact of the release are being recorded?				
Record of measures taken to prevent the reoccurrence of any prohibited discharge?				

Pollution Prevention (PART II.B.4.e.1-9):

Item	Yes	No	N/A	Comments/Notes
Prevent and respond to leaks, spills, and other releases				
Prevent the discharge of spilled and leaked fuels and chemicals from vehicle fueling and maintenance activities				
Prevent the discharge of soaps, solvents, detergents, and wash water from construction materials, including the clean-up of stucco, paint, form release oils, and curing compounds				
Minimize the discharge of pollutants from vehicle and equipment washing, wheel wash water, and other types of washing				
Direct concrete wash water into a leak-proof container or leak-proof settling basin.				
Minimize the discharge of pollutants from storage, handling, and disposal of construction products, materials, and wastes				
Prevent the discharge of fuels, oils, and other petroleum products, hazardous or toxic wastes, waste concrete, and sanitary wastes				
Address any other discharge from the potential pollutant-generating activities not addressed above;				
Minimize the exposure of waste materials to precipitation by closing or covering waste containers during precipitation events and at the end of the business day or implementing other similarly effective practices.				

Appendix C: Stormwater Pollution Prevention Plan Template

**Virginia Stormwater Management Program-
Stormwater Pollution Prevention Plan (SWPPP)**

Old Dominion University

[Project Title]

[State Project Code (if applicable)]

Norfolk, Virginia

PREPARED FOR

Old Dominion University
Hampton Boulevard
Norfolk, Virginia 22807

PREPARED BY



4500 Main Street, Suite 400
Virginia Beach, VA 23462
757.490.0132

[Month XX, 20XX]

Table of Contents

Table of Contents	2
Introduction.....	1
Plan Purpose.....	1
Background – Construction General Permit	2
SWPPP Coordinator and Duties.....	4
Contractor Agreement.....	4
SWPPP Administration	5
General Information	5
Incorporation of Other Plans	5
Plan Availability.....	5
Plan Updates.....	6
Contractor Responsibilities	6
Specific Requirements	7
Site Description.....	7
Construction Sequence	7
Controls and Measures.....	8
Maintenance	10
Inspections	10
Non-Storm Water Discharges	13
Water Quality Protection	13
Post-Construction Stormwater Management Measures	13
Offsite Nutrient Credits	13
Receiving Waters.....	13
Contractor Certification.....	14
References.....

Appendices

Appendix	Description
A	Site Location Map
B	Storm Water Construction General Permit
C	Forms: Notice of Registration and Notice of Termination
D	Notice of Project Completion
E	Record of Land Disturbance
F	Record of Inspections
G	Record of Contractor Certification
H	Water Quality Protection
I	Details of Best Management Practices
J	ESC & SWM Approval Letters
K	Site Plans (11" x 17" reductions)
L	Amendment Log

Introduction

Plan Purpose

This Storm Water Pollution Prevention Plan (SWPPP) has been developed in accordance with the requirements of the Virginia Stormwater Management Program (VSMP) General Permit for Discharges of Stormwater from Construction Activities (Permit), as defined in General Permit No. VAR10 Effective Date: July 1, 2024, Expiration Date: June 30, 2029. The purpose of this SWPPP is to:

1. Identify potential sources of pollution that may reasonably be expected to affect the quality of storm water discharges from the construction activity, and,
2. To describe and ensure the implementation of practices that will be used to minimize pollutants in storm water discharges from the construction site and to assure compliance with the terms and conditions of the Permit.

Implementation of the components of this SWPPP is required as a condition of the Permit (Appendix B). The Department of Environmental Quality (DEQ) has been granted authority to administer the VSMP program and is therefore the regulatory authority overseeing the implementation of this SWPPP.

Pursuant to VSMP Regulation, Section 520 Pollution Prevention Plans (9VAC25-875-520), this SWPPP must meet the following requirements:

1. Minimize discharge of pollutants from equipment and vehicle washing, wheel wash water and other wash waters. Wash waters must be treated prior to discharge;
2. Minimize exposure of all materials on site to precipitation and stormwater;
3. Minimize discharge of pollutants from spills and leaks and implement chemical spill and leak prevention and response procedures;
4. Best management practices (BMPs) to prohibit wastewater from washout of concrete mixers and equipment, unless managed by appropriate control;
5. BMPs to prohibit wastewater from washout and cleanout of equipment containing stucco, paint, form release oils, curing compounds, and other construction materials;

6. BMPs to prohibit discharges of fuels, oils or other pollutants used in vehicle/equipment operation/ maintenance;
7. BMPs to prohibit discharges of soaps or solvents used in vehicle/equipment washing;
8. Discharges from dewatering activities are prohibited unless managed by appropriate controls.

Background – Construction General Permit

In 1972, Congress passed the Federal Water Pollution Control Act (FWPCA), also known as the Clean Water Act (CWA), to restore and maintain the quality of the nation's waterways. The ultimate goal was to make sure those rivers and streams were fishable, swimmable, and drinkable. In 1987, the Water Quality Act (WQA) added provisions to the CWA that allowed the EPA to govern storm water discharges from construction sites. In 1990, the EPA promulgated rules establishing Phase I of the NPDES storm water program. Phase I addresses, among other discharges, discharges from large construction activities disturbing 5 acres or more of land. In 1998, the EPA published the final notice for General Permits for Storm Water Discharges from Construction Activities (63 Federal Register, February 14, 1998). The general permit includes provisions for development of a SWPPP to maximize the potential benefits of pollution prevention and erosion and sediment control measures at construction sites. Phase II of the NPDES storm water program covers small construction activities disturbing between 1 and 5 acres. Phase II became final on December 8, 1999 with small construction permit applications due by March 10, 2003. Specific compliance dates were to be set by the NPDES permitting authority in each State. The Virginia Department of Environmental Quality amended the General Virginia Pollution Discharge Elimination System (VPDES) Permit Regulations for Discharges of Storm Water from Construction Activities (9 VAC 25-180-10 et seq.) to conform with the EPA Phase II final rule and became effective December 4, 2002. The 2004 Virginia General Assembly passed House Bill 1177 transferring regulatory authority from the State Water Control Board to the Soil and Water Conservation Board and transferred oversight of the programs from the department of Environmental Quality to the Department of Conservation and Recreation. This transfer became effective January 29, 2005. Program oversight was transferred again from the Department of Conservation and Recreation to the Department of Environmental Quality effective July 1, 2013. The General Permit for Discharges of Stormwater from Construction Activities, in accordance with 9VAC25-880, is effective starting July 2024 and applies to all VSMP Permits for Discharge of Stormwater from Construction Activities issued after July 1, 2024.

The General Permit has a fixed term of 5 years from the effective date of July 1, 2024 and is required for all "Small Construction Activity" projects that will disturb 1 acre or greater and less than 5 acres of total land area, and for "Large Construction Activity" projects that disturb 5 acres or more of total land area. To obtain a Permit, operators must submit a Registration Statement (Appendix C) prior to the commencement of construction activities (clearing, grading, or other activities that result in soil disturbance).

The Permit authorizes the discharge of storm water from construction activities until the Permit's expiration date on June 30, 2029. The Permit also authorizes certain non-storm water discharges, provided the conditions contained in the Permit (Part I D) are met.

To terminate coverage under the General Permit, an accurate and complete Notice of Termination (Appendix C) must be submitted to the DEQ within 30 days of one of the following conditions:

1. Necessary post-construction control measures included in the SWPPP for the site are in place and functioning effectively and final stabilization as defined in 9VAC25-880-1 Definitions has been achieved on all portions of the site for which the operator has operational controls;
2. Another operator has assumed control over all areas of the site that have not been finally stabilized and obtained coverage for the ongoing discharge;
3. Coverage under an alternative State or VSMP permit has been obtained; or
4. For individual lots in residential construction, only, final stabilization has been completed and the residence has been transferred to the homeowner.

Coverage under the Permit will be deemed terminated at midnight on the date the Notice of Termination is submitted.

2

SWPPP Coordinator and Duties

SWPPP Coordinator

The construction site SWPPP coordinator for the facility is the undersigned contractor representative. The contractor will be responsible for maintenance of and compliance with the SWPPP. The SWPPP coordinator duties include the following:

- Implement the SWPPP;
- Oversee maintenance practices identified in the SWPPP;
- Implement and oversee employee training;
- Conduct or provide for inspection and monitoring activities;
- Identify other potential pollutant sources and make sure they are added to this SWPPP;
- Identify any deficiencies in this SWPPP and make sure they are corrected; and
- Ensure that any changes in construction plans are addressed in this SWPPP.
- Ensure that the SWPPP is available for review in accordance with the Plan Administration requirements in Chapter 3.
- Respond to regulatory agency requests for information about the construction site as it relates to the SWPPP and coverage under this permit.

A qualified representative will be responsible for conducting inspections for quality control.

Contractor Agreement

Contractor Representative Name

Signature

Title

Date

SWPPP Administration

General Information

Incorporation of Other Plans

The Old Dominion University [Project Title] project incorporates by reference other plans developed for this construction activity. The construction plans comply with current City requirements regarding erosion and sediment control and storm water management and comply with State regulatory requirements as presented in the *Virginia Stormwater Management Handbook, Latest Edition*. All plans incorporated by reference into this SWPPP are enforceable under the Permit. If a plan incorporated by reference does not contain all of the required elements of the SWPPP, the operator must develop the missing elements and include them in the SWPPP.

Plan Availability

In accordance with Part II B of the Permit:

Copies of this SWPPP must be retained on site, or at another location easily accessible during normal business hours, from the date of commencement of construction activity to the date of final stabilization, along with copies of the registration statement, permit, and acknowledgement letter from the permit issuing authority.

Operators with day to day operational control over SWPPP implementation shall have a copy of the SWPPP available at a central location on-site for use by those identified as having responsibilities under the SWPPP. The SWPPP shall be made available to the DEQ, permit-issuing authority, and operator of the municipal separate storm sewer system (MS4) receiving discharges from the site for review at the time of an on-site inspection. If an on-site location is unavailable to store the SWPPP when no personnel are present, a sign must be posted near the main construction entrance indicating the SWPPP's location.

The Operator shall make the SWPPP and all updates available upon request to the DEQ, the permit-issuing authority, EPA, a state or local agency approving erosion and sediment control plans, grading plans, and stormwater management plans, local government officials, or the operator of a MS4 receiving discharges from the construction activity.

A sign must be posted near the main entrance of the construction site containing the following information:

- A copy of the permit coverage letter with the registration number for the construction activity;
- Internet address at which a copy of the SWPPP can be found or the location of the hard copy with a name and telephone number for arranging a viewing of the document during normal business hours.

Plan Updates

The Operator shall amend this SWPPP whenever there is a change in design, construction, operation, or maintenance of the construction site that has a significant effect on the potential for the discharge of pollutants to surface waters and that has not been addressed in the normal implementation of this SWPPP. The Operator must also update this SWPPP as soon as possible when determined necessary or whenever it is found to be ineffective in meeting the requirements of the Permit. The SWPPP shall be updated no later than 7 days following any modification to its implementation, unless approval by a VESCP authority, VSMP authority, or the department is necessary for the implementation of an additional or modified control measure.

If approval is required by the permit-issuing authority, revisions shall be made within 5 business days of approval. Implementation of these additional or modified control measures must be accomplished as described in Permit Part II C.2. Revisions to the SWPPP must be dated and signed in accordance with Permit Section III K.2, but are not required to be certified in accordance with Permit Section III K.4 The SWPPP must clearly identify the contractor(s) or subcontractor(s) that will implement and maintain each measure identified in the SWPPP. The SWPPP shall be revised to identify any new contractor that will implement a measure.

Contractor Responsibilities

The Contractor shall be responsible for executing the conditions of the VSMP Permit as defined in Part III (Appendix B) of the Permit. Specifically, the contractor shall be responsible for maintaining a complete record of monitoring, field reports and investigations, notices of noncompliance, etc.

Specific Requirements

Site Description

The proposed project, [Project Title], is located within [Location] on the Old Dominion University Campus in Norfolk, Virginia. The purpose of the proposed building project is [Purpose and Description of Project] on the Old Dominion University Campus.

The site is bound to the north by [Boundary], to the south by [Boundary], to the west by [Boundary], and to the east by [Boundary]. Adjacent land use is [Adjacent Lane Use].

A site location map is included as Appendix A. Plans showing the proposed scope of work are included in Appendix KJ. The project will disturb approximately [X.XX] acres as shown on plans in Appendix KJ. Existing site cover consists of [Existing Site Cover and Vegetation]. The site is located within the [Lafayette or Elizabeth] watershed, a tributary to the James River watershed, and a tributary to part of the larger Chesapeake Bay watershed. [Description of Site Stormwater]. The site is located in hydrologic unit code JL56.

The proposed site is relatively flat and principally drains through overland flow to site inlets or curb inlets on the adjacent street. The stormwater eventually outfalls into the [Lafayette or Elizabeth] River.

According to Natural Resource Conservation Service Soil Survey Maps, the predominant soil types located in the site area are [Soil Types]. This soil type is classified as [Soil Type Class].

Construction Sequence

[Provide Sequence of Construction]

General Project Phasing

Site development will occur in three overlapping stages:

1. Site Preparation,
2. Construction, and
3. Final grading and Stabilization.

Dates of major grading activities will be recorded on plans included in Appendix K.

Site Preparation Stage

Prior to beginning any construction activities, erosion control measures will be installed as shown on the attached project plans. The contractor shall use existing pavement to access the site, as indicated on the plans included in Appendix K.

The erosion control barriers will be inspected and maintained routinely throughout the duration of the project. Following the installation of erosion and sedimentation controls, the site clearing and grading activities will occur. Safety fence will also be installed around the site perimeter to prevent unwanted access to the site.

Construction Stage

The proposed [Project Title] will be constructed during this phase. Prior to construction of the [Project Title], demolition and disposal of the existing [Site Features] will occur. Immediately after the area has been cleared, construction will begin. General construction activities will consist of [Construction Activities]. Newly constructed and existing storm drain inlets will be protected with inlet protection and/or silt fence. Silt fence will also be placed around any stockpiles created from movement of extracted topsoil. All erosion and sediment control measures for the site will be constructed and maintained in accordance with current Virginia Stormwater Management Handbook. Potential pollutant sources anticipated during construction include [Pollutant Sources].

Final Grading and Stabilization Stage

Final site grading and stabilization will be completed as soon as practicable to minimize exposed soils and potential sources of erosion. Areas to be paved will be covered by bituminous pavement after final subgrades are established. All litter, as well as debris generated by construction activities, will be removed from the site and adjacent undeveloped areas.

Controls and Measures

The Permit requires the use of various types of controls and measures to control pollutants in storm water discharges from the project site. The Permit specifically requires the implementation of erosion and sediment control practices (both structural and non-structural), storm water management practices, and other specific controls to prevent pollutants from being discharged. In general, controls employed in this project were selected to meet and/or exceed State and local requirements and are detailed in the referenced design plans (Appendix K). The design plans for this project contain detailed information regarding various types of controls used in this project. Table 2 summarizes where the detailed information can be found in the design plans:

Table 2: Control Measures – Included in the Design Documents

Type of Control Measure	Plan Sheet No.
Stormwater Management Measures	[Sheet Number]
Stormwater Management Measures Details	[Sheet Number]
Erosion and Sediment Control Notes & Narrative	[Sheet Number]
Erosion and Sediment Control Plan	[Sheet Number]
Erosion and Sediment Control Details	[Sheet Number]

Several requirements of the Permit relating to controls (Part II Appendix B) are not included in the referenced design plans. A description of these required items is presented below, along with how they are addressed in this SWPPP:

- a) In accordance with Part II C.4.a, a record of the dates when major grading activities occur, when construction activities temporarily or permanently cease on a portion of the site, and when stabilization measures are initiated shall be maintained and included in Appendix E of this SWPPP.
- b) In accordance with Part II B.4.e.6, minimize the discharge of pollutants from storage, handling, and disposal of construction products. Materials, and wastes including building products such as roofing materials and concrete mixtures; pesticides, insecticides and fertilizers; and construction and domestic wastes such as packaging materials, scrap construction materials, masonry products, pipe and electrical cuttings and other trash building materials.
- c) Inspections shall be held at least once every four business days or at least once every five business days and no later than 24 hours following a measurable storm event. These inspections shall be conducted by "qualified personnel". The inspection report should encompass the requirements detailed in Part II G.4.
- d) In accordance with Part II B.8, the construction operator shall establish and undertake a method for controlling and documenting construction dewatering discharges by establishing one of the turbidity benchmark options.

In addition, Appendix I includes all Erosion and Sediment Control Measures as detailed in the Virginia Stormwater Management Handbook as well as an additional measure for a concrete washout area. The contractor is responsible for recording all potential pollutants associated with construction activities and must submit the record to the owner for review and approval prior to proceeding with construction activities. This record is included in Appendix H: Water Quality Protection. Minimum Erosion and Sediment Control Measures are indicated on the site plans (Appendix K) and may include but are not limited to the following measures:

- Silt fencing
- Tree protection
- Construction site entrance
- Concrete washout area
- Dust control
- Safety fence
- Straw bales

- Storm Drain inlet protection
- Topsoiling
- Dewatering methods
- Temporary and permanent seeding
- Soil stabilization blanket matting

Soil stabilization shall be applied to denuded areas within 7 days after final grade is reached.

Maintenance

Maintenance of temporary and permanent erosion and sediment control facilities shall be carried out in accordance with the Virginia Erosion and Stormwater Management Regulation (9VAC25-875-560) and Part II B.2 of the Permit (Appendix B). During the period that the project site is under construction, the contractor will be responsible for maintenance of the temporary erosion and sediment control facilities. The site contractor shall inspect the erosion and sediment control facilities on a regular basis, especially after periods of rainfall, and repair any damage immediately. Furthermore, a readily available supply of erosion and sediment control materials will be maintained by the contractor at all times. Detailed descriptions of the maintenance procedures are contained in the project design plans and are incorporated in this SWPPP by reference.

Inspections

The SWPPP Coordinator shall appoint appropriate personnel, who are familiar with all aspects of this SWPPP and the employed control practices, to perform regular inspections of the construction site. Inspections shall include the date and time of inspection and when applicable the date and rainfall amount of the last measurable storm event. Each inspection should record any discharges occurring at time of inspection and any land-disturbing activities that have occurred outside of the approved erosion and sediment control plan. Per Part II G.3, inspections should review of all disturbed areas, structural and non-structural control measures, material storage areas, and vehicular access points. Inspections are to be performed at least once every five business days, or at least once every 10 business days and no later than 24 hours following a measurable storm event. Construction activities that discharge to impaired waters, surface waters with a TMDL approved prior to the term of the Permit, and exceptional waters shall be inspected a minimum of once every 4 business days, or once every 5 business days and no later than 24 hours following a measurable storm event. Areas that already have been stabilized or where runoff is unlikely due to frozen or snow covered ground shall be inspected at least on a monthly basis.

Inspections are intended to identify areas where the pollutant control measures at the site are ineffective and are allowing pollutants to enter surface waters. Receiving waters shall be inspected to ascertain whether control measures are effective in preventing significant impacts. Locations where vehicles enter or exit the site shall be inspected for evidence of offsite sediment tracking.

If as a result of the inspection, the site conditions and/or control measures are found to have changed, this SWPPP shall be updated within a period of 5 calendar days. If control measures need to be modified to assure effectiveness or if additional measures are determined necessary, implementation shall be completed prior to the next anticipated. If implementation prior to the next anticipated measurable storm event is impracticable, then alternative control measures shall be implemented as soon as practicable, but no later than 5 business days after discovery or a longer period as established by the VSMP authority. If adverse weather causes the safety of the inspection personnel to be in jeopardy, the SWPPP inspection may be delayed until the next business day on which it is safe to perform the inspection. Any time inspections are delayed due to adverse weather conditions, evidence of the adverse weather conditions must be included in the SWPPP with the dates of occurrence.

A report summarizing the inspections and the subsequent maintenance activities must be completed and maintained as part of this SWPPP. The inspection report must be added to the SWPPP no later than 4 business days after the inspection is conducted. The inspection forms are included in Appendix F. Required elements include major observations (including information on control measure performance and incidents of non-compliance), and information on the inspecting personnel. If an inspection does not identify any incidents or non-compliance, then the certification statement contained in the inspection form will apply.

[Site Inspector] (phone number: [123-456-7890]), [Site Inspector Title], will be responsible for conducting inspections for quality control.

Spill Prevention and Response Plan

All vehicles and equipment on-site shall be in a well-maintained condition. All vehicles and equipment including subcontractor vehicles will be checked for leaking oil and fluids. Vehicles leaking fluids will not be allowed on-site. Drip pans will be placed under all vehicles and equipment that are parked overnight. Hazardous materials will be stored in accordance with local and federal regulations. Spill kits will be within the materials storage area and concrete washout areas. All spills will be cleaned up immediately upon discovery and a spill report shall be filled out and retained by the Contractor. Spent absorbent materials and rags will be hauled off-site immediately after the spill is cleaned up for disposal. Spills of 25 gallons or more or large enough to discharge to surface water will be reported to Old Dominion University Project Manager, [ODU Project Manager]. Material safety data sheets, a material inventory, and emergency contact information will be maintained at the on-site project trailer.

These spill prevention measures will be implemented once construction begins on-site. All personnel will be instructed, during tailgate training sessions, regarding the correct

procedures for spill prevention and control. Notices that state these practices will be posted in the office trailer, and the individual who manages day-to-day site operations will be responsible for seeing that these procedures are followed.

Concrete Washdown Areas

A designated temporary above-ground concrete washdown area will be constructed at the location depicted on-site. Volume shall be sufficient to contain all liquid and concrete waste generated by washout operations. The washout area shall be lined with plastic sheeting at least 10 mils thick and free of holes and tears. Signs will be posted marking the location of the washout area to ensure that concrete equipment operators use the proper facility.

Concrete pours will not be conducted during or before an anticipated storm event. All excess concrete and concrete washout slurries from the concrete mixer trucks and chutes will be discharged to the washout area or hauled off-site for disposal. When the temporary washout area is no longer needed for the project, the hardened concrete and materials used to construct the concrete washdown areas will be removed and disposed of in accordance with local and federal regulations. Washdown areas shall then be backfilled, graded, and stabilized with erosion control measures.

Portable Bathrooms

Portable bathrooms are to be located away from streets, gutters, waterways, and storm drains. Secondary containment techniques such as dikes, berms, curbing, or other containment methods shall be implemented to prevent spills from spreading and to protect groundwater and down grade storm inlets.

Storage/Staging and Waste Management Areas

Fuel containers are to be double-walled. Staging area for this project is to be located [Staging Area Location] with appropriate erosion and sedimentation control measures for protection along the perimeter. Paints, solvents, pesticides, fuels, oils, other hazardous materials, or building materials that have the potential to contaminate stormwater shall be stored indoors or have a cover provided for them. Secondary containment techniques such as dikes, berms, curbing, or other containment methods should be in place to prevent spills from spreading and to protect groundwater and down grade storm inlets.

Dumpsters shall be located away from streets, gutters, waterways, and storm drains. They should be covered to prevent precipitation from entering container. Liquids are not to

be disposed of in dumpsters. Locations of the proposed dumpsters and liquid disposal areas will be coordinated between the contractor and Old Dominion University personnel and shown on an exhibit. A copy of the exhibit shall be incorporated into the SWPPP.

Non-Storm Water Discharges

All discharges for this Site will be comprised entirely of storm water associated with construction activity. At this time, non-storm water discharges are not part of this project. The contractor shall be responsible for notifying the DEQ of any non-storm water discharges other than those authorized in Part I E. If non-storm water discharges become part of the project, the SWPPP may be updated.

Water Quality Protection

The permittee must select, install, implement and maintain best management practices (BMPs) at the construction site that minimize pollutants in the discharge as necessary to meet applicable water quality standards, as presented in Part I G of the permit (Appendix B).

Post-Construction Stormwater Management Measures

[Stormwater Management Controls and Descriptions]

Offsite Nutrient Credits

[Nutrient Offset Descriptions]

Receiving Waters

The site is located within the *[Lafayette or Elizabeth]* watershed.

[IF LAFAYETTE: The Lafayette River is a tidal body of water included in the 2022 Impaired Waters 303(d) List under cause category 4A for Dissolved Oxygen and Enterococcus. Category 4A indicates that a Total Maximum Daily Load (TMDL) Waste Load Allocation (WLA) has been established for stormwater discharges from a construction activity. In order to ensure that stormwater discharges are in conformance with the TMDL WLA, Virginia Stormwater Management Handbook Minimum Standards (MS-19) shall be adhered to throughout construction.]

[IF ELIZABETH:] : The Elizabeth River is a tidal body of water included in the 2022 Impaired Waters 303(d) List under cause category 4A for Dissolved Oxygen. Category 4A indicates that a Total Maximum Daily Load (TMDL) Waste Load Allocation (WLA) has been established for stormwater discharges from a construction activity. To ensure that

stormwater discharges are in conformance with the TMDL WLA, Virginia Stormwater Management Handbook Minimum Standards (MS-19) Minimum Standards (MS-19) shall be adhered to throughout construction. The Elizabeth River is also listed on the 2022 Impaired Waters 303(d) List under cause category 5A for Estuarine Bioassessments. Category 5A indicates that a WLA has not yet been established for stormwater discharges from a construction activity.]

Contractor Certification

All contractors and/or sub-contractors who have responsibility for implementing and maintaining the controls identified in this SWPPP must sign the certification statement contained in Appendix G. The person signing the certification must meet the signatory requirements, as presented in Permit Part III K (Appendix B). The certifications must be maintained as part of this SWPPP.

References

Virginia Stormwater Management Handbook, latest edition. Virginia Department of Environmental Quality, 2024.

Site Plans titled [Project Title], dated [Date], prepared by [Engineer].

This page intentionally left blank.

Construction Operators' Cooperative Agreement

The cooperative agreement describes stormwater responsibilities for Old Dominion University and its undersigned contractor (Contractor) regarding the [Project Title] project. The construction operators below agree to abide by the following condition throughout the duration of the project, effective the date of signature.

This project is subject to the Virginia Stormwater Management Program (VSMP) General Permit for Storm Water Discharges Associated with Industrial Activity (Permit), as defined in General Permit No. VAR10 Effective Date: July 1, 2024 Expiration Date: June 30, 2029. The goal of this permit is to prevent the discharge of pollutants associated with construction activity from entering the storm drain system or surface waters. [Engineer] has developed a SWPPP for [Project Title] project, and the SWPPP has been reviewed by Old Dominion University (owner/Owner). The SWPPP is available for review at the construction site.

Owner Responsibilities:

- Complete periodic inspections of construction activities
- Be involved with any changes in the SWPPP

Contractor Responsibilities:

- Maintain SWPPP documentation
- Conduct and document inspections on a weekly basis and within 24 hours of the end of a storm event
- Provide copies of the inspection reports to owner within 24 hours of each inspection. Any non-compliances must be immediately reported to owner
- Maintain compliance with applicable section of the SWPPP, including installation of erosion and sediment controls. Any BMP changes that will require a change to the SWPPP must be communicated immediately to owner.
- Maintain erosion and sediment control BMPs in all areas of the site under its day-to-day control.
- (If applicable) Provide adequately designated concrete washout areas throughout the construction project and properly dispose of the concrete, mortar, grout, or other construction materials collected here.

- Maintain the cleanliness of the streets and storm drain inlet protection BMPs throughout the construction project. Sweep streets as needed, especially before rain events. Inspect and replace storm drain inlet protection BMPs as necessary.
- Follow Old Dominion University criteria for the storage of chemicals.
 - All chemicals must be stored on contaminant pads, which must be inspected weekly and approved by Old Dominion University personnel.
- Maintain a clean site. Trash and debris must be picked up and properly disposed of daily.
- Each operator is responsible for advising employees and subcontractors working on this project of the requirements of the SWPPP. Emphasis will be placed on ensuring employees and subcontractors do not damage BMPs and do not introduce pollutants into the storm drain system. All personnel working on-site should have stormwater training.

Agreement

The undersigned agree to abide by the terms and conditions of this cooperative agreement as described above.

Owner

Operator Name

Signature

Title

Date

Contractor

Operator Name

Signature

Title

Date

Delegation of Authority

In accordance with the General VPDES Permit for Discharges of Stormwater from Construction Activities, the individuals or positions with delegated authority to sign inspection reports and/or amend this SWPPP must be identified. If the individual or position identified on the Title Sheet of the SWPPP changes or additional individuals or positions are given this responsibility after the preconstruction meeting occurs, the changes/additions must be noted below.

Delegation of Authority

I, _____ (name), hereby designate the person or specifically described position below to be a duly authorized representative for the purpose of overseeing compliance with environmental requirements, including the VPDES "General Permit for Storm Water Discharges Associated with Construction Activity" (General Permit), at the

[*Project Site*] construction site.

Owner Signature: _____

Name of Operator: _____

Company: _____

Phone Number: _____

Owner Certification

"I certify under the penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Company: _____

Address: _____

Phone: _____

Name: _____
Printed Title

Signature: _____

Date: _____

Appendix A

Site Location Map

Appendix B

Stormwater General Permit



Commonwealth of Virginia

VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY

www.deq.virginia.gov

General Permit No.: VAR10

Effective Date: July 1, 2024

Expiration Date: June 30, 2029

**GENERAL VPDES PERMIT FOR DISCHARGES OF STORMWATER FROM
CONSTRUCTION ACTIVITIES**

**AUTHORIZATION TO DISCHARGE UNDER THE VIRGINIA EROSION AND
STORMWATER MANAGEMENT PROGRAM AND THE VIRGINIA EROSION AND
STORMWATER MANAGEMENT ACT**

In compliance with the provisions of the Clean Water Act, as amended, and pursuant to the Virginia Erosion and Stormwater Management Act and regulations adopted pursuant thereto, operators of construction activities are authorized to discharge to surface waters within the boundaries of the Commonwealth of Virginia, except those specifically named in State Water Control Board regulations that prohibit such discharges.

The authorized discharge shall be in accordance with the registration statement filed with the Department of Environmental Quality, this cover page, Part I - Discharge Authorization and Special Conditions, Part II - Stormwater Pollution Prevention Plan, and Part III - Conditions Applicable to All VPDES Permits as set forth in this general permit.

For stormwater discharge associated with a small construction activity of a single-family detached residential structure, within or outside a common plan of development or sale, the authorized discharge shall be in accordance with this cover page, Part I - Discharge Authorization and Special Conditions, Part II - Stormwater Pollution Prevention Plan, and Part III - Conditions Applicable to All VPDES Permits as set forth in this general permit.

PART I

DISCHARGE AUTHORIZATION AND SPECIAL CONDITIONS

A. Coverage under this general permit.

1. During the period beginning with the date of coverage under this general permit and lasting until the general permit's expiration date, the operator is authorized to discharge stormwater from construction activities.
2. This general permit also authorizes stormwater discharges from construction support activities located on-site or off-site provided that:
 - a. The support activity is directly related to the construction site that is required to have general permit coverage for discharges;
 - b. The support activity is neither a commercial operation nor serves multiple unrelated construction sites;
 - c. The support activity does not operate beyond the completion of the last construction activity it supports;
 - d. The support activity is identified in the registration statement at the time of general permit coverage or reported in a modified registration statement once the need for the support activity is known;
 - e. Appropriate control measures are identified in a stormwater pollution prevention plan and implemented to address the discharges from the support activity; and
 - f. All applicable state, federal, and local approvals are obtained for the support activity.

B. Limitations on coverage.

1. Post-construction discharges. This general permit does not authorize stormwater discharges that originate from the construction site after construction activities have been completed and the construction site, including any construction support activity covered under the general permit registration, has undergone final stabilization. Post-construction industrial stormwater discharges may need to be covered by a separate VPDES permit.
2. Discharges mixed with nonstormwater. This general permit does not authorize discharges that are mixed with sources of nonstormwater, other than those discharges that are identified in Part I E (Authorized nonstormwater discharges) and are in compliance with this general permit.
3. Discharges covered by another permit. This general permit does not authorize discharges of stormwater from construction activities that are covered under an individual permit or required to obtain coverage under an alternative general permit.

4. Impaired waters and total maximum daily load (TMDL) limitation.

a. Nutrient and sediment impaired waters. Discharges of stormwater from construction activities to surface waters identified as impaired in the 2022 § 305(b)/303(d) Water Quality Assessment Integrated Report for Benthic Macroinvertebrates Bioassessments or for which a TMDL wasteload allocation has been established and approved prior to the term of this general permit for (i) sediment or a sediment-related parameter (i.e., total suspended solids or turbidity) or (ii) nutrients (i.e., nitrogen or phosphorus), including all surface waters within the Chesapeake Bay Watershed, are not eligible for coverage under this general permit unless the operator develops, implements, and maintains a stormwater pollution prevention plan (SWPPP) in accordance with Part II B 5 of this permit that minimizes the pollutants of concern and, when applicable, is consistent with the assumptions and requirements of the approved TMDL wasteload allocations and implements an inspection frequency consistent with Part II G 2 a.

b. Polychlorinated biphenyl (PCB) impaired waters. Discharges of stormwater from construction activities that include the demolition of any structure with at least 10,000 square feet of floor space built or renovated before January 1, 1980, to surface waters identified as impaired in the 2022 § 305(b)/303(d) Water Quality Assessment Integrated Report or for which a TMDL wasteload allocation has been established and approved prior to the term of this general permit for PCB are not eligible for coverage under this general permit unless the operator develops, implements, and maintains a SWPPP in accordance with Part II B 6 of this permit that minimizes the pollutants of concern and, when applicable, is consistent with the assumptions and requirements of the approved TMDL wasteload allocations and implements an inspection frequency consistent with Part II G 2 a.

5. Exceptional waters limitation. Discharges of stormwater from construction activities not previously covered under the general permit effective on July 1, 2019, to exceptional waters identified in 9VAC25-260-30 A 3 c are not eligible for coverage under this general permit unless the operator develops, implements, and maintains a SWPPP in accordance with Part II B 7 of this permit and implements an inspection frequency consistent with Part II G 2 a.

6. There shall be no discharge of floating solids or visible foam in other than trace amounts.

C. Commingled discharges. Discharges authorized by this general permit may be commingled with other sources of stormwater that are not required to be covered under a permit, so long as the commingled discharge is in compliance with this general permit. Discharges authorized by a separate state or VPDES permit may be commingled with discharges authorized by this general permit so long as all such discharges comply with all applicable state and VPDES permit requirements.

D. Prohibition of nonstormwater discharges. Except as provided in Part I A 2, C, and E, all discharges covered by this general permit shall be composed entirely of stormwater associated with construction activities. All other discharges, including the following, are prohibited:

1. Wastewater from washout of concrete;

2. Wastewater from the washout or cleanout of stucco, paint, form release oils, curing compounds, and other construction materials;
3. Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance;
4. Oils, toxic substances, or hazardous substances from spills or other releases; and
5. Soaps, solvents, or detergents used in equipment and vehicle washing.

E. Authorized nonstormwater discharges. The following nonstormwater discharges from construction activities are authorized by this general permit:

1. Discharges from emergency firefighting activities;
2. Fire hydrant flushings, managed to avoid an instream impact;
3. Waters used to wash vehicles or equipment, provided no soaps, solvents, or detergents are used and the wash water is filtered, settled, or similarly treated prior to discharge;
4. Water used to control dust that is filtered, settled, or similarly treated prior to discharge;
5. Potable water, including uncontaminated waterline flushings, managed in a manner to avoid an instream impact;
6. Routine external building wash down provided no soaps, solvents or detergents are used, external building surfaces do not contain hazardous substances, and the wash water is filtered, settled, or similarly treated prior to discharge;
7. Pavement wash waters, provided spills or leaks of toxic or hazardous materials have not occurred, unless all spilled or leaked material has been removed prior to washing; soaps, solvents, or detergents are not used; and where the wash water is filtered, settled, or similarly treated prior to discharge;
8. Uncontaminated air conditioning or compressor condensate;
9. Uncontaminated ground water or spring water;
10. Foundation or footing drains, provided flows are not contaminated with process materials such as solvents or contaminated groundwater;
11. Uncontaminated excavation dewatering, including dewatering of trenches and excavations that are filtered, settled, or similarly treated prior to discharge; and
12. Landscape irrigation.

F. Termination of general permit coverage.

1. The operator of the construction activity shall submit a notice of termination in accordance with 9VAC25-880-60, unless a registration statement was not required to be

submitted in accordance with 9VAC25-880-50 A 1 c or A 2 b for single-family detached residential structures, to the Virginia Erosion and Stormwater Management (VESMP) authority after one or more of the following conditions have been met:

- a. Necessary permanent control measures included in the SWPPP for the construction site are in place and functioning effectively and final stabilization has been achieved on all portions of the construction site for which the operator has operational control. When applicable, long-term responsibility and maintenance requirements for permanent control measures shall be recorded in the local land records prior to the submission of a complete and accurate notice of termination and the construction record drawing prepared;
 - b. Another operator has assumed control over all areas of the construction site that have not been finally stabilized and obtained coverage for the ongoing discharge;
 - c. Coverage under an alternative VPDES permit or other applicable permit has been obtained; or
 - d. For individual lots in residential construction only, final stabilization as defined in 9VAC25-880-1 has been completed, including providing written notification to the homeowner and incorporating a copy of the notification and signed certification statement into the SWPPP, and the residence has been transferred to the homeowner.
2. The notice of termination shall be submitted no later than 30 days after one of the conditions in subdivision 1 of this subsection is met.
3. Termination of authorization to discharge shall be effective upon notification from the department that the provisions of subdivision 1 of this subsection have been met or 90 days after submittal of a complete and accurate notice of termination in accordance with 9VAC25-880-60 C, whichever occurs first, unless otherwise notified by the VESMP or the department.
4. The notice of termination shall be signed in accordance with Part III K 1 and include the required certification in accordance with Part III K 4 of this general permit.

G. Water quality protection.

1. The operator shall select, install, implement, and maintain control measures as identified in the SWPPP at the construction site that minimize pollutants in the discharge as necessary to ensure that the operator's discharge does not cause or contribute to an excursion above any applicable water quality standard.
2. If it is determined by the department that the operator's discharges are causing, have reasonable potential to cause, or are contributing to an excursion above any applicable water quality standard, the department, in consultation with the VESMP authority, may take appropriate enforcement action and require the operator to:
 - a. Modify or implement additional control measures in accordance with Part II C to adequately address the identified water quality concerns;

b. Submit valid and verifiable data and information that are representative of ambient conditions and indicate that the receiving water is attaining water quality standards; or

c. Submit an individual permit application in accordance with 9VAC25-875-980 B 3.

H. All written responses required under this general permit shall include a signed certification consistent with Part III K.

PART II

STORMWATER POLLUTION PREVENTION PLAN

A. Stormwater pollution prevention plan.

1. A stormwater pollution prevention plan (SWPPP) shall be developed prior to the submission of a registration statement and implemented for the construction activity, including any construction support activity, covered by this general permit. For a small construction activity of a single-family detached residential structure, within or outside a common plan of development or sale, a SWPPP shall be developed and implemented prior to the initiation of the construction activity, including any construction support activity covered by this general permit.

2. SWPPPs shall be prepared in accordance with good engineering practices. Construction activities that are part of a larger common plan of development or sale and disturb less than one acre may utilize a SWPPP template provided by the department and need not provide a separate stormwater management plan if one has been prepared and implemented for the larger common plan of development or sale.

3. The SWPPP requirements of this general permit may be fulfilled by incorporating by reference other plans such as a spill prevention control and countermeasure (SPCC) plan developed for the construction site under § 311 of the federal Clean Water Act or best management practices (BMP) programs otherwise required for the construction site provided that the incorporated plan meets or exceeds the SWPPP requirements of Part II B. All plans incorporated by reference into the SWPPP become enforceable under this general permit. If a plan incorporated by reference does not contain all of the required elements of the SWPPP, the operator shall develop the missing elements and include them in the SWPPP.

4. Any operator that was authorized to discharge under the general permit effective July 1, 2019, and that intends to continue coverage under this general permit shall update its stormwater pollution prevention plan to comply with the requirements of this general permit no later than 60 days after the date of coverage under this general permit.

B. Contents. The SWPPP shall include the following items:

1. General information.

a. A signed copy of the registration statement, if required, for coverage under this general permit;

- b. Upon receipt, a copy of the notice of coverage under this general permit (i.e., notice of coverage letter);
 - c. Upon receipt, a copy of the general VPDES permit for discharges of stormwater from construction activities;
 - d. A narrative description of the nature of the construction activity, including the function of the project (e.g., low density residential, shopping mall, highway);
 - e. A legible map of the construction site identifying:
 - (1) Existing and proposed drainage patterns on the construction site and approximate slopes before and after major grading activities;
 - (2) Limits of clearing and grading (i.e., land disturbance), including steep slopes and natural buffers around surface waters that will remain undisturbed;
 - (3) Locations of major structural and nonstructural control measures, including sediment basins and traps, perimeter dikes and diversions, sediment barriers, and other measures intended to filter, settle, or similarly treat sediment that will be installed between disturbed areas and the undisturbed vegetated areas in order to increase sediment removal and maximize stormwater infiltration;
 - (4) Locations of surface waters;
 - (5) Locations where concentrated stormwater is discharged;
 - (6) Locations of any construction support activities, including (i) areas where equipment and vehicle washing, wheel wash water, and other wash water is to occur; (ii) storage areas for chemicals such as acids, fuels, fertilizers, and other lawn care chemicals; (iii) concrete wash out areas; (iv) vehicle fueling and maintenance areas; (v) sanitary waste facilities, including those temporarily placed on the construction site; (vi) construction waste storage; and (vii) areas where polymers, flocculants, or other stormwater treatment chemicals will be used or stored; and
 - (7) When applicable, the location of the on-site rain gauge or the methodology established in consultation with the VESMP authority used to identify measurable storm events for inspection as allowed by Part II G 2 a (1) (ii) or 2 b (2).
2. Erosion and sediment control plan for the construction activity authorized by this general permit.
- a. An erosion and sediment control plan designed and approved in accordance with the Virginia Erosion and Stormwater Management Regulations (9VAC25-875), an "agreement in lieu of a plan" as defined in 9VAC25-875-20, or an erosion and sediment control plan prepared in accordance with department-approved standards and specifications.

b. All erosion and sediment control plans shall include a statement describing the maintenance responsibilities required for the erosion and sediment controls used.

c. An approved erosion and sediment control plan, "agreement in lieu of a plan," or erosion and sediment control plan prepared in accordance with department-approved standards and specifications shall be implemented to:

(1) Control the volume and velocity of stormwater runoff within the construction site to minimize soil erosion;

(2) Control stormwater discharges, including peak flow rates and total stormwater volume, to minimize erosion at outlets and to minimize downstream channel and stream bank erosion;

(3) Minimize the amount of soil exposed during the construction activity;

(4) Minimize the disturbance of steep slopes;

(5) Minimize sediment discharges from the construction site in a manner that addresses (i) the amount, frequency, intensity, and duration of precipitation; (ii) the nature of resulting stormwater runoff; and (iii) soil characteristics, including the range of soil particle sizes present on the construction site;

(6) Provide and maintain natural buffers around surface waters, direct stormwater to vegetated areas to increase sediment removal, and maximize stormwater infiltration, unless infiltration would be inadvisable due to the underlying geology (e.g., karst topography) and groundwater contamination concerns or infeasible due to site conditions;

(7) Minimize soil compaction. Minimizing soil compaction is not required where the intended function of a specific area of the construction site dictates that it be compacted;

(8) Unless infeasible, preserve topsoil. Preserving topsoil is not required where the intended function of a specific area of the construction site dictates that the topsoil be disturbed or removed;

(9) Ensure the initiation of stabilization activities of disturbed areas occurs immediately whenever any clearing, grading, excavating, or other land-disturbing activities have permanently ceased on any portion of the construction site, or temporarily ceased on any portion of the construction site and will not resume for a period exceeding 14 days; and

(10) Utilize outlet structures that withdraw stormwater from the surface (i.e., above the permanent pool or wet storage water surface elevation), unless infeasible, when discharging from sediment basins or sediment traps.

3. Stormwater management plan for the construction activity authorized by this general permit.

- a. Except for those projects identified in Part II B 3 b, a stormwater management plan approved in accordance with the Virginia Erosion and Stormwater Management Regulation (9VAC25-875) or an "agreement in lieu of a plan" as defined in 9VAC25-875-20 or a stormwater management plan prepared in accordance with department-approved standards and specifications.
 - b. For any operator meeting the conditions of 9VAC25-875-480 B of the Virginia Erosion and Stormwater Management Regulation, an approved stormwater management plan is not required. In lieu of an approved stormwater management plan, the SWPPP shall include a description of and all necessary calculations supporting all post-construction stormwater management measures that will be installed prior to the completion of the construction process to control pollutants in stormwater discharges after construction operations have been completed. Structural measures should be placed on upland soils to the degree possible. Such measures must be designed and installed in accordance with applicable VESCP authority, VESMP authority, state, and federal requirements, and any necessary permits must be obtained.
4. Pollution prevention plan for the construction activity authorized by this general permit. A pollution prevention plan that addresses potential pollutant-generating activities that may reasonably be expected to affect the quality of stormwater discharges from the construction activity, including any support activity. The pollution prevention plan shall:
- a. Identify the potential pollutant-generating activities and the pollutant that is expected to be exposed to stormwater;
 - b. Describe the location where the potential pollutant-generating activities will occur, or if identified on the site plan, reference the site plan;
 - c. Identify all nonstormwater discharges, as authorized in Part I E of this general permit, that are or will be commingled with stormwater discharges from the construction activity, including any applicable support activity;
 - d. Identify the person responsible for implementing the pollution prevention practices for each pollutant-generating activity (if other than the person listed as the qualified personnel);
 - e. Describe the pollution prevention practices and procedures that will be implemented to:
 - (1) Prevent and respond to leaks, spills, and other releases, including (i) procedures for expeditiously stopping, containing, and cleaning up spills, leaks, and other releases; and (ii) procedures for reporting leaks, spills, and other releases in accordance with Part III G;
 - (2) Prevent the discharge of spilled and leaked fuels and chemicals from vehicle fueling and maintenance activities (e.g., providing secondary containment such as spill berms, decks, spill containment pallets, providing cover where appropriate, and having spill kits readily available);

(3) Prevent the discharge of soaps, solvents, detergents, and wash water from construction materials, including the clean-up of stucco, paint, form release oils, and curing compounds (e.g., providing (i) cover (e.g., plastic sheeting or temporary roofs) to prevent contact with stormwater; (ii) collection and proper disposal in a manner to prevent contact with stormwater; and (iii) a similarly effective means designed to prevent discharge of these pollutants);

(4) Minimize the discharge of pollutants from vehicle and equipment washing, wheel wash water, and other types of washing (e.g., locating activities away from surface waters and storm drain inlets and constructed or natural site drainage features and directing wash waters to sediment basins or traps, using filtration devices such as filter bags or sand filters, or using similarly effective controls);

(5) Direct concrete wash water into a leak-proof container or leak-proof settling basin designed so that no overflows can occur due to inadequate sizing or precipitation. Hardened concrete wastes shall be removed and disposed of in a manner consistent with the handling of other construction wastes. Liquid concrete wastes shall be removed and disposed of in a manner consistent with the handling of other construction wash waters and shall not be discharged to surface waters, disposed of through infiltration, or otherwise disposed of on the ground;

(6) Minimize the discharge of pollutants from storage, handling, and disposal of construction products, materials, and wastes, including (i) building products such as asphalt sealants, copper flashing, roofing materials, adhesives, and concrete admixtures; (ii) pesticides, herbicides, insecticides, fertilizers, and landscape materials; and (iii) construction and domestic wastes such as packaging materials, scrap construction materials, masonry products, timber, pipe and electrical cuttings, plastics, Styrofoam, concrete, and other trash or building materials;

(7) Prevent the discharge of fuels, oils, and other petroleum products, hazardous or toxic wastes, waste concrete, and sanitary wastes;

(8) Address any other discharge from the potential pollutant-generating activities not addressed in this subdivision 4; and

(9) Minimize the exposure of waste materials to precipitation by closing or covering waste containers during precipitation events and at the end of the business day or implementing other similarly effective practices. Minimization of exposure is not required in cases where the exposure to precipitation will not result in a discharge of pollutants; and

f. Describe procedures for providing pollution prevention awareness of all applicable wastes, including any wash water, disposal practices, and applicable disposal locations of such wastes, to personnel in order to comply with the conditions of this general permit. The operator shall implement the procedures described in the SWPPP.

5. SWPPP requirements for discharges to nutrient and sediment impaired waters. For discharges to surface waters (i) identified as impaired in the 2022 § 305(b)/303(d) Water Quality Assessment Integrated Report for Benthic Macroinvertebrates Bioassessments or (ii) with an applicable TMDL wasteload allocation established and approved prior to the

term of this general permit for sediment or a sediment-related parameter (i.e., total suspended solids or turbidity) or nutrients (i.e., nitrogen or phosphorus), including all surface waters within the Chesapeake Bay Watershed, the operator shall:

a. Identify the impaired waters, approved TMDLs, and pollutants of concern in the SWPPP; and

b. Provide documentation in the SWPPP that:

(1) Permanent or temporary soil stabilization shall be applied to denuded areas within seven days after final grade is reached on any portion of the construction site;

(2) Nutrients shall be applied in accordance with manufacturer's recommendations or an approved nutrient management plan and shall not be applied during rainfall events; and

(3) A modified inspection schedule shall be implemented in accordance with Part II G 2 a.

6. SWPPP requirements for discharges to polychlorinated biphenyl (PCB) impaired waters. For discharges from construction activities that include the demolition of any structure with at least 10,000 square feet of floor space built or renovated before January 1, 1980, to surface waters (i) identified as impaired in the 2022 § 305(b)/303(d) Water Quality Assessment Integrated Report or (ii) with an applicable TMDL wasteload allocation established and approved prior to the term of this general permit for PCB, the operator shall:

a. Identify the impaired waters, approved TMDLs, and pollutant of concern in the SWPPP;

b. Implement the approved erosion and sediment control plan in accordance with Part II B 2;

c. Dispose of waste materials in compliance with applicable state, federal, and local requirements; and

d. Implement a modified inspection schedule in accordance with Part II G 2 a.

7. SWPPP requirements for discharges to exceptional waters. For discharges to surface waters identified in 9VAC25-260-30 A 3 c as an exceptional water, the operator shall:

a. Identify the exceptional surface waters in the SWPPP; and

b. Provide documentation in the SWPPP that:

(1) Permanent or temporary soil stabilization shall be applied to denuded areas within seven days after final grade is reached on any portion of the construction site;

(2) Nutrients shall be applied in accordance with manufacturer's recommendations or an approved nutrient management plan and shall not be applied during rainfall events; and

(3) A modified inspection schedule shall be implemented in accordance with Part II G 2 a.

8. SWPPP requirements for construction dewatering discharges to sediment impaired waters or exceptional waters. Dewatering discharges of uncontaminated stormwater or groundwater from footers or foundations of a single-family detached residential structure are exempt from the requirements of this subdivision 8, provided that such discharges are not discharged directly to surface waters. For construction dewatering discharges to surface waters (i) identified as impaired in the 2022 § 305(b)/303(d) Water Quality Assessment Integrated Report for Benthic Macroinvertebrates Bioassessments; (ii) with an applicable TMDL wasteload allocation established and approved prior to the term of this general permit for sediment or a sediment-related parameter (i.e., total suspended solids or turbidity), including all surface waters within the Chesapeake Bay Watershed; or (iii) identified in 9VAC25-260-30 A 3 c as an exceptional water, the operator shall undertake one of the following methods for controlling and documenting construction dewatering discharges:

a. Turbidity benchmark option 1:

(1) Identify the location of all construction dewatering discharges in the SWPPP;

(2) Select, install, implement, and maintain control measures at each dewatering location that minimize pollutants, including suspended solids, in construction dewatering discharges prior to discharging into a stormwater conveyance system or surface water; and

(3) Provide documentation in the SWPPP that:

(a) Sample frequency. At least one grab sample shall be collected from each construction dewatering discharge when the first discharge at that location occurs, daily thereafter until the dewatering discharge stops, and after any installation of new controls or routine maintenance activity of existing controls. An upstream grab sample shall be collected from the receiving stream;

(b) Sample timing. Grab samples of the construction dewatering discharge shall be collected during the first 15 minutes of the construction dewatering discharge and daily thereafter until the dewatering discharge stops. Upstream grab samples of the receiving stream shall be collected within 15 minutes of the corresponding construction dewatering discharge sample;

(c) Sample location. Grab samples shall be collected after the construction dewatering water has been filtered, settled, or similarly treated and prior to its discharge into a stormwater conveyance system or surface water;

(d) Test methods. Grab samples taken as required by this subdivision 8 shall be measured using a turbidity meter that reports results in nephelometric

turbidity units (NTUs) or formazin turbidity units (FTUs), and a turbidity meter calibration verification shall be conducted prior to each day's use, consistent with manufacturer recommendations;

(e) Visual monitoring. All dewatering discharges shall be visually monitored for changes in the characterization of effluent discharge;

(f) Corrective action. If (i) any turbidity measurement of the construction dewatering discharge exceeds the upstream grab sample of the receiving stream by more than 50 NTUs/FTUs or (ii) visual monitoring indicates a change in the characterization of effluent discharge, corrective action shall be taken in accordance with Part II H 2 of this general permit; and

(g) Recordkeeping. Turbidity monitoring information (i.e., location, date, sample collection time, and turbidity measurement) and any necessary corrective actions taken shall be recorded in the SWPPP; or

b. Turbidity benchmark option 2:

(1) Identify the location of all construction dewatering discharges in the SWPPP;

(2) Select, install, implement, and maintain control measures at each dewatering location that minimize pollutants, including suspended solids, in construction dewatering discharges prior to discharging into a stormwater conveyance system or surface water; and

(3) Provide documentation in the SWPPP that:

(a) Sample frequency. At least one grab sample shall be collected from each construction dewatering discharge when the first discharge at that location occurs, daily thereafter until the dewatering discharge stops, and after any installation of new controls or routine maintenance activity of existing controls. Grab samples shall be tested to confirm a turbidity measurement of equal to or less than 150 NTUs/FTUs from the construction dewatering discharge;

(b) Sample timing. Grab samples of the construction dewatering discharge shall be collected during the first 15 minutes of the construction dewatering discharge and daily thereafter until the dewatering discharge stops;

(c) Sample location. Grab samples shall be collected after the construction dewatering water has been filtered, settled, or similarly treated and prior to its discharge into a stormwater conveyance system or surface water;

(d) Test methods. Grab samples taken as required by this subdivision 8 shall be measured using a turbidity meter that reports results in nephelometric turbidity units (NTUs) or formazin turbidity unit (FTUs), and a turbidity meter calibration verification shall be conducted prior to each day's use, consistent with manufacturer recommendations;

(e) Visual monitoring. All dewatering discharges shall be visually monitored for changes in the characterization of effluent discharge;

(f) Corrective action. If (i) any turbidity measurement of the construction dewatering discharge exceeds 150 NTUs/FTUs or (ii) visual monitoring indicates a change in the characterization of effluent discharge, corrective action shall be taken in accordance with Part II H 2 of this general permit; and

(g) Recordkeeping. Turbidity monitoring information (i.e., location, date, sample collection time, and turbidity measurement) and any necessary corrective actions taken shall be recorded in the SWPPP ; or

c. Turbidity benchmark option 3:

(1) Identify the location of all construction dewatering discharges in the SWPPP;

(2) Select, install, implement, and maintain control measures at each dewatering location that minimize pollutants, including suspended solids, in construction dewatering discharges prior to discharging into a stormwater conveyance system or surface water; and

(3) Provide documentation in the SWPPP that:

(a) Sample frequency. At least one grab sample shall be collected from each construction dewatering discharge when the first discharge at that location occurs, daily thereafter until the dewatering discharge stops, and after any installation of new controls or routine maintenance activity of existing controls. Grab samples shall be tested to confirm a turbidity measurement of equal to or less than 50 NTUs/FTUs, based on a weekly average, from the construction dewatering discharge;

(b) Sample timing. Grab samples of the construction dewatering discharge shall be collected during the first 15 minutes of the construction dewatering discharge and daily thereafter until the dewatering discharge stops;

(c) Sample location. Grab samples shall be collected after the construction dewatering water has been filtered, settled, or similarly treated and prior to its discharge into a stormwater conveyance system or surface water;

(d) Test methods. Grab samples taken as required by this subdivision 8 shall be measured using a turbidity meter that reports results in NTUs or FTUs, and a turbidity meter calibration verification shall be conducted prior to each day's use, consistent with manufacturer recommendations;

(e) Visual monitoring. All dewatering discharges shall be visually monitored for changes in the characterization of effluent discharge;

(f) Corrective action. If (i) the weekly average of the turbidity measurements of the construction dewatering discharge exceeds 50 NTUs/FTUs or (ii) visual monitoring indicates a change in the characterization of effluent discharge,

corrective action shall be taken in accordance with Part II H 2. The weekly average is the sum of all turbidity samples taken during a monitoring week (starting on Monday and ending on Sunday) divided by the number of samples measures during that week; and

(g) Recordkeeping. Turbidity monitoring information (i.e., location, date, sample collection time, and turbidity measurement) and any necessary corrective actions taken shall be recorded in the SWPPP.

d. Request for alternative benchmark threshold:

(1) At any time prior to or during coverage under this permit, a request may be submitted to the department to approve a benchmark that is higher than turbidity benchmark options 1, 2, and 3 if information is available demonstrating the higher number is the same as the receiving water's water quality standard for turbidity. To request approval of an alternate benchmark, the operator must submit the following to the department:

(a) The current turbidity water quality standard that applies to the receiving water; and

(b) Information on the natural or background turbidity level to determine the specific standard for the receiving water, including available data that can be used to establish the natural turbidity levels of the receiving water.

(2) The department will notify the operator of its decision on whether to approve the requested alternate benchmark within 30 days. Until the department approves an alternate benchmark, the operator is required to use the option 1, option 2, or option 3 turbidity benchmark and take any required corrective actions if an exceedance occurs.

9. Identification of qualified personnel. The name, telephone number, and qualifications of the qualified personnel conducting inspections required by this general permit.

10. Duly authorized representatives. The SWPPP shall include the names of individuals or positions duly authorized to sign inspection reports or modify the SWPPP on behalf of the operator. Any authorization shall be signed and dated in accordance with Part III K 2 and shall include the required certification in accordance with Part III K 4.

11. SWPPP signature and certification. The SWPPP shall be signed and dated in accordance with Part III K 2 of this general permit and shall include the required certification in accordance with Part III K 4 of this general permit.

C. SWPPP amendments, modification, and updates.

1. The operator shall amend the SWPPP whenever there is a change in the design, construction, operation, or maintenance that has a significant effect on the discharge of pollutants to surface waters and that has not been previously addressed in the SWPPP.

2. The SWPPP shall be amended if during inspections or investigations by the operator's qualified personnel or by local, state, or federal officials, it is determined that the existing control measures are ineffective in minimizing pollutants in discharges from the construction activity. Revisions to the SWPPP shall include additional or modified control measures designed and implemented to correct problems identified. If approval by the VESCP authority, VESMP authority, or department is necessary for the control measure, revisions to the SWPPP shall be completed no later than five business days following approval. Implementation of these additional or modified control measures shall be accomplished as described in Part II H.

3. The SWPPP shall clearly identify the contractors that will implement and maintain each control measure identified in the SWPPP. The SWPPP shall be amended to identify any new contractor that will implement and maintain a control measure.

4. The operator shall update the SWPPP as soon as possible but no later than five business days following any modification to its implementation. All modifications or updates to the SWPPP shall be noted and shall include the following items:

a. A record of dates when:

(1) Major grading activities occur;

(2) Construction activities temporarily or permanently cease on a portion of the construction site; and

(3) Stabilization measures are initiated;

b. Documentation of replaced or modified controls where periodic inspections or other information have indicated that the controls have been used inappropriately or incorrectly and were modified;

c. Areas that have reached final stabilization and where no further SWPPP or inspection requirements apply;

d. All properties that are no longer under the legal control of the operator and the dates on which the operator no longer had legal control over each property;

e. The date of any prohibited discharges, the discharge volume released, and what actions were taken to minimize the impact of the release;

f. Measures taken to prevent the reoccurrence of any prohibited discharge; and

g. Measures taken to address any evidence identified as a result of an inspection required under Part II G.

5. Amendments, modifications, or updates to the SWPPP shall be signed in accordance with Part III K 2 and shall include the required certification in accordance with Part III K 4.

D. Public notification. Upon commencement of construction activities, the operator shall post a copy of the notice of coverage letter at a publicly accessible location near the main entrance of

the construction site. For linear projects, the operator shall post a copy of the notice of coverage letter at a publicly accessible location near an active part of the construction site (e.g., where a pipeline crosses a public road). The copy of the notice of coverage letter shall be visible such that it can be readily viewed from a public right-of-way. The operator shall maintain the posted information until termination of general permit coverage as specified in Part I F.

E. SWPPP availability.

1. Operators with day-to-day operational control over SWPPP implementation shall have a copy of the SWPPP available at a central location on-site for use by those identified as having responsibilities under the SWPPP whenever they are on the construction site.
2. The operator shall make the SWPPP and all amendments, modifications, and updates available upon request to the department, the VESMP authority, the EPA, the VESCP authority, local government officials, or the operator of a municipal separate storm sewer system receiving discharges from the construction activity. If an on-site location is unavailable to store the SWPPP when no personnel are present, notice of the SWPPP's location shall be posted near the main entrance of the construction site.
3. The operator shall make the SWPPP available for public review in an electronic format or in hard copy. Information for public access to the SWPPP shall be posted and maintained in accordance with Part II D. If not provided electronically, public access to the SWPPP may be arranged upon request at a time and at a publicly accessible location convenient to the operator or the operator's designee but shall be no less than once per month and shall be during normal business hours. Information not required to be contained within the SWPPP by this general permit is not required to be released.

F. SWPPP implementation. The operator shall implement the SWPPP and subsequent amendments, modifications, and updates from commencement of land disturbance until termination of general permit coverage as specified in Part I F.

1. All control measures shall be properly maintained in effective operating condition in accordance with good engineering practices and, where applicable, manufacturer specifications.
2. If a site inspection required by Part II G identifies a control measure that is not operating effectively or needs routine maintenance, corrective actions or routine maintenance shall be completed as soon as practicable, but no later than five business days after discovery or a longer period as established by the VESMP authority, to maintain the continued effectiveness of the control measures.
3. If the operator must make the same repairs more than two times to the same control at the same location, even if the fix can be completed by the close of the next business day, the operator shall either:
 - a. Complete work to fix any subsequent repeat occurrences of this same problem under the corrective action procedures in Part II H, including keeping any records of the condition and how it was corrected under Part II C; or

- b. Document in the inspection report under Part II G why the specific reoccurrence of this same problem should still be addressed as a routine maintenance fix.
4. If site inspections required by Part II G identify an existing control measure that needs to be modified or if an additional or alternative control measure is necessary for any reason, implementation shall be completed prior to the next anticipated measurable storm event. If implementation prior to the next anticipated measurable storm event is impracticable, then additional or alternative control measures shall be implemented as soon as practicable, but no later than five business days after discovery or a longer period as established by the VESMP authority.

G. SWPPP Inspections.

- 1. Personnel responsible for on-site and off-site inspections. Inspections required by this general permit shall be conducted by the qualified personnel identified by the operator in the SWPPP. The operator is responsible for ensuring that the qualified personnel conduct the inspection. Qualified personnel may be a person on the operator's staff or a third party hired to conduct such inspections.
- 2. Inspection schedule.
 - a. For construction activities that discharge to a surface water identified in Part II B 5 and B 6 as impaired or having an approved TMDL or Part II B 7 as exceptional, the following inspection schedule requirements apply:
 - (1) Inspections shall be conducted at a frequency of (i) at least once every four business days or (ii) at least once every five business days and no later than 24 hours following a measurable storm event. In the event that a measurable storm event occurs when there are more than 24 hours between business days, the inspection shall be conducted on the next business day; and
 - (2) Representative inspections as authorized in Part II G 2 d shall not be allowed.
 - b. Except as specified in Part II G 2 a, inspections shall be conducted at a frequency of:
 - (1) At least once every five business days; or
 - (2) At least once every 10 business days and no later than 24 hours following a measurable storm event. In the event that a measurable storm event occurs when there are more than 24 hours between business days, the inspection shall be conducted on the next business day.
 - (a) A storm event that produces 0.25 inches or more of rain within a 24-hour period on the first day of the storm and continues to produce 0.25 inches or more of rain on subsequent days. The operator is required to conduct an inspection within 24 hours of the first day of the storm and within 24 hours after the last day of the storm that produces 0.25 inches or more of rain.

(b) A discharge caused by snowmelt from a snow event producing 3.25 inches or more of snow within a 24-hour period. The operator is required to conduct one inspection once the discharge of snowmelt occurs. Additional inspections are only required if, following the discharge from the first snowmelt, there is a discharge from a separate storm event.

c. Where areas have been temporarily stabilized or construction activities will be suspended due to continuous frozen ground conditions and stormwater discharges are unlikely, the inspection frequency described in Part II G 2 a and 2 b may be reduced to once per month. If weather conditions (such as above freezing temperatures or rain or snow events) make discharges likely, the operator shall immediately resume the regular inspection frequency.

d. Except as prohibited in Part II G 2 a (2), representative inspections may be utilized for utility line installation, pipeline construction, or other similar linear construction activities provided that:

(1) Temporary or permanent soil stabilization has been installed and vehicle access may compromise the temporary or permanent soil stabilization and potentially cause additional land disturbance increasing the potential for erosion;

(2) Inspections occur on the same frequency as other construction activities;

(3) Control measures are inspected along the construction site 0.25 miles above and below each access point (i.e., where a roadway, undisturbed right-of-way, or other similar feature intersects the construction activity and access does not compromise temporary or permanent soil stabilization); and

(4) Inspection locations are provided in the inspection report required by Part II G.

e. If adverse weather causes the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. Any time inspections are delayed due to adverse weather conditions, evidence of the adverse weather conditions shall be included in the SWPPP with the dates of occurrence.

3. Inspection requirements. As part of the inspection, the qualified personnel shall at a minimum:

a. Record the date and time of the inspection and, when applicable, the date and rainfall or snowfall amount of the last measurable storm event;

b. Record the information and a description of any discharges occurring at the time of the inspection or evidence of discharges occurring prior to the inspection;

c. Record any construction activities that have occurred outside of the approved erosion and sediment control plan;

d. Inspect all stormwater discharge locations at the construction site. If a stormwater discharge is occurring during the inspection, observe and document the visual quality

and characteristics of the discharge, including color; odor; floating, settled, or suspended solids; foam; oil sheen; and other indicators of stormwater pollutants;

e. Inspect all construction dewatering discharge locations at the construction site, if applicable. If a construction dewatering discharge is occurring during the inspection, observe and document the visual quality and the characteristics of the discharge, including color; odor; floating, settled, or suspended solids; foam; oil sheen; and other indicators of pollutants;

f. Inspect the following for installation in accordance with the approved erosion and sediment control plan, identification of any maintenance needs, and evaluation of effectiveness in minimizing sediment discharge, including whether the control has been inappropriately or incorrectly used:

- (1) All perimeter erosion and sediment controls, such as silt fence;
- (2) Soil stockpiles, when applicable, and borrow areas for stabilization or sediment trapping measures;
- (3) Completed earthen structures, such as dams, dikes, ditches, and diversions for stabilization and effective impoundment or flow control;
- (4) Cut and fill slopes;
- (5) Sediment basins and traps, sediment barriers, and other measures installed to control sediment discharge from stormwater;
- (6) Temporary or permanent channels, flumes, or other slope drain structures installed to convey concentrated runoff down cut and fill slopes;
- (7) Storm inlets that have been made operational to ensure that sediment laden stormwater does not enter without first being filtered or similarly treated; and
- (8) Construction vehicle access routes that intersect or access paved or public roads for minimizing sediment tracking;

g. Inspect areas that have reached final grade or that will remain dormant for more than 14 days to ensure:

- (1) Initiation of stabilization activities have occurred immediately, as defined in 9VAC25-880-1; and
- (2) Stabilization activities have been completed within seven days of reaching grade or stopping work;

h. Inspect for evidence that the approved erosion and sediment control plan, "agreement in lieu of a plan," or erosion and sediment control plan prepared in accordance with department-approved standards and specifications has not been properly implemented. This includes:

(1) Concentrated flows of stormwater in conveyances such as rills, rivulets, or channels that have not been filtered, settled, or similarly treated prior to discharge, or evidence thereof;

(2) Sediment laden or turbid flows of stormwater that have not been filtered or settled to remove sediments prior to discharge;

(3) Sediment deposition in areas that drain to unprotected stormwater inlets or catch basins that discharge to surface waters. Inlets and catch basins with failing sediment controls due to improper installation, lack of maintenance, or inadequate design are considered unprotected;

(4) Sediment deposition on any property (including public and private streets) outside of the construction activity covered by this general permit;

(5) Required stabilization has not been initiated or completed or is not effective on portions of the construction site;

(6) Sediment basins without adequate wet or dry storage volume or sediment basins that allow the discharge of stormwater from below the surface of the wet storage portion of the basin;

(7) Sediment traps without adequate wet or dry storage or sediment traps that allow the discharge of stormwater from below the surface of the wet storage portion of the trap; and

(8) Land disturbance or sediment deposition outside of the approved area to be disturbed;

i. Inspect pollutant generating activities identified in the pollution prevention plan for the proper implementation, maintenance, and effectiveness of the procedures and practices;

j. Identify and report any pollutant generating activities not identified in the pollution prevention plan; and

k. Identify and document the presence of any evidence of the discharge of pollutants prohibited by this general permit.

4. Inspection report. Each inspection report shall include the following items:

a. The date and time of the inspection and, when applicable, the date and rainfall or snowfall amount of the last measurable storm event;

b. Summarized findings of the inspection;

c. The locations, visual quality, and characteristics of all stormwater discharges, when occurring;

- d. The locations, visual quality, and characteristics of all construction dewatering discharges, if applicable;
 - e. The locations of prohibited discharges;
 - f. The locations of control measures that require routine maintenance;
 - g. The locations of control measures that failed to operate as designed or proved inadequate or inappropriate for a particular location;
 - h. The locations where any evidence identified under Part II G 3 h exists;
 - i. The locations where any additional control measure is needed;
 - j. A list of corrective actions required (including any changes to the SWPPP that are necessary) as a result of the inspection or to maintain permit compliance;
 - k. Documentation of any corrective actions required from a previous inspection that have not been implemented;
 - l. Any incidents of noncompliance. If none, the report shall contain a certification that the construction activity is in compliance with the SWPPP and this general permit;
 - m. The required certification in accordance with Part III K 4 of this general permit; and
 - n. The date and signature of the qualified personnel and the operator or its duly authorized representative in accordance with Part III K 2 of this general permit.
5. The inspection report shall be included into the SWPPP no later than four business days after the inspection is complete.
6. The inspection report and any actions taken in accordance with Part II shall be retained by the operator as part of the SWPPP for at least three years from the date that general permit coverage expires or is terminated.

H. Corrective actions.

1. Except as required in Part II H 2, the operator shall implement the corrective actions identified as a result of an inspection as soon as practicable but no later than five business days after discovery or a longer period as approved by the VESMP authority. If approval of a corrective action by a regulatory authority (e.g., VESMP authority, VESCP authority, or the department) is necessary, additional control measures shall be implemented to minimize pollutants in stormwater discharges until such approvals can be obtained.
2. When any turbidity measurement of the construction dewatering discharge exceeds the selected benchmark option or visual monitoring indicates a change in the characteristics of effluent discharge, as outlined in Part II B 8, the operator shall :

- a. Immediately cease the construction dewatering discharge at the location that exceeds the turbidity benchmark or where visual monitoring indicates a change in the characterization of effluent discharge;
- b. Determine whether the construction dewatering controls are operating effectively or need routine maintenance or if an additional or alternate control measure is necessary; and
- c. Make any necessary adjustments, additions, repairs, or replacements to the construction dewatering controls.

Once these corrective action steps are completed and any necessary adjustments, additions, repairs, or replacements are made, the operator may resume its construction dewatering discharge and shall sample for turbidity within 15 minutes of the construction dewatering discharge commencing. No additional corrective action items are required beyond recording the results in the SWPPP.

3. The operator may be required to remove accumulated sediment deposits located outside of the construction site covered by this general permit as soon as practicable in order to minimize environmental impacts.

4. The operator shall notify the VESMP authority and the department as well as obtain all applicable federal, state, and local authorizations, approvals, and permits prior to the removal of sediments accumulated in surface waters, including wetlands.

PART III

CONDITIONS APPLICABLE TO ALL VPDES PERMITS

Discharge monitoring is not required for this general permit. If the operator chooses to monitor stormwater discharges or control measures, the operator shall comply with the requirements of Part III A, B, and C, as appropriate.

A. Monitoring.

1. Samples and measurements taken for the purpose of monitoring shall be representative of the monitoring activity.
2. Monitoring shall be conducted according to procedures approved under 40 CFR Part 136 or alternative methods approved by the U.S. Environmental Protection Agency, unless other procedures have been specified in this general permit. Analyses performed according to test procedures approved under 40 CFR Part 136 shall be performed by an environmental laboratory certified under regulations adopted by the Department of General Services (1VAC30-45 or 1VAC30-46).
3. The operator shall periodically calibrate and perform maintenance procedures on all monitoring and analytical instrumentation at intervals that will ensure accuracy of measurements.

B. Records.

1. Monitoring records and reports shall include:

- a. The date, exact place, and time of sampling or measurements;
- b. The individuals who performed the sampling or measurements;
- c. The dates and times analyses were performed;
- d. The individuals who performed the analyses;
- e. The analytical techniques or methods used; and
- f. The results of such analyses.

2. The operator shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by this general permit, and records of all data used to complete the registration statement for this general permit, for a period of at least three years from the date of the sample, measurement, report, or request for coverage. This period of retention shall be extended automatically during the course of any unresolved litigation regarding the regulated activity or regarding control standards applicable to the operator, or as requested by the department.

C. Reporting monitoring results.

1. The operator shall update the SWPPP to include the results of the monitoring as may be performed in accordance with this general permit, unless another reporting schedule is specified elsewhere in this general permit.

2. Monitoring results shall be reported on a discharge monitoring report (DMR); on forms provided, approved, or specified by the department; or in any format provided that the date, location, parameter, method, and result of the monitoring activity are included.

3. If the operator monitors any pollutant specifically addressed by this general permit more frequently than required by this general permit using test procedures approved under 40 CFR Part 136 or using other test procedures approved by the U.S. Environmental Protection Agency or using procedures specified in this general permit, the results of this monitoring shall be included in the calculation and reporting of the data submitted in the DMR or reporting form specified by the department.

4. Calculations for all limitations that require averaging of measurements shall utilize an arithmetic mean unless otherwise specified in this general permit.

D. Duty to provide information. The operator shall furnish, within a reasonable time, any information that the department may request to determine whether cause exists for terminating this general permit coverage or to determine compliance with this general permit. The department, EPA, or VESMP authority may require the operator to furnish, upon request, such plans, specifications, and other pertinent information as may be necessary to determine the effect of the

wastes from the operator's discharge on the quality of surface waters, or such other information as may be necessary to accomplish the purposes of the Clean Water Act and the Virginia Erosion and Stormwater Management Act. The operator shall also furnish to the department, EPA, or VESMP authority, upon request, copies of records required to be kept by this general permit.

E. Compliance schedule reports. Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this general permit shall be submitted no later than 14 days following each schedule date.

F. Unauthorized stormwater discharges. Pursuant to § 62.1-44.5 of the Code of Virginia, except in compliance with a permit issued by the department, it shall be unlawful to cause a stormwater discharge from a construction activity.

G. Reports of unauthorized discharges. Any operator who discharges or causes or allows a discharge of sewage, industrial waste, other wastes, any noxious or deleterious substance, a hazardous substance, or oil in an amount equal to or in excess of a reportable quantity established under either 40 CFR Part 110, 40 CFR Part 117, 40 CFR Part 302, or § 62.1-44.34:19 of the Code of Virginia that occurs during a 24-hour period into or upon surface waters or that discharges or causes or allows a discharge that may reasonably be expected to enter surface waters shall notify the department and the VESMP authority of the discharge immediately upon discovery of the discharge, but in no case later than within 24 hours after said discovery. A written report of the unauthorized discharge shall be submitted to the department and the VESMP authority within five calendar days of discovery of the discharge. The written report shall contain:

1. A description of the nature and location of the discharge;
2. The cause of the discharge;
3. The date on which the discharge occurred;
4. The length of time that the discharge continued;
5. The volume of the discharge;
6. If the discharge is continuing, how long it is expected to continue;
7. If the discharge is continuing, what the expected total volume of the discharge will be; and
8. Any steps planned or taken to reduce, eliminate, and prevent a recurrence of the present discharge or any future discharges not authorized by this general permit.

Discharges reportable to the department and the VESMP authority under the immediate reporting requirements of other regulations are exempted from this requirement.

H. Reports of unusual or extraordinary discharges. If any unusual or extraordinary discharge, including a "bypass" or "upset," as defined in this general permit, should occur from a construction site and the discharge enters or could be expected to enter surface waters, the operator shall promptly notify, in no case later than within 24 hours, the department and the VESMP authority after the discovery of the discharge. This notification shall provide all available details of the

incident, including any adverse effects on aquatic life and the known number of fish killed. The operator shall reduce the report to writing and shall submit it to the department and the VESMP authority within five calendar days of discovery of the discharge in accordance with Part III I 2. Unusual and extraordinary discharges include any discharge resulting from:

1. Unusual spillage of materials resulting directly or indirectly from processing operations;
2. Breakdown of processing or accessory equipment;
3. Failure or taking out of service of some or all of the facilities; and
4. Flooding or other acts of nature.

I. Reports of noncompliance. The operator shall report any noncompliance that may adversely affect state waters or may endanger public health.

1. A report to the department and the VESMP authority shall be provided within 24 hours from the time the operator becomes aware of the circumstances. The following shall be included as information that shall be reported within 24 hours under this subsection:

- a. Any unanticipated bypass; and
- b. Any upset that causes a discharge to surface waters.

2. A written report shall be submitted within five days and shall contain:

- a. A description of the noncompliance and its cause;
- b. The period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and
- c. Steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.

The department may waive the written report on a case-by-case basis for reports of noncompliance under Part III I if the oral report has been received within 24 hours and no adverse impact on surface waters has been reported.

3. The operator shall report all instances of noncompliance not reported under Part III I 1 or 2 in writing as part of the SWPPP. The reports shall contain the information listed in Part III I 2.

4. The immediate (within 24 hours) reports required in Part III G, H, and I may be made to the department and the VESMP authority. Reports may be made by telephone, email, or online at <https://www.deq.virginia.gov/our-programs/pollution-response>. For reports outside normal working hours, leaving a recorded message shall fulfill the immediate reporting requirement. For emergencies, the Virginia Department of Emergency Management maintains a 24-hour telephone service at 1-800-468-8892.

5. Where the operator becomes aware of a failure to submit any relevant facts, or submittal of incorrect information in any report, including a registration statement, to the department or the VESMP authority, the operator shall promptly submit such facts or correct information.

J. Notice of planned changes.

1. The operator shall give notice to the department and the VESMP authority as soon as possible of any planned physical alterations or additions to the permitted facility or activity. Notice is required only when:

- a. The operator plans an alteration or addition to any building, structure, facility, or installation that may meet one of the criteria for determining whether a facility is a new source in 9VAC25-875-990; or
- b. The operator plans an alteration or addition that would significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants that are not subject to effluent limitations in this general permit.

2. The operator shall give advance notice to the department and VESMP authority of any planned changes in the permitted facility or activity that may result in noncompliance with permit requirements.

3. The operator may continue construction activities based on the information provided in the original registration statement and SWPPP but must wait until the review period has ended before commencing or continuing construction activities on any portion of the construction site that would be affected by any of the planned changes or modifications. Any operator that chooses to proceed with unapproved construction activities while plans are being reviewed is proceeding at its own risk and subject to compliance actions if the plan is determined to be inadequate.

K. Signatory requirements.

1. Registration statement and notice of termination. All registration statements and notices of termination shall be signed as follows:

- a. For a corporation: by a responsible corporate officer. For the purpose of this chapter, a responsible corporate officer means (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy-making or decision-making functions for the corporation; or (ii) the manager of one or more manufacturing, production, or operating facilities, provided the manager is authorized to make management decisions that govern the operation of the regulated facility, including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long-term compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures;

b. For a partnership or sole proprietorship: by a general partner or the proprietor, respectively; or

c. For a municipality, state, federal, or other public agency: by either a principal executive officer or ranking elected official. For purposes of this chapter, a principal executive officer of a public agency includes (i) the chief executive officer of the agency or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.

2. Reports and other information. All reports required by this general permit, including SWPPPs, and other information requested by the department shall be signed by a person described in Part III K 1 or by a duly authorized representative of that person. A person is a duly authorized representative only if:

a. The authorization is made in writing by a person described in Part III K 1;

b. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, operator of a well or a well field, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters for the operator. (A duly authorized representative may thus be either a named individual or any individual occupying a named position); and

c. The signed and dated written authorization is included in the SWPPP. A copy shall be provided to the department and VESMP authority, if requested.

3. Changes to authorization. If an authorization under Part III K 2 is no longer accurate because a different individual or position has responsibility for the overall operation of the construction activity, a new authorization satisfying the requirements of Part III K 2 shall be submitted to the VESMP authority as the administering entity for the department prior to or together with any reports or information to be signed by an authorized representative.

4. Certification. Any person signing a document under Part III K 1 or 2 shall make the following certification:

"I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

L. Duty to comply. The operator shall comply with all conditions of this general permit. Any noncompliance with this general permit constitutes a violation of the Virginia Erosion and Stormwater Management Act and the Clean Water Act, except that noncompliance with certain provisions of this general permit may constitute a violation of the Virginia Erosion and Stormwater Management Act but not the Clean Water Act. Permit noncompliance is grounds for enforcement

action; for permit coverage, termination, revocation, and reissuance, or modification of permit coverage; or denial of a permit renewal application.

The operator shall comply with effluent standards or prohibitions established under § 307(a) of the Clean Water Act for toxic pollutants within the time provided in the regulations that establish these standards or prohibitions or standards for sewage sludge use or disposal, even if this general permit has not yet been modified to incorporate the requirement.

M. Duty to reapply. If the operator wishes to continue an activity regulated by this general permit after the expiration date of this general permit, the operator shall submit a new registration statement at least 90 days before the expiration date of the existing general permit, unless permission for a later date has been granted by the department. The department shall not grant permission for registration statements to be submitted later than the expiration date of the existing general permit.

N. Effect of a permit. This general permit neither conveys any property rights in either real or personal property or any exclusive privileges nor authorizes any injury to private property or invasion of personal rights, or any infringement of federal, state, or local law or regulations.

O. State law. Nothing in this general permit shall be construed to preclude the institution of any legal action under or relieve the operator from any responsibilities, liabilities, or penalties established pursuant to any other state law or regulation or under authority preserved by § 510 of the Clean Water Act. Except as provided in general permit conditions on bypassing under Part III U and upset under Part III V, nothing in this general permit shall be construed to relieve the operator from civil and criminal penalties for noncompliance.

P. Oil and hazardous substance liability. Nothing in this general permit shall be construed to preclude the institution of any legal action or relieve the operator from any responsibilities, liabilities, or penalties to which the operator is or may be subject under §§ 62.1-44.34:14 through 62.1-44.34:23 of the State Water Control Law or § 311 of the Clean Water Act.

Q. Proper operation and maintenance. The operator shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances), which are installed or used by the operator to achieve compliance with the conditions of this general permit. Proper operation and maintenance also includes effective plant performance, adequate funding, adequate staffing, and adequate laboratory and process controls, including appropriate quality assurance procedures. This provision requires the operation of back-up or auxiliary facilities or similar systems, which are installed by the operator only when the operation is necessary to achieve compliance with the conditions of this general permit.

R. Disposal of solids or sludges. Solids, sludges, or other pollutants removed in the course of treatment or management of pollutants shall be disposed of in a manner so as to prevent any pollutant from such materials from entering surface waters and in compliance with all applicable state and federal laws and regulations.

S. Duty to mitigate. The operator shall take all steps to minimize or prevent any discharge in violation of this general permit that has a reasonable likelihood of adversely affecting human health or the environment.

T. Need to halt or reduce activity not a defense. It shall not be a defense for an operator in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this general permit.

U. Bypass.

1. "Bypass," as defined in 9VAC25-875-850, means the intentional diversion of waste streams from any portion of a treatment facility. The operator may allow any bypass to occur that does not cause effluent limitations to be exceeded, but only if it also is for essential maintenance to ensure efficient operation. These bypasses are not subject to the provisions of Part III U 2 and U 3.

2. Notice.

a. Anticipated bypass. If the operator knows in advance of the need for a bypass, the operator shall submit prior notice to the department, if possible at least 10 days before the date of the bypass.

b. Unanticipated bypass. The operator shall submit notice of an unanticipated bypass as required in Part III I.

3. Prohibition of bypass.

a. Except as provided in Part III U 1, bypass is prohibited, and the department may take enforcement action against an operator for bypass unless:

(1) Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage. Severe property damage means substantial physical damage to property, damage to the treatment facilities that causes them to become inoperable, or substantial and permanent loss of natural resources that can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production;

(2) There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass that occurred during normal periods of equipment downtime or preventive maintenance; and

(3) The operator submitted notices as required under Part III U 2.

b. The department may approve an anticipated bypass, after considering its adverse effects, if the department determines that it will meet the three conditions listed in Part III U 3 a.

V. Upset.

1. An "upset," as defined in 9VAC25-875-850, means an exceptional incident in which there is unintentional and temporary noncompliance with technology-based permit effluent

limitations because of factors beyond the reasonable control of the operator. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.

2. An upset constitutes an affirmative defense to an action brought for noncompliance with technology-based permit effluent limitations if the requirements of Part III V 3 are met. A determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is not a final administrative action subject to judicial review.

3. An operator who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs or other relevant evidence that:

- a. An upset occurred and that the operator can identify the cause of the upset;
- b. The permitted facility was at the time being properly operated;
- c. The operator submitted notice of the upset as required in Part III I; and
- d. The operator complied with any remedial measures required under Part III S.

4. In any enforcement proceeding, the operator seeking to establish the occurrence of an upset has the burden of proof.

W. Inspection and entry. The operator shall allow the department, the VESMP authority, EPA, or an authorized representative of either entity (including an authorized contractor), upon presentation of credentials and other documents as may be required by law, to:

1. Enter upon the operator's premises where a regulated facility or activity is located or conducted or where records shall be kept under the conditions of this general permit;
2. Have access to and copy, at reasonable times, any records that shall be kept under the conditions of this general permit;
3. Inspect and photograph at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this general permit; and
4. Sample or monitor at reasonable times, for the purposes of ensuring permit compliance or as otherwise authorized by the Clean Water Act or the Virginia Erosion and Stormwater Management Act, any substances or parameters at any location.

For purposes of this section, the time for inspection shall be deemed reasonable during regular business hours and whenever the facility is discharging. Nothing contained in this general permit shall make an inspection unreasonable during an emergency.

X. Permit actions. Permit coverage may be modified, revoked and reissued, or terminated for cause. The filing of a request by the operator for a permit modification, revocation and reissuance,

or termination, or a notification of planned changes or anticipated noncompliance does not stay any permit condition.

Y. Transfer of permit coverage.

1. Permits are not transferable to any person except after notice to the department. Except as provided in Part III Y 2, a permit may be transferred by the operator to a new operator only if the permit has been modified or revoked and reissued, or a minor modification made, to identify the new operator and incorporate such other requirements as may be necessary under the Virginia Erosion and Stormwater Management Act and the Clean Water Act.

2. As an alternative to transfers under Part III Y 1, this permit may be automatically transferred to a new operator if:

a. The current operator notifies the department at least 30 days in advance of the proposed transfer of the title to the facility or property;

b. The notice includes a written agreement between the existing and new operators containing a specific date for transfer of permit responsibility, coverage, and liability between them; and

c. The department does not notify the existing operator and the proposed new operator of its intent to modify or revoke and reissue the permit. If this notice is not received, the transfer is effective on the date specified in the agreement mentioned in Part III Y 2 b.

3. For ongoing construction activity involving a change of operator, the new operator shall accept and maintain the existing SWPPP, or prepare and implement a new SWPPP prior to taking over operations at the construction site.

Z. Severability. The provisions of this general permit are severable, and if any provision of this general permit or the application of any provision of this permit to any circumstance, is held invalid, the application of such provision to other circumstances and the remainder of this general permit shall not be affected thereby.

Appendix C

Forms: Notice of Registration and Notice of Termination

**VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY
GENERAL VPDES PERMIT FOR DISCHARGES OF
STORMWATER FROM CONSTRUCTION ACTIVITIES (VAR10)
REGISTRATION STATEMENT 2024**

PERMIT #: _____
PLAN/ID #: _____

Application type. (CHOOSE ONE) ☐ NEW PERMIT ISSUANCE
☐ MODIFICATION WITH ACREAGE INCREASE: Permit # _____
☐ MODIFICATION WITHOUT ACREAGE INCREASE: Permit # _____
☐ EXISTING PERMIT REISSUANCE: Permit # _____

Section I. Operator/Permittee/Billing Information.

A. Construction Activity Operator (Permittee). The person or entity that is applying for permit coverage and will have operational control over construction activities to ensure compliance with the general permit. A person with signatory authority for this operator must sign the certification in Section V (per Part III.K of the VAR10 Permit).

Operator Name:	
Contact person:	
Address:	
City, State and Zip Code:	
Phone Number:	
Primary and CC Email(s):	
State Corporation Commission Entity Number (if applicable):	

B. Electronic correspondence. To receive an emailed coverage letter or to pay by credit card, you must choose **YES** and include a valid email. May we transmit correspondence electronically? **YES** ☐ **NO** ☐

Section II. Construction Activity Information.

A. Include a legible site map showing the location of the existing or proposed land-disturbing activities for which the operator is seeking permit coverage, the limits of land disturbance, construction entrances, construction support activities, and all waterbodies receiving stormwater discharges from the construction site.

B. Project site location information.

Construction Activity Name:	
Address:	
City and/or County and Zip Code:	
Construction Activity Entrance Location (description or street address):	
Latitude and Longitude (6-digit, decimal degrees format, e.g. 37.1234, -78.1234):	

C. Acreage totals for all land-disturbing activities to be included under this permit coverage. Report to the nearest one-hundredth of an acre.

Total area of the construction site (including off-site area):	
Estimated area to be disturbed by the construction activity (on-site only):	
Off-site estimated area to be disturbed (if applicable; please also refer to Section III):	

D. Construction Activity Status: **FEDERAL** ☐ **STATE** ☐ **PUBLIC** ☐ **PRIVATE** ☐

E. Nature of the Construction Activity Description (i.e. commercial, industrial, residential, agricultural, utility, solar, linear, stream restoration, etc.):

CONSTRUCTION GENERAL PERMIT (VAR10) REGISTRATION STATEMENT 2024

F. Municipal Separate Storm Sewer System (MS4) name(s) (if the construction activity is discharging to an MS4):	ODU/CITY OF NORFOLK
G. Estimated Construction Activity Dates.	
Start Date:	SEPTEMBER 1ST, 2024
Completion Date:	AUGUST 31ST, 2026
H. Is this construction activity part of a larger common Plan of development or sale?	YES <input type="checkbox"/> NO <input type="checkbox"/>
I. 6 th Order Hydrologic Unit Code (HUC) and Receiving Water Name(s). Include additional areas on a separate page.	
HUC	NAME(S) OF RECEIVING WATER WATERBODY
JL56	EASTERN BRANCH OF THE ELIZABETH RIVER

Section III. Off-site Support Activity Location Information.

List all off-site support activities and excavated material disposal areas being utilized for this project. Include additional areas on a separate page.	
Off-site Activity Name:	
Address:	
City or County:	
Off-site Activity Entrance Location (description or street address):	
Latitude and Longitude (6-digit, decimal degrees format, e.g., 37.1234, -78.1234):	
Is this off-site activity an excavated material disposal area?	YES <input type="checkbox"/> NO <input type="checkbox"/>
If this off-site activity is an excavated material disposal area, list the contents of the excavated fill material:	
Will a separate VPDES permit cover this off-site activity?	YES <input type="checkbox"/> Permit # _____ NO <input type="checkbox"/>

Section IV. Other Information.

A. A Stormwater Pollution Prevention Plan (SWPPP) must be prepared in accordance with the requirements of the General VPDES Permit for Discharges of Stormwater from construction activities <u>prior to</u> submitting the registration statement. By signing the registration statement, the operator certifies the SWPPP has been prepared.	
B. Has an Erosion and Sediment Control Plan been submitted to the VESC Authority for review?	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>
Erosion and Sediment Control Plan Approval Date: (for the estimated area to be disturbed; MM/DD/YYYY)	
C. Has land-disturbance commenced?	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>
D. Standards and Specifications. If this project is utilizing approved Standards and Specifications (S&S), attach the completed S&S Entity Form.	
E. Will nutrient credits be used to comply with the water quality design criteria requirements (9VAC25-875-580)? YES <input type="checkbox"/> NO <input type="checkbox"/> (If yes, please include a copy of the letter of availability from an appropriate nutrient bank that nonpoint source nutrient credits are available.)	

CONSTRUCTION GENERAL PERMIT (VAR10) REGISTRATION STATEMENT 2024

Section V. Certification. A person representing the operator as identified in Section I.A and meeting the requirements of Part III.K of 9VAC25-880-70 must physically sign this certification. A typed signature is not acceptable. Please note that operator is defined in 9VAC25-875-20 as follows:

“Operator” means the owner or operator of any facility or activity subject to the VESMA and this chapter. In the context of stormwater associated with a large or small construction activity, “operator” means any person associated with a construction project that meets either of the following two criteria: (i) the person has direct operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications or (ii) the person has day-to-day operational control of those activities at a project that are necessary to ensure compliance with a stormwater pollution prevention plan for the site or other permit or VESMP authority permit conditions (i.e., the person is authorized to direct workers at a site to carry out activities required by the stormwater pollution prevention plan or comply with other permit conditions). In the context of stormwater discharges from an MS4, “operator” means the operator of the regulated MS4 system.

9VAC25-880-70. Part III.K. Signatory requirements. All registration statements shall be signed as follows:

- a. *“For a corporation: by a responsible corporate officer. For the purpose of this chapter, a responsible corporate officer means: (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy-making or decision-making functions for the corporation; or (ii) the manager of one or more manufacturing, production, or operating facilities, provided the manager is authorized to make management decisions that govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long-term compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures;*
- b. *For a partnership or sole proprietorship: by a general partner or the proprietor, respectively; or*
- c. *For a municipality, state, federal, or other public agency: by either a principal executive officer or ranking elected official. For purposes of this chapter, a principal executive officer of a public agency includes (i) the chief executive officer of the agency or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.”*

Certification: "I certify under penalty of law that I have read and understand this registration statement and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is to the best of my knowledge and belief true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations."

Printed Name: _____

Signature (signed in ink): _____

Date Signed: _____

Section VI. Submittal Instructions. Submit this form to the VESMP Authority. If the locality is the VESMP Authority, please send your registration statement submittal directly to the locality; do NOT send this form to DEQ. A list of local VESMP Authorities is available here: [VESMP Authorities](#).

If DEQ is the VESMP Authority, please send to:

Department of Environmental Quality
Office of Stormwater Management Suite 1400
PO Box 1105
Richmond VA 23218
constructiongp@deq.virginia.gov

If the locality is the VESMP Authority, please send to:

The Local VESMP Authority (insert address below):

CONSTRUCTION GENERAL PERMIT (VAR10) REGISTRATION STATEMENT 2024

INSTRUCTIONS

PLEASE DO NOT PRINT OR SUBMIT

This registration statement is for coverage under the General Virginia Pollutant Discharge Elimination System (VPDES) Permit for Discharges of Stormwater from Construction Activities (also referred to as the Construction General Permit). This form covers the following permit actions: new permit issuance, existing permit modification with an increase in acreage, existing permit modifications that result in a plan modification but do not result in an increase in disturbed acreage, and reissuance of an active permit coverage.

Application type. Select **NEW PERMIT ISSUANCE** to obtain a new permit coverage. Modifications are for modifying an existing, active permit coverage. Select **MODIFICATION WITH ACREAGE INCREASE** when the previously approved acreage(s) increases (permit modifications are not performed for decreases in acreage unless they result in plan changes – see Modification WITHOUT Acreage Increase). Select **MODIFICATION WITHOUT ACREAGE INCREASE** when there is a change to the site design resulting in a change to the approved plans with no increase in acreage(s). Select **EXISTING PERMIT REISSUANCE** to extend an expiring permit coverage for the next permit cycle and include the existing permit number.

Section I. Operator/Permittee/Billing Information.

A. Construction Activity Operator (Permittee). The person or entity that is applying for permit coverage and will have operational control over construction activities to ensure compliance with the general permit. For companies, use the complete, active, legal entity name as registered with a state corporation commission. Entities that are considered operators commonly consist of the property owner, developer of a project (the party with control of project plans and specifications), or general contractor (the party with day-to-day operational control of the activities at the project site that are necessary to ensure compliance with the general permit). If an individual person is listed as the operator, that person (or a legal representative of) must sign the certification in Section V. An operator may be one of the following:

9VAC25-875-20. Definitions.

“Operator” means the owner or operator of any facility or activity subject to the VESMA and this chapter. In the context of stormwater associated with a large or small construction activity, “operator” means any person associated with a construction project that meets either of the following two criteria: (i) the person has direct operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications or (ii) the person has day-to-day operational control of those activities at a project that are necessary to ensure compliance with a stormwater pollution prevention plan for the site or other permit or VESMP authority permit conditions (i.e., the person is authorized to direct workers at a site to carry out activities required by the stormwater pollution prevention plan or comply with other permit conditions). In the context of stormwater discharges from an MS4, “operator” means the operator of the regulated MS4 system.

“Owner” means the same as that term as defined in § 62.1-44.3 of the Code of Virginia. For a regulated land-disturbing activity that does not require a permit, “owner” also means the owner of the freehold of the premises of lesser estate therein, mortgagee or vendee in possession, assignee of rents, receiver, executor, trustee, lessee, or other person, firm or corporation in control of a property.

“Person” means any individual, partnership, firm, association, joint venture, public or state corporation, trust, estate, commission, board, public or private institution, utility, cooperative, county, city, town, or other political subdivision of the Commonwealth, governmental body, including a federal or state entity as applicable, any interstate body or any other legal entity.

B. May we transmit correspondence electronically? If you choose **YES** to this question and provide an email address in Section I. A., all correspondence, forms, invoices and notifications will be transmitted by email to the operator. This will also give the operator the ability to pay by credit card and to receive permit coverage approval letters immediately upon permit approval.

Section II. Construction Activity Information.

A. A legible site map showing the location of the existing or proposed land-disturbing activities for which the operator is seeking permit coverage, the limits of land disturbance, construction entrances, construction support activities, and all water bodies receiving stormwater discharges from the construction site must be included with the submittal of this form. Aerial imagery maps or topographic maps showing the required items are acceptable. Plan sheet sized site maps are not required. Please consult your VESMP authority if you have additional questions regarding site map requirements.

B. Construction Activity Name and location. Provide a descriptive name of the construction activity to be covered under the general permit (it is helpful to use the same naming convention as listed on the Stormwater Management plans), 911 street address (if available), city/county of the construction activity, and the 6-digit latitude and longitude in decimal degrees format for the centroid, main construction entrance or start and end points for linear projects (i.e., 37.1234, -77.1234).

C. Acreage totals for all construction site activities, on- and off-site, to be included under this permit. Acreages are to be reported to the nearest one-hundredth acre (two decimal places, i.e., 1.15 acres). Provide the total acreage of the construction site as approved on the Stormwater Management Plans and the estimated on-site acreage to be disturbed by the construction activity as approved under the Erosion and Sediment Control Plans. The off-site estimated area to be disturbed is the sum of the disturbed acreages for all off-site support activities to be covered under this general permit. The total area of the construction site includes the construction support activities located on-site and off-site. Permit fees are calculated based on your disturbed acreage total for all on- and off-site areas being disturbed under this permit coverage (the sum of all on-site and off-site disturbed acreages).

D. Construction activity owner status. The status of the construction activity property owner. Any property not owned by a government entity or agency (i.e. federal, state or local governments) is **PRIVATE**.

E. Nature of the construction activity description. Choose the designation that best describes the post-construction use of this project (you may choose more than one). (i.e. commercial, industrial, residential, agricultural, utility, solar, linear, stream restoration, etc.). Describe the post-construction use of the project (i.e. commercial – one new office building and associated parking and utilities; transportation – linear roads, sidewalks and utilities; agricultural – three poultry houses, etc.).

F. Municipal Separate Storm Sewer System (MS4) name(s) if discharging to an MS4. If stormwater is discharged through an MS4 (either partially or completely), provide the name of the MS4(s) that will be receiving water from this construction activity. The MS4 name is typically the town, city, county, institute, or federal facility where the construction activity is located.

G. Estimated construction activity dates. Provide the estimated construction activity start date and completion date in Month/Day/Year or MM/DD/YYYY format (i.e. 07/30/2019).

H. Is this construction activity is part of a larger common plan of development or sale? Per 9VAC25-875-20, “common plan of development or sale” means a contiguous area where separate and distinct construction activities may be taking place at different times on different schedules (i.e. a subdivision, commercial development, business park, etc.).

I. Sixth (6th) Order Hydrologic Unit Code (HUC) and associated Receiving Water Name(s). Provide all 6th order HUCs and receiving waterbody names, for the primary site and any off-site areas included under this permit coverage, that could potentially receive stormwater runoff discharging from this activity. The HUC can be either a 12-digit number (i.e., 0208010101) or 2-letter, 2-number code (i.e., JL52). Include additional HUCs or receiving waters on a separate page. You may utilize DEQ’s web-based GIS application to obtain this information.

- DEQ Environmental Data Mapper (EDM) application link: [Environmental Data Mapper](#)
- Instructions, help and resources for using DEQ’s EDM application link: [EDM Help & Resources](#)

Section III. Off-site Support Activity Location Information.

This general permit also authorizes stormwater discharges from support activities (e.g., concrete or asphalt batch plants, equipment staging yards, material storage areas, excavated material disposal areas, borrow areas, etc.) located on-site or off-site provided that (i) the support activity specifically supports the construction activity that is required to have general permit coverage; (ii) the support activity is not a commercial operation, nor does it serve multiple unrelated construction activities by different operators; (iii) the support activity does not operate beyond the completion of the construction activity it supports; (iv) the support activity is identified in the registration statement at the time of general permit coverage; (v) appropriate control measures are identified in a SWPPP and implemented to address the discharges from the support activity areas; and (vi) all applicable state, federal, and local approvals are obtained for the support activity.

Off-site activity name and location information. Provide a descriptive off-site project name, 911 street address (if available), construction entrance location (address or description), city/county and the 6-digit latitude and longitude in decimal degrees (i.e., 37.1234, -77.1234) of all off-site support activities. Indicate whether the off-site support activity will be covered under this general permit or a separate VPDES permit.

If excavated material (i.e., fill) will be transported off-site for disposal, the name and physical location address, when available, of all off-site excavated material disposal areas including city or county; 6-digit latitude and longitude in decimal degrees (i.e., 37.1234, -77.1234) and the contents of the excavated material.

List additional off-site areas to be included under this permit coverage on a separate page. Off-site areas not included on this registration will need to obtain coverage under a separate VPDES permit.

Section IV. Other Information.

A. A stormwater pollution prevention plan (SWPPP) must be prepared prior to submitting the registration statement per 9VAC25-880. See 9VAC25-880-70 Part II Of the General Permit for the SWPPP requirements.

B. If the Erosion and Sediment Control Plan for the estimated area to be disturbed listed in Section II. C has been submitted to the Virginia Erosion and Sediment Control Program (VESCP) Authority for review and approval, choose **YES**. If you are submitting this application to reissue an existing permit coverage, please provide the date that the VESCP Authority approved the Erosion and Sediment Control Plan for the estimated area to be disturbed. If land disturbance has commenced, choose **YES**. “Land disturbance” or “land-disturbing activity” means a man-made change to the land surface that may result in soil erosion or has the potential to change its runoff characteristics, including construction activity such as the clearing, grading, excavating, or filling of land.

D. If this project is using approved Standards and Specifications (S&S), attach the completed S&S Entity Form. If the S&S Entity is different from the operator identified in Section I.A., list the S&S Entity Name. The S&S entity is the entity or agency that holds the approved standards & specification. Please indicate if this project is also requesting a plan waiver.

- S&S Entity Form link: [Standards and Specifications Entity Information Form](#)

E. If nutrient credits will be used to comply with the water quality design criteria requirements (9VAC25-875-590), choose **YES**. In addition, include a copy of the letter of availability from an appropriate nutrient bank that nonpoint source nutrient credits are available. If nutrient credits will not be used, choose **NO**.

Section V. Certification.

A properly authorized individual associated with the operator identified in Section I.A. of the registration statement is responsible for certifying and signing the registration statement. A person must physically sign the certification, a typed signature is unacceptable. State statutes provide for severe penalties for submitting false information on the registration statement. State regulations require that the registration statement be signed as follows per 9VAC25-880-70 Part III.K.1:

- "a. For a corporation: by a responsible corporate officer. For the purpose of this part, a responsible corporate officer means:*
- (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy-making or decision-making functions for the corporation; or*
 - (ii) the manager of one or more manufacturing, production, or operating facilities, provided the manager is authorized to make management decisions that govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long-term compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedure;*
- b. For a partnership or sole proprietorship: by a general partner or the proprietor, respectively; or*
- c. For a municipality, state, federal, or other public agency: by either a principal executive officer or ranking elected official. For purposes of this part, a principal executive officer of a public agency includes:*
- (i) the chief executive officer of the agency, or*
 - (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.*

Section VI. Submittal Instructions.

Submit this completed signed form to the VESMP/VSMP authority that has jurisdiction for your construction activity. The appropriate authority may be either the local government your locality depending on the location and type of project or DEQ. If your project is under the jurisdiction of a local VESMP authority, please contact the locality for additional submittal instructions. A blank area is provided for the local VESMP authority's mailing address.

Who is the authority for my project? DEQ or the locality?

- **DEQ:** DEQ is the VSMP Authority and administers permit coverage for land-disturbing activities that are:
 - within a locality that is not a VESMP authority;
 - owned by the State or Federal government; or
 - utilizing approved Standards and Specifications.

Email the completed and signed form to: constructiongp@deq.virginia.gov

- **The Locality:** The local government (locality) is the VESMP authority and administers permit coverage for all other projects not covered by DEQ as listed above. For these projects, please submit permit forms directly to the local VESMP authority. A list of local VESMP authorities is available on DEQ's website here: [Local VESMP Authority List](#).

**VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY
GENERAL VPDES PERMIT FOR DISCHARGES OF STORMWATER
FROM CONSTRUCTION ACTIVITIES (VAR10) PERMIT FEE FORM 2024**

Section I. Construction Activity Operator/Permittee Information. Operator information as it appears on the registration statement for a new permit issuance or the current, active permit coverage.

Operator Name: _____

Contact Person: _____

Address: _____

City, State and Zip Code: _____

Phone Number: _____

Primary Email: _____

CC Email: _____

Section II. Construction Activity Location Information. Location information regarding the construction activity.

Existing Permit Number
(if applicable): _____

Construction Activity
Name: _____

City and/or County
and Zip Code: _____

Section III. Type of Permit. Choose the type of construction activity permit for which you are applying (choose one).

General Permit Coverage ☐ Individual Permit Coverage ☐ Expedited General Permit Coverage (>100 acres) ☐

Section IV. Type of Permit Action. Choose the type of permit being performed (choose one).

New Issuance ☐ Reissuance ☐ Maintenance ☐ Modification ☐ Transfer ☐

Section V. Fee. The fee is calculated based on the total estimated area to be disturbed by the construction activity. From the Fee Schedule. Amount of fee submitted: _____

Section VI. Instructions. Fees are required and must be paid when applications for permit issuance, reissuance, modification or transfer are submitted. Applications are considered incomplete if the proper fee is not paid in full and will not be processed until the fee is received. The fee schedule for permits is included with this form. Invoices will be emailed if you chose "YES" to e-transmit and included a valid email on your permit registration statement.

Please submit this form to the VESMP Authority that has jurisdiction for your construction activity. If the locality is the VESMP Authority, please submit your form directly to the locality; do NOT send this form to DEQ.

If DEQ is the VSMP Authority, please send to:
Department of Environmental Quality
Office of Stormwater Management Suite 1400
PO Box 1105
Richmond VA 23218
constructiongp@deq.virginia.gov

If the locality is the VESMP Authority, please send to:
The Local VESMP Authority (*insert address below*):

**VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY
GENERAL VPDES PERMIT FOR DISCHARGES OF STORMWATER
FROM CONSTRUCTION ACTIVITIES (VAR10) PERMIT FEE FORM 2024**

A. Individual Permits. The fee for filing a permit application for a Construction Activity Individual Permit issued by the Board is as follows: (NOTE: Individual permittees pay an annual permit maintenance fee instead of a reapplication fee. The permittee is billed separately by DEQ for the annual permit maintenance fee.)

TYPE OF PERMIT	ISSUANCE
Individual Permit for Discharges from Construction Activities	\$15,000

B. Registration Statements. The fee for filing a permit application (registration statement) for coverage under a Construction Activity General Permit issued by the Board, including a state or federal agency that does not administer a project in accordance with approved annual standards and specifications, is as follows:

TYPE OF PERMIT	ISSUANCE
General / Stormwater Management - Small Construction Activity/Land Clearing (Areas within common plans of development or sale with land-disturbance acreage less than one acre, except for single-family detached residential structures)	\$290
General / Stormwater Management - Small Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than one acre and less than five acres)	\$2,700
General / Stormwater Management - Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than five acres and less than 10 acres)	\$3,400
General / Stormwater Management - Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 10 acres and less than 50 acres)	\$4,500
General / Stormwater Management - Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 50 acres and less than 100 acres)	\$6,100
General / Stormwater Management - Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 100 acres)	\$9,600

The fee for filing a permit application (registration statement) for coverage under a Construction Activity General Permit issued by the Board for a state or federal agency that administers a project in accordance with approved annual standards and specifications is as follows:

TYPE OF PERMIT	ISSUANCE
Construction General / Stormwater Management – Phase I Land Clearing (“Large” Construction Activity – Sites or common plans of development or sale equal to or greater than 5 acres)	\$750
Construction General / Stormwater Management – Phase II Land Clearing (“Small” Construction Activity – Sites or common plans of development or sale equal to or greater than 1 acre and less than 5 acres)	\$450

**VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY
GENERAL VPDES PERMIT FOR DISCHARGES OF STORMWATER
FROM CONSTRUCTION ACTIVITIES (VAR10) PERMIT FEE FORM 2024**

C. Permit Modification or Transfer Fees. The following fees apply to the modification or transfer of a Construction Activity Individual Permit or a Construction Activity General Permit issued by the Board. The fee assessed shall be based on the total disturbed acreage of the construction activity. In addition to the permit modification fee, modifications resulting in an increase in total disturbed acreage shall pay the difference in the initial Construction Activity General Permit fee paid and the Construction Activity General Permit fee that would have applied for the total disturbed acreage in Section B.

TYPE OF PERMIT	MODIFICATION
General / Stormwater Management – Small Construction Activity/Land Clearing (Areas within common plans of development or sale with land disturbance acreage less than one acre, except for single-family detached residential structures)	\$20
General / Stormwater Management – Small Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than one and less than five acres)	\$200
General / Stormwater Management – Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than five acres and less than 10 acres)	\$250
General / Stormwater Management – Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 10 acres and less than 50 acres)	\$300
General / Stormwater Management – Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 50 acres and less than 100 acres)	\$450
General / Stormwater Management – Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 100 acres)	\$700
Individual Permit for Discharges from Construction Activities	\$5,000

D. Permit Maintenance Fees. The following annual permit maintenance fees apply to each permit identified below, including expired permits that have been administratively continued. No annual permit maintenance fee is required for coverage under a Construction Activity General Permit for a state or federal agency that administers a project in accordance with approved annual standards and specifications.

TYPE OF PERMIT	MAINTENANCE
General / Stormwater Management – Small Construction Activity/Land Clearing (Areas within common plans of development or sale with land disturbance acreage less than one acre, except for single-family detached residential structures)	\$50
General / Stormwater Management – Small Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than one and less than five acres)	\$400
General / Stormwater Management – Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than five acres and less than 10 acres)	\$500
General / Stormwater Management – Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 10 acres and less than 50 acres)	\$650

**VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY
GENERAL VPDES PERMIT FOR DISCHARGES OF STORMWATER
FROM CONSTRUCTION ACTIVITIES (VAR10) PERMIT FEE FORM 2024**

General / Stormwater Management – Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 50 acres and less than 100 acres)	\$900
General / Stormwater Management – Large Construction Activity/Land Clearing (Sites or areas within common plans of development or sale with land-disturbance acreage equal to or greater than 100 acres)	\$1,400
Individual Permit for Discharges from Construction Activities	\$3,000

**VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY
GENERAL VPDES PERMIT FOR DISCHARGES OF
STORMWATER FROM CONSTRUCTION ACTIVITIES (VAR10)
NOTICE OF TERMINATION 2024**

Permit Coverage Number (VAR10#####): _____

Section I. Operator/Permittee Information. The person or entity that has active permit coverage approval and operational control over construction activities to ensure compliance with the general permit. A person with signatory authority for this operator must sign the certification in Section VII (per Part III K of the VAR10 Permit).

Construction Activity Operator Name: _____

Contact Person: _____

Address: _____

City, State, Zip Code: _____

Phone Number: _____

Primary Email: _____

Section II. Construction Activity Location Information. Project site information.

Construction Activity Name: _____

Address: _____

City and/or County and Zip Code: _____

Latitude and Longitude (6-digit, decimal degrees format): _____

Section III. Requirements for Termination of general permit coverage. The operator of the construction activity shall submit a complete and accurate notice of termination, unless a registration statement was not required to be submitted in accordance with 9VAC25-880-50 A 1 c or A 2 b for a stormwater discharge associated with a small construction activity of a single family detached residential structure, within or outside of a common plan of development or sale, to the VESMP authority after one or more of the following conditions have been met:

- ☐ Necessary permanent control measures included in the SWPPP for the construction site are in place and functioning effectively **and** final stabilization has been achieved on all portions of the construction site for which the operator has operational control. When applicable, long-term responsibility and maintenance requirements for permanent control measures shall be recorded in the local land records prior to the submission of a complete and accurate notice of termination, and the construction record drawing prepared.
- ☐ Another operator has assumed control over all areas of the construction site that have not been finally stabilized and obtained coverage for the ongoing discharge.
- ☐ Coverage under an alternative VPDES permit or other applicable permit has been obtained.
- ☐ For individual lots in residential construction only, final stabilization as defined in 9VAC25-880-1 has been completed, including providing written notification to the homeowner and incorporating a copy of the notification and signed certification statement into the SWPPP, and the residence has been transferred to the homeowner.

CONSTRUCTION GENERAL PERMIT (VAR10) NOTICE OF TERMINATION 2024

Section IV. Participation in a Regional Stormwater Management Plan. If your site discharges to a regional stormwater management facility, provide information related to the regional stormwater management plan. Attach a separate list if discharging to multiple regional facilities.

Regional Stormwater Management Facility Type: _____

Address: _____

City, State, Zip Code: _____

Latitude and Longitude (6-digit, decimal degrees format): _____

Total Site Acres Treated by Regional Facility (report to one-hundredth of an acre): _____

Impervious Site Acres Treated by Regional Facility (report to one-hundredth of an acre): _____

Section V. Perpetual Nutrient Credits. If your site is utilizing nutrient credits, provide information related to the perpetual nutrient credits that were acquired in accordance with § 62.1-44.15:35 of the Code of Virginia. Attach a separate list if needed.

Nonpoint Nutrient Credit Generating Entity (Bank Name): _____

Perpetual Nutrient Credits Acquired (pounds/acres/year): _____

*An affidavit of sale is required for all nutrient credits acquired.

Section VI. Permanent Control Measures. If applicable, list the permanent stormwater management facilities or best management practices (BMPs) that were constructed and installed as part of this activity to comply with the stormwater management water quality and water quantity technical criteria (structural and nonstructural, on-site and off-site). Attach a separate list if needed.

Was a permanent control measure constructed and installed to comply with the stormwater management water quality and water quantity technical criteria? ☐ YES ☐ NO

If you have permanent control measures, the following items are required to be submitted with this form to complete your Notice of Termination submittal:

- ☐ A. [Engineer's Certification Statement](#)
- ☐ B. As-built plans (construction record drawings) – digital
- ☐ C. Stormwater Management Plans - digital
- ☐ D. [BMP Maintenance Agreement](#) (notarized original for projects where DEQ is the VSMP Authority)
- ☐ E. BMP Maintenance Agreement Court Receipt
- ☐ F. Affidavit of Sale for any nutrient credit purchases

CONSTRUCTION GENERAL PERMIT (VAR10) NOTICE OF TERMINATION 2024

Stormwater Management Facility Types (please choose from the following bmp types):

Part V, Article 4 (previously Part IIC) BMPs

Bioretention basin
Bioretention filter
Constructed wetlands
Extended detention (2 x WQ Vol)
Extended detention basin-enhanced
Grassed swale
Infiltration (1 x WQ Vol)
Infiltration (2 x WQ Vol)
Retention basin I (3 x WQ Vol)
Retention basin II (4 x WQ Vol)
Retention basin III (4 x WQ Vol with aquatic bench)
Sand filter
Vegetated filter strip
Other:

- Detention Only BMP
- Forest/Open Space
- Manufactured Treatment Device – Filtering
- Manufactured Treatment Device – Hydrodynamic
- Etc.

Part V, Article 3 (previously Part IIB) BMPs

Bioretention 1
Bioretention 2
Constructed Wetland 1
Constructed Wetland 2
Dry Swale 1
Dry Swale 2
Extended Detention Pond
Extended Detention Pond 2
Filtering Practice 1
Filtering Practice 2
Grass Channel
Infiltration 1
Infiltration 2
Permeable Pavement 1
Permeable Pavement 2
Rooftop Disconnection
Sheet flow to Vegetated Filter or Conserved Open Space 1
Sheet flow to Vegetated Filter or Conserved Open Space 2
Urban Bioretention
Vegetated Roof 1
Vegetated Roof 2
Wet Pond 1
Wet Pond 2
Wet Swale 1
Wet Swale 2
Other:

- Detention Only BMP
- Forest
- Manufactured Treatment Device – Biofilter
- Manufactured Treatment Device – Filtering
- Manufactured Treatment Device – Hydrodynamic
- Regenerative Stormwater Conveyance 1
- Regenerative Stormwater Conveyance 2
- Tree BMP over Impervious
- Tree BMP over Pervious, A/B Soils
- Tree BMP over Pervious, C/D Soils
- Etc.

CONSTRUCTION GENERAL PERMIT (VAR10) NOTICE OF TERMINATION 2024

Stormwater Management Facility #1 BMP Type:	
Date BMP Became Functional:	
Address (if available):	
City and/or County and Zip Code:	
Latitude and Longitude (6-digit, decimal degrees format):	
Receiving Water(s) (outfall discharge):	
Total Acres Treated (report to one-hundredth of an acre):	
Impervious Acres Treated (report to one-hundredth of an acre):	
Stormwater Management Facility #2 BMP Type:	
Date BMP Became Functional:	
Address (if available):	
City and/or County and Zip Code:	
Latitude and Longitude (6-digit, decimal degrees format):	
Receiving Water(s) (outfall discharge):	
Total Acres Treated (report to one-hundredth of an acre):	
Impervious Acres Treated (report to one-hundredth of an acre):	
Stormwater Management Facility #3 BMP Type:	
Date BMP Became Functional:	
Address (if available):	
City and/or County and Zip Code:	
Latitude and Longitude (6-digit, decimal degrees format):	
Receiving Water(s) (outfall discharge):	
Total Acres Treated (report to one-hundredth of an acre):	
Impervious Acres Treated (report to one-hundredth of an acre):	

CONSTRUCTION GENERAL PERMIT (VAR10) NOTICE OF TERMINATION 2024

Section VII. Certification. This Certification must be signed by a person representing the operator identified in Section I. and meeting the requirements of Part III K of 9VAC25-880-70.

Certification: "I certify under penalty of law that I have read and understand this notice of termination and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is to the best of my knowledge and belief true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations."

Printed Name: _____

Signature (signed in ink): _____

Date: _____

Section VIII. Submittal Instructions. Please submit this form to the appropriate Virginia Erosion and Stormwater Management Program (VESMP) authority that has jurisdiction for your construction activity or to DEQ where DEQ serves as the Virginia Stormwater Management Program (VSMP) authority. If the locality is the VESMP Authority, please submit your form directly to the locality; do NOT send this form to DEQ. A list of local VESMP Authorities is available here: [VESMP Authorities](#).

If DEQ is the VSMP Authority, please send to:

Department of Environmental Quality
Office of Stormwater Management Suite 1400
PO Box 1105
Richmond VA 23218
constructiongp@deq.virginia.gov

If the locality is the VESMP Authority, please send to:

Local VESMP Authority (*insert address below*)

Permit terminations may be delayed if there are outstanding Annual Maintenance Fee balances.

CONSTRUCTION GENERAL PERMIT (VAR10) NOTICE OF TERMINATION 2024 INSTRUCTIONS
PLEASE DO NOT PRINT OR SUBMIT

A complete and accurate notice of termination is required for terminating coverage under the General VPDES Permit for Discharges of Stormwater from Construction Activities. Termination shall become effective upon notification from the department that the provisions of termination have been met or 90 days after receipt of a complete and accurate notice of termination, whichever occurs first, unless otherwise notified by the VESMP authority or the department. With terminating coverage, the operator shall submit all permit fees including all outstanding permit maintenance fees in accordance with 9VAC25-875-1290 unless not required.

Permit Coverage Number. Include your existing, active permit coverage number. Example: VAR10####.

Section I. Operator/Permittee Information. The construction activity operator (permittee). The permittee with active permit coverage and that has operational control over the construction activities to ensure compliance with the general permit. For companies, use the complete, active, legal entity name as registered with a state corporation commission. Entities that are considered operators commonly consist of the property owner, developer of a project (the party with direct operational control of construction plans and specifications), or general contractor (the party with day-to-day operational control of the activities at the project site that are necessary to ensure compliance with the general permit). If an individual person is named as the operator, that person (or a representative of) must sign the certification in Section VII.

Section II. Construction Activity Location Information. Project site information. Complete this section with the same information as listed on the current registration statement. A list of active permits and location information is available on the DEQ website.

Section III. Reason for Terminating Coverage under the General Permit. The operator shall submit the notice of termination in accordance with 9VAC25-880-60, unless a registration statement was not required to be submitted in accordance with 9VAC25-880-50 A 1 c or A 2 b for single-family detached residential structures, to the VESMP authority after one or more of the following conditions being met:

1. Necessary permanent control measures included in the SWPPP for the construction site are in place and functioning effectively and final stabilization has been achieved on all portions of the construction site for which the operator has operational control. When applicable, long-term responsibility and maintenance requirements for permanent control measures shall be recorded in the local land records prior to the submission of a complete and accurate notice of termination and the construction record drawing prepared;
2. Another operator has assumed control over all areas of the construction site that have not been finally stabilized and obtained coverage for the ongoing discharge;
3. Coverage under an alternative VPDES permit or other applicable permit has been obtained; or
4. For individual lots in residential construction only, final stabilization as defined in 9VAC25-880-1 has been completed, including providing written notification to the homeowner and incorporating a copy of the notification and signed certification statement into the SWPPP, and the residence has been transferred to the homeowner.

The notice of termination shall be submitted no later than 30 days after one of the above conditions is met. Termination of authorization to discharge shall become effective upon notification of the department of the provisions of this section have been met or 90 days after receipt of a complete and accurate notice of termination, in accordance with 9VAC25-880-60 C, whichever occurs first, unless otherwise notified by the VESMP authority or the department.

Section IV. Participation in a Regional Stormwater Management Plan. Where applicable, include information for each regional stormwater management facility to which this site contributes. If your site is contributing to more than one regional facility, please include the information for each facility in a separate list.

CONSTRUCTION GENERAL PERMIT (VAR10) NOTICE OF TERMINATION 2024 INSTRUCTIONS
PLEASE DO NOT PRINT OR SUBMIT

The following information shall be included for each regional stormwater management facility installed:

- The type of regional facility to which the site contributes (see the list of facility types on page 3 of the notice of termination).
- The location of the facility, including city or county, and latitude and longitude in decimal degrees.
- The number of total and impervious site acres treated by the regional facility to the nearest one-hundredth of an acre.

Section V. Perpetual Nutrient Credits. Where application, the following information related to perpetual nutrient credits that were acquired in accordance with § 62.1-44.15:35 of the Code of Virginia:

- The name of the nonpoint nutrient credit generating entity from which perpetual nutrient credits were acquired, and
- The number of perpetual nutrient credits acquired (pounds per acre per year).

Attach the affidavit(s) of sale for the purchase of all nutrient credits acquired for this activity.

Section VI. Permanent Control Measures. Where applicable, a list of the on-site and off-site permanent control measures (both structural and nonstructural) that were installed to comply with the stormwater management water quality and water quantity technical criteria. Clearly indicate if a permanent control measure was constructed and installed by selecting yes or no. For each permanent measure that was installed, the following information shall be included. Choose the type from the list provided in the notice of termination form Section VI. If you have multiple BMPs, attach a separate list if needed.

The following information shall be included for each permanent control measure installed:

- the type of permanent control measure installed and the date that it became functional as a permanent control measure;
- the location of the permanent control measure, including city or county, and latitude and longitude in decimal degrees (i.e., 37.1234, -77.1234);
- the receiving water(s) to which the permanent control measure discharges; and
- the number of total and impervious acres treated by the permanent control measures to the nearest one-hundredth of an acre.

The following items are required to be submitted with the Notice of Termination if you have permanent control measures:

- [Engineer's Certification Statement](#): Signed by a professional registered in the Commonwealth of Virginia, certifying that the stormwater management facilities were constructed in accordance with the approved plan;
- Construction record drawing(s) (as-built plan) in a format as specified by the VESMP authority for long-term stormwater management facilities in accordance with 9VAC25-875-535 appropriately sealed and signed by a professional registered in the Commonwealth of Virginia, certifying that the stormwater management facilities have been constructed in accordance with the approved plan;
- Stormwater management plans (digital); and
- [BMP Maintenance Agreement](#). Where applicable, evidence that the signed Stormwater Maintenance Agreement has been recorded in an instrument within the local land records; *Termination is not final until you submit the local court record of receipt to DEQ showing that the signed Stormwater Management Maintenance Agreement was recorded with the land deed.*

Section VII. Certification. This Certification must be signed by a person representing the operator identified in Section I and meeting the requirements of Part III K of 9VAC25-880-70.

CONSTRUCTION GENERAL PERMIT (VAR10) NOTICE OF TERMINATION 2024 INSTRUCTIONS
PLEASE DO NOT PRINT OR SUBMIT

Section VIII. Submittal Instructions. Submit this form to the VESMP authority that has jurisdiction for your construction activity. Depending on the location and type of project, the appropriate authority may be either your locality or DEQ where DEQ serves as the VSMP authority. If your project is under the jurisdiction of a local VESMP authority, please contact the locality for additional submittal instructions. A blank area is provided for the local VESMP authority to include their mailing address.

Who is the appropriate stormwater management authority for my project? DEQ or the locality?

DEQ: DEQ is the VSMP Authority and administers permit coverage for land-disturbing activities that are:

- within a locality that is not a VESMP Authority;
- owned by the State or Federal government; or
- utilizing approved Standards and Specifications.

Email the completed and signed form to: constructiongp@deq.virginia.gov

The Locality: The local government (locality) is the VESMP Authority and administers permit coverage for all other projects not covered by DEQ as listed above. For these projects, please submit permit forms directly to the Local VESMP Authority. A list of Local VESMP Authorities is available on DEQ's website here: [Local VESMP Authority List](#).

For assistance or questions about the termination process, email constructiongp@deq.virginia.gov.

Appendix D

Notice of Project Completion

Notice of Project Completion

Construction Activity Operator

Name: _____
Title: _____
Firm: _____
Name: _____
Address: _____

Telephone: _____
Date: _____
Signature: _____

Location of Construction Activity

Name: _____
Title: _____
Firm: _____
Name: _____
Address: _____

Telephone: _____
Date: _____
Signature: _____

Project Completed Certification Under the site specific SWPPP

Certification:

"I certify under penalty of law that in signing this notice of project completion all necessary post-construction control measures included in the SWPPP for the site are in place and functioning effectively and final stabilization has been achieved on all portions of the site for which the operator is responsible."

Name: _____

Title: _____

Date: _____

RLD Signature: _____

Appendix E

Record of Land Disturbance

Record of Land Disturbance

<i>Location (Attach a map showing the location of the activity)</i>	<i>Dates</i>		
	<i>Land Disturbance Began</i>	<i>Land Disturbance Ended</i>	<i>Stabilization Measures Implemented</i>

Appendix F

Record of Inspections

Record of Site Inspection

(Attach as many sheets as necessary, including maps)

<i>Inspection Item</i>	<i>Location</i>	<i>Control Measure</i>			<i>Incident of Non-Compliance (Y/N)¹</i>	<i>Comments</i>	<i>Corrective Measure</i>	<i>Re-Inspection</i>
		<i>Type</i>	<i>Maintenance Req'd (Y/N)</i>	<i>Additional BMP Req'd (Y/N)</i>				
Concrete Washout Area								
Construction Entrance								
Exit								
Silt Fencing								
Stockpile								
Chemical Storage								
Equipment Storage								
Receiving Waterway								
Dry Weather Flow Pumpback								
Runoff Appearance								
Tree Protection								

<i>Inspection Item</i>	<i>Location</i>	<i>Control Measure</i>			<i>Incident of Non-Compliance (Y/N)¹</i>	<i>Comments</i>	<i>Corrective Measure</i>	<i>Re-Inspection</i>
		<i>Type</i>	<i>Maintenance Req'd (Y/N)</i>	<i>Additional BMP Req'd (Y/N)</i>				
Dust Control								
Dewatering Methods								
Safety Fencing								
Straw Bales								
Storm Drain Inlet Protection								
Topsoiling								
Temporary & Permanent Seeding								
Soil Stabilization Blanket Matting								
<i>Receiving Channel</i>								

Name: _____ Title: _____ Date: _____

Signature: _____

¹If no incidents of Non-Compliance have been noted above, I certify that the site complies with the provisions of this SWPPP and Permit.

²Blank lines should be used for additional inspection items including potential pollutants and items defined by owner.

Record of Potential Construction Site Pollutants

<i>Material/Chemical</i>	<i>Physical Description</i>	<i>Stormwater Pollutant</i>	<i>Location</i>

Appendix G

Record of Contractor Certification

Record of Contractor Certification

"I certify under penalty of law that I understand the terms and conditions of this Virginia Stormwater Management Program (VSMP) general permit that authorizes the storm water discharges from the construction activity identified as part of this certification."

Site: _____

Contractor No. _____
Name: _____
Title: _____
Firm: _____
Address: _____

Telephone: _____
Date: _____
Signature: _____

Contractor No. _____
Name: _____
Title: _____
Firm: _____
Address: _____

Telephone: _____
Date: _____
Signature: _____

Appendix H

Water Quality Protection

Water Quality Protection

<i>Permanent BMP Description</i>	<i>Geographic Location</i>	<i>Water body Discharge</i>	<i>Acres Treated</i>


Appendix I

Details of Best Management Practices

7.3 Overview of Best Management Practices

































The following are summary overviews of the construction BMPs specified for use in Virginia. Complete standards and specifications for these practices are included in this chapter.

The construction BMPs are numbered and categorized in the following subsections.

 [Download File](#) – CAD and PDF files for Chapter 7.3



























7.3.1 Erosion Control Measures – C-ECM

These construction BMPs are intended to prevent sheet, rill and gully erosion. These BMPs reduce the overland flow velocities, shorten the length of flow, and divert and convey runoff safely through the site.

EROSION CONTROL MEASURES		
C-ECM-01 STRAW WATTLES		
C-ECM-02 IMPERMEABLE DIVERSION FENCE		
C-ECM-03 SLOPE INTERRUPTION DEVICE		
C-ECM-04 TEMPORARY DIVERSION DIKE		
C-ECM-05 DIVERSION		
C-ECM-06 TEMPORARY FILL DIVERSION		
C-ECM-07 TEMPORARY RIGHT-OF-WAY DIVERSION		
C-ECM-08 WATERBARS AND SHEET FLOW BREAKERS		
C-ECM-09 STORMWATER CONVEYANCE CHANNEL		
C-ECM-10 SUBSURFACE DRAIN		
C-ECM-11 PAVED FLUME		
C-ECM-12 TEMPORARY SLOPE DRAIN		
C-ECM-13 RIPRAP		
C-ECM-14 TEMPORARY LEVEL SPREADER		
C-ECM-15 OUTLET PROTECTION		
C-ECM-16 FLEXIBLE TRANSITION MAT		























7.3.2 Sediment Control Measures – C-SCM

These construction BMPs are intended to prevent sediment transported by surface flows from leaving the site. These BMPs typically provide a means to capture or filter sediment practices.

SEDIMENT CONTROL MEASURES		
C-SCM-01 DUST CONTROL		
C-SCM-02 CONSTRUCTION ROAD STABILIZATION		
C-SCM-03 TEMP STONE CONSTRUCTION ENTRANCE		
C-SCM-04 INLET PROTECTION		
C-SCM-05 CULVERT INLET PROTECTION		
C-SCM-06 WOOD CHIP FILTER BERM		
C-SCM-07 ROCK CHECK DAMS		
C-SCM-08 ROCK FILTER OUTLET		
C-SCM-09 TURBIDITY CURTAIN		
C-SCM-10 DEWATERING STRUCTURE		
C-SCM-11 TEMPORARY SEDIMENT TRAP		
C-SCM-12 TEMPORARY SEDIMENT BASIN		
C-ECM-13 CONCRETE WASHOUT PIT		











7.3.3 Surface Stabilization Measures – C-SSM

These construction BMPs are intended for use where final grade has been established to protect disturbed soil from surface runoff. The BMPs include both temporary covering and permanent vegetative cover that can become part of the final landscape.

SURFACE STABILIZATION MEASURES		
C-SSM-01 TREE PRESERVATION AND PROTECTION		
C-SSM-02 TOPSOILING		
C-SSM-03 SURFACE ROUGHENING		
C-SSM-04 COMPOST BLANKETS		
C-SSM-05 SOIL STABILIZATION BLANKETS AND MATTING		
C-SSM-06 SODDING		
C-SSM-07 BERMUDAGRASS AND ZOYSIAGRASS ESTABLISHMENT		
C-SSM-08 TREES, SHRUBS, VINES, AND GROUND COVER		
C-SSM-09 TEMPORARY SEEDING		
C-SSM-10 PERMANENT SEEDING		
C-SSM-11 MULCHING		

7.3.4 Perimeter Control Measures – C-PCM































These construction BMPs are intended to intercept sheet flow from slopes and remove sediment and other contaminants through ponding, settling, and physical filtration, effectively preventing contaminants from leaving the site and entering surface waters.

PERIMETER CONTROL MEASURES		
C-PCM-01 SAFETY FENCE		
C-PCM-02 STRAW BALE BARRIER		
C-PCM-03 BRUSH BARRIER		
C-PCM-04 SILT FENCE		
C-PCM-05 COMPOST FILTER SOCK		

7.3.5 Environmentally Sensitive Area Protection – C-ENV

These construction BMPs are intended for use in environmentally sensitive areas, typically stream corridors, wetlands, and floodplains. These BMPs are typically applied where crossing or working within an

environmentally sensitive area is necessary.

ENVIRONMENTAL SENSITIVE AREA PROTECTION		
C-ENV-01 VEGETATIVE STREAMBANK STABILIZATION		
C-ENV-02 STRUCTURAL STREAMBANK STABILIZATION		
C-ENV-03 TEMPORARY VEHICULAR STREAM CROSSING		
C-ENV-04 UTILITY STREAM CROSSING		
C-ENV-05 COFFERDAM CROSSING		
C-ENV-06 STABLE WETLAND CROSSING		
C-ENV-07 GABIONS/GABION DEFLECTORS		
C-ENV-08 PUMP AROUND DIVERSION		
C-ENV-09 OVERNIGHT CHANNEL PROTECTION		
C-ENV-10 TRENCHLESS SILT FENCE		
C-ENV-11 WETLAND BERM		
C-ENV-12 WETLAND WEIR OUTLET		
C-ENV-13 WETLAND CELL SEDIMENT TRAP		
C-ENV-14 MODIFIED TURBIDITY CURTAIN FOR STREAMS		
C-ENV-15 SEEDING, MULCHING, AND SOIL STABILIZATION WETLANDS STREAMS		

Designate Washout Areas

Instructions

Describe location(s) and controls to eliminate the potential for discharges from washout areas for concrete mixers, paint, stucco, and so on.

BMP Description

A designated temporary, above-grade concrete washout area *will be coordinated with the owner*. The temporary concrete washout area could be constructed as shown in the figure below, with a recommended minimum length and minimum width of 10 feet and with sufficient quantity and volume to contain all liquid and concrete waste generated by washout operations. The washout area will be lined with plastic sheeting at least 10 mils thick and free of any holes or tears. Signs will be posted marking the location of the washout area to ensure that concrete equipment operators use the proper facility.


Concrete pours will not be conducted during or before an anticipated storm event. Concrete mixer trucks and chutes will be washed in the designated area or concrete wastes will be properly disposed of off-site. When the temporary washout area is no longer needed for the construction project, the hardened concrete and materials used to construct the area will be removed and disposed of according to the maintenance section below, and the area will be stabilized.

Installation Schedule

The washout area will be constructed before concrete pours occur at the site.

Maintenance and Inspection

The washout areas will be inspected daily to ensure that all concrete washing is being discharged into the washout area, no leaks or tears are present, and to identify when concrete wastes need to be removed. The washout areas will be cleaned out once the area is filled to 75 percent of the holding capacity. Once the area's holding capacity has been reached, the concrete wastes will be allowed to harden; the concrete will be broken up, removed, and taken to a nearby Landfill for disposal. The plastic sheeting will be replaced if tears occur during removal of concrete wastes from the washout area.



Design Specifications:

1. Temporary concrete washout type Above Grade will be constructed as shown above, with a recommended minimum length and minimum width of 10 feet.
2. The washout will be a minimum of 50 feet from storm drain inlets.
3. Plastic lining will be free of holes, tears, or other defects that compromise the impermeability of the material.

Responsible Staff: Contractor

Appendix J

ESC & SWM Approval Letters

Appendix K

Site Plans (11" x 17"

reductions)

Appendix L

Amendment Log

SWPPP Amendment Log

Instructions: Include additions of new BMPs, replacement of failed BMPs, significant changes in the activities or the timing of the project, changes in personnel, changes in inspection and maintenance procedures, and updates to site maps, etc.

<i>Date Changed</i>	<i>Concern</i>	<i>Actions Taken</i>	<i>Completed By</i>	<i>Signature</i>

Appendix D:

Non-VSMH Specifications

Table of Contents

Table of Contents	1
1. Construction Entrance & Construction Road Stabilization	1
Alturnamats & Versamats.....	1
2. Inlet Protection	8
Dandy Bag, Curb, Curb Bag, Curb Sack, and Sack	8
Erosion Eel and Gutter Buddy	13
Silt Sack	16

1. Construction Entrance & Construction Road Stabilization

Alturnamats & Versamats

Definition

Temporary protective matting employed to provide ingress and egress throughout the construction site.

Purpose

The mats provide vehicular access while protecting the existing ground cover.

Conditions Where Practice Applies

Temporary protective mats are typically used in areas in which installing a temporary stone construction entrance/road is not feasible and/or in situations where access will be needed for a relatively short period of time.

Planning Considerations

Provisions must be made on construction sites to minimize the transport of sediment by vehicular traffic onto a paved surface per Minimum Standard #17. The use of temporary matting prevents vehicles from disturbing unpaved, grassed, and/or denuded areas. As a result, the matting reduces the amount of mud picked up by construction vehicles.

Construction Specifications

1. Install mats where temporary access is needed.
2. Join mats together using links to ensure the mats do not shift.



ALTURNAMATS® GROUND PROTECTION MATS

The Original Ground Protection Mats Featuring Maximum Traction Diamond Plate Tread Design

These rugged mats are made of 1/2" thick polyethylene so they are virtually indestructible. They withstand vehicles weighing up to 120 tons, bend but do not break and feature a Limited Lifetime Warranty. AlturnaMATS® have been tested in record cold and heat. AlturnaMATS® are an environmentally friendly mat as they are made from recycled plastic materials.

With AlturnaMATS®, getting stuck is virtually eliminated. They are available smooth on one side or smooth on both sides, ideal for removing dirt or gravel.



ALTURNAMATS® FEATURES:

- Easily supports 120 ton vehicles
- Rugged 1/2" thick polyethylene
- Bold cleat design for great traction
- Build a roadway or working platform in minutes
- Leave turf smooth, even in soft conditions
- No more splintered, warped, water logged plywood
- Simply hosing down leaves the mats clean
- Available in black, white and clear mats
- Mats can be locked together with Turn-A-Links forming a continuous roadway
- Limited Lifetime Warranty



Diamond Plate Tread

ALTURNAMATS® BUILT TOUGH!



SIZES TO SUIT YOUR NEEDS

BLACK	WHITE	APPROX. SHIP WEIGHT
4' x 8' (1.22 x 2.44m)	4' x 8' (1.22 x 2.44m)	86.00 lb. (39.00 kg.)
3' x 8' (0.91 x 2.44m)	3' x 8' (0.91 x 2.44m)	64.50 lb. (29.25 kg.)
3' x 6' (0.91 x 1.83m)	3' x 6' (0.91 x 1.83m)	51.00 lb. (23.13 kg.)
2' x 8' (0.61 x 2.44m)	2' x 8' (0.61 x 2.44m)	43.00 lb. (19.50 kg.)
2' x 6' (0.61 x 1.83m)	2' x 6' (0.61 x 1.83m)	32.25 lb. (14.62 kg.)
2' x 4' (0.61 x 1.22m)	2' x 4' (0.61 x 1.22m)	21.50 lb. (9.75 kg.)



LANDSCAPING



TREE CARE



CONSTRUCTION



CONCRETE



S

MATRAX • 855-575-7512 • www.matraxinc.com

SAFETY TECH PADS ONE PIECE PLASTIC OUTRIGGER PADS

Delivering the safety, quality and performance you expect from the industry leader.

SAFETY TECH PADS FEATURES:

- Reliable Load Distribution
- Lightweight
- Safety Texturing
- Memory Recovery
- Lifetime Guarantee



STANDARD PADS


MODEL	LOAD VERTICAL	45° ANGLE	WIDTH	LENGTH	HEIGHT	WEIGHT	SQUARE INCH
PAD15151.75	40,000 lb. (KG20,412)	18,000 lb. (KG9,072)	15 in. (C38.1)	15 in. (C1.905)	.75 in. (C2.54)	5.5 lb. (KG3.40)	225 (CT1,451.70)
PAD18181	55,000 lb. (KG24,948)	30,000 lb. (KG13,608)	18 in. (C45.72)	18 in. (C45.72)	1 in. (C2.54)	11 lb. (KG4.99)	324 (CT2,090.45)
PAD24241	60,000 lb. (KG27,216)	35,000 lb. (KG15,876)	24 in. (C60.96)	24 in. (C60.96)	1 in. (C2.54)	20 lb. (KG9.07)	576 (CT3,761.36)
PAD24242	62,000 lb. (KG28,123)	40,000 lb. (KG18,144)	24 in. (C60.96)	24 in. (C60.96)	2 in. (C5.08)	38 lb. (KG17.24)	576 (CT3,761.36)
PAD30301	81,000 lb. (KG36,741)	41,000 lb. (KG18,597.6)	30 in. (C76.2)	30 in. (C76.2)	1 in. (C2.54)	31 lb. (KG14.06)	900 (CT5,806.8)
PAD36361	93,000 lb. (KG42,184.8)	43,000 lb. (KG19,504.8)	36 in. (C91.44)	36 in. (C91.44)	1 in. (C2.54)	45 lb. (KG20.41)	1296 (CT8,361.79)
PAD48481	135,000 lb. (KG61,236)	52,000 lb. (KG23,587.2)	48 in. (C121.92)	48 in. (C121.92)	1 in. (C2.54)	80 lb. (KG36.29)	2304 (CT14,865.4)
PAD30302	85,000 lb. (KG38,556)	43,000 lb. (KG19,504.8)	30 in. (C76.2)	30 in. (C76.2)	2 in. (C5.08)	62 lb. (KG28.12)	900 (CT5,806.8)
PAD36362	98,000 lb. (KG44,252.8)	45,000 lb. (KG20,412)	36 in. (C91.44)	36 in. (C91.44)	2 in. (C5.08)	90 lb. (KG40.83)	1296 (CT8,361.79)
PAD48482	140,000 lb. (KG63,504)	55,000 lb. (KG24,948)	48 in. (C121.92)	48 in. (C121.92)	2 in. (C5.08)	160 lb. (KG72.58)	2304 (CT14,865.4)

*6" x 10" Outrigger Leg applied under two separate conditions: 10,000# vertically and 10,000# with a 45 degree angle.

**TuffGrip Handle located on width side of all pads. Pads 900 sq. in. or larger have two or more handles or more handles opposite each other.

Custom size pads available. Requires a minimum order. Lead time for non-stock items is 30-45 days.

KEY: C = Centimeters; KG = Kilograms; CT = Square Centimeters



Safety Texture



MANUF. HOUSING



REC AREAS/EVENTS



TRENCHING



SEPTIC PUMPING

MATRAX • 855-575-7512 • www.matraxinc.com



AlturnaMATS® & VersaMATS®

AlturnaMATS® & VersaMATS® each leave turf smooth, even under heavy vehicle traffic. No costly turf repair bills and you'll Never Get Stuck Again.

ADVANTAGES:

- AlturnaMATS: Featuring a bold diamond plate tread for maximum traction.
- VersaMATS: Featuring a flat, slip-resistant tread on one side designed for pedestrian traffic, and the bold diamond plate tread on the other side for vehicle traffic.
- Limited Lifetime Warranty

These mats virtually eliminate damage to lawns and landscaped areas throughout the world... from North America, Asia, Australia, Europe, to even Antarctica. These rugged mats are the popular choice among professionals. They are easy to use. Lock into place to form a continuous, solid roadway or work platform and they last for years. They are unequalled for quality and performance under the most hazardous conditions.

Each mat can be used in a broad variety of applications such as construction, golf courses, utilities, landscaping, tree care, cemeteries, drilling, sewage...wherever saving the costs of ground restoration is a factor. And they are great to save heavy vehicles from getting stuck in mud.

AlturnaMATS and VersaMATS provide locking links designed of steel to fit into holes on each end of the mats, locking them end-to-end to create a continuous roadway, or you can easily create a large platform for working vehicles.

**EASY TO WALK ON... SAFE TO WORK ON...
GREAT TO DRIVE ON PLUS...
PERFECT FOR STORING MATERIALS
ON WORK SITE AND OUT OF THE MUD**



DON'T GET STUCK IN A RUT!

Now there is no reason to create ruts such as shows here after a stumpster traversed this front lawn. The owner had the ruts repaired at a cost of \$1,800 and needless to say, never used the tree removal company again.



MATRAX • 855-675-7512 • www.matraxinc.com

ALTURNAMATS® ACCESSORIES

TURN-A-LINKS

Steel links lock mats together to form a semi-permanent, yet portable, continuous roadway, walkway or working platform. The same steel material, but with a galvanized coating: easier to locate & harder to rust.



Single Turn-a-Link



Double Turn-a-Link




Galvanized Turn-A-Link: Single or Double



EZ-LINK SYSTEM

E-Z Links are a quick & convenient linking system for the AlturnaMATS® VersaMATS®. The links are available in single or double, & are suitable for pedestrian applications as well as movement of light, compact equipment (Less than 12,000 GVW) when on stable ground conditions.



Single E-Z Link


DESCRIPTION	ITEM NUMBER	SHIP WEIGHT
SINGLE ROUND LINK	RTL-S-G	8 oz.
DOUBLE ROUND LINK	RTL-D-G	20 oz.
SINGLE FLAT LINK	FTL-SG	8 oz.
DOUBLE FLAT LINK	FTL-DG	20 oz.
SINGLE EZ LINKS	EZL-S	4 oz.
DOUBLE EZ LINKS	EZL-D	6 oz.

MAT-PAK

This complete package is the handy way to transport and store your AlturnaMATS®.

Pak Consists of:

- 12 Mats (4' x 8' or 3' x 8')
- 1 Metal storage, skid rack
- 20 Single Turn-A-Links
- 2 Handi-Hooks
- 2 Ratchet Straps



MAT-PAK DIAMOND PLATE	ITEM NO.	WEIGHT
Black - 4' x 8' Package	AMCP4	1126 lbs.
Black - 3' x 8' Package	AMCP3	868 lbs.
White - 4' x 8' Package	WMCP4	1126 lbs.
White - 3' x 8' Package	WMCP3	868 lbs.
MAT-PAK VERSAMATS®	ITEM NO.	WEIGHT
Black - 4' x 8' Package	VMCP4	1126 lbs.
Black - 3' x 8' Package	VMCP3	868 lbs.
White - 4' x 8' Package	WVCP4	1126 lbs.
White - 3' x 8' Package	WVCP3	868 lbs.

HANDI-HOOKS

AlturnaMATS® Handi-Hooks make moving mats easier, even in wet areas. Made of steel rod, painted white.

LENGTH	WEIGHT
3' (91.44cm)	2.5 lbs. (1.13kg)



Manufactured by
CHECKERS®
INDUSTRIAL SAFETY PRODUCTS

To view our full line of Safety Products, visit us at
www.matraxinc.com or call 1-855-575-7512.



Maintenance/Inspections

The matting shall be maintained in a condition which will prevent tracking or flow of mud onto public rights-of-way. All materials spilled, dropped, washed, or tracked from vehicles onto roadways or into storm drains must be removed immediately. Inspect the matting to ensure adjoining pieces do not separate. The use of water trucks to remove materials dropped, washed, or tracked onto roadways is not be permitted under any circumstances. If matting begins to separate, adjust or align the entrance/road as necessary.

2. Inlet Protection

Dandy Bag, Curb, Curb Bag, Curb Sack, and Sack

Definition

A sediment filter around a storm drain drop inlet or curb inlet.

Purpose

To prevent sediment from entering storm drainage systems prior to permanent stabilization of the disturbed area.

Conditions Where Practice Applies

Where storm drain inlets are to be made operational before permanent stabilization of the corresponding disturbed drainage areas.

Planning Considerations

Storm sewers which are made operational prior to stabilization of the associated drainage areas can convey large amounts of sediment to natural drainageways. In cases of extreme sediment loading, the storm sewer itself may clog and lose a major portion of its capacity. To avoid these problems, it is necessary to prevent sediment from entering the system at the inlets.

This practice contains several types of inlet filters and traps which have different applications dependent upon site conditions and type of inlet. The following inlet protection devices are for drainage areas of one acre or less.


Design Criteria

1. Drainage area shall be no greater than 1 acre.
2. The inlet protection device shall be constructed in a manner that will facilitate clean-out and disposal of trapped sediment and minimize interference with construction activities.
3. The inlet protection measure shall be appropriately sized to prevent stormwater from unintentionally bypassing the protection measure.

Construction Specifications


Dandy Bag

1. Place the empty Dandy Bag over the grate as the grate stands on end.
2. Tuck the enclosure flap inside to completely enclose the grate.
3. Holding the lifting devices, insert the grate into the inlet being careful not to damage the Dandy Bag unit.




Dandy Curb

1. Place Dandy Curb inlet protection unit on ground with aggregate pouch on street side near inlet it will be installed on.
2. Fill pouch with aggregate such as #5-7, 8's or similar to a level (at least $\frac{1}{2}$ full) that will keep unit in place during a rain event and create a seal between the Dandy Curb and the surface of the Street. Reseal Velcro access.
3. Center the unit against curb or median inlet opening so that the curb side of the unit creates a seal with the curb or median barrier and inlet structure. There will be approximately twelve (12) inches of inlet protection unit overhanging on each side of the opening. If the unit is not installed in this manner, it will not function properly.




Dandy Curb Bag

1. Place the empty Dandy Curb Bag unit over the grate as the grate stands on end.
2. Tuck the enclosure flap inside to completely enclose the grate.
3. Holding the lifting devices, being careful not to damage the sewn fabric unit, insert the grate into its frame, street side edge first, then lower back edge with cylindrical tube into place. The cylindrical tube should be partially blocking the curb hold opening when installed properly.




Dandy Curb Sack

1. Remove the grate from the catch basin.
2. Stand the grate on end. Move the top lifting straps out of the way and place the grate into the Dandy Curb Sack unit so that the grate is below the top straps and above the lower straps. The grate should be cradled between the upper and lower straps.
3. Holding the lifting devices, insert the grate into the inlet, then lower back edge with cylindrical tube into place, being careful that the grate remains in place and being careful not to damage the Dandy Curb Sack unit. The cylindrical tube should partially block the curb hood opening when installed properly.



Dandy Sack

1. Remove the grate from the catch basin.
2. Stand the grate on end. Move the top lifting straps out of the way and place the grate into the Dandy Sack unit so that the grate is below the top straps and above the lower straps. The grate should be cradled between the upper and lower straps.
3. Holding the lifting devices, insert the grate into the inlet, being careful that the grate remains in place and being careful not to damage the Dandy Sack unit.



Maintenance/Inspections

1. Structures shall be inspected after each runoff producing rain event and repairs shall be made as needed.
2. Sediment shall be removed as necessary. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
3. Replace the inlet protection measure if any rips, tears, or holes are found.

Erosion Eel and Gutter Buddy

Definition

A sediment filter around a storm drain drop inlet or curb inlet.

Purpose

To prevent sediment from entering storm drainage systems prior to permanent stabilization of the disturbed area.

Conditions Where Practice Applies

Where storm drain inlets are to be made operational before permanent stabilization of the corresponding disturbed drainage areas.

Planning Considerations

Storm sewers which are made operational prior to stabilization of the associated drainage areas can convey large amounts of sediment to natural drainageways. In case of extreme sediment loading, the storm sewer itself may clog and lose a major portion of its capacity. To avoid these problems, it is necessary to prevent sediment from entering the system at the inlets.

This practice contains several types of inlet filters and traps which have different applications dependent upon site conditions and type of inlet. The following inlet protection devices are for drainage areas of one acre or less.


Design Criteria

1. Drainage area shall be no greater than 1 acre.
2. The inlet protection device shall be constructed in a manner that will facilitate clean-out and disposal of trapped sediment and minimize interference with construction activities.
3. The inlet protection measure shall be appropriately sized to prevent stormwater from unintentionally bypassing the protection measure.

Construction Specifications


Erosion Eel

1. Place Erosion Eel at curb inlet. Bed the Eel in a jute mesh (or Floccmat) cradle.
2. If more than one Erosion Eel is placed in a row, install the Eels by firmly butting the sewn end against the tied end of the Eels together to form a butt joint. No wraps are required around the joint locations.
3. Eels shall be installed where the handles will be positioned at the very top of the bag.



Gutter Buddy

1. Choose an appropriately sized Gutter Buddy and Install the measure in front of the curb inlet.
2. Ensure the Gutter Buddy overlaps a minimum of 12" beyond the throat opening.



Maintenance/Inspections

1. Structures shall be inspected after each runoff producing rain event and repairs shall be made as needed.
2. Sediment shall be removed, and the protection device restored to its original dimensions when sediment has accumulated to one half the design depth of the trap. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
3. Replace the inlet protection measure if any rips, tears, or holes are found.

Silt Sack

Definition

A sediment filter around a storm drain drop inlet or curb inlet.

Purpose

To prevent sediment from entering storm drainage systems prior to permanent stabilization of the disturbed area.

Conditions Where Practice Applies

Where storm drain inlets are to be made operational before permanent stabilization of the corresponding disturbed drainage areas.

Planning Considerations

Storm sewers which are made operational prior to stabilization of the associated drainage areas can convey large amounts of sediment to natural drainageways. In case of extreme sediment loading, the storm sewer itself may clog and lose a major portion of its capacity. To avoid these problems, it is necessary to prevent sediment from entering the system at the inlets.



This practice contains several types of inlet filters and traps which have different applications dependent upon site conditions and type of inlet. The following inlet protection devices are for drainage areas of one acre or less.

Design Criteria

1. The drainage area shall be no greater than 1 acre.
2. The inlet protection device shall be constructed in a manner that will facilitate clean-out and disposal of trapped sediment and minimize interference with construction activities.
3. The inlet protection measure shall be appropriately sized to prevent stormwater from unintentionally bypassing the protection measure.


Construction Specifications

1. Remove the grate and place the sack in the opening. Hold approximately six inches of the sack outside the frame. This is the area of the lifting straps.
2. Replace the grate to hold the sack in place.



ACF
ENVIRONMENTAL
2831 Cardwell Road
Richmond, VA 23234
WWW.ACFENVIRONMENTAL.COM

ACF
ENVIRONMENTAL
2831 Cardwell Road
Richmond, VA 23234
WWW.ACFENVIRONMENTAL.COM



ACF
ENVIRONMENTAL
2831 Cardwell Road
Richmond, VA 23234
WWW.ACFENVIRONMENTAL.COM

Maintenance/Inspections

1. Inlet protection shall be inspected immediately after each runoff producing rain event.
2. Check for tears, rips, or holes in sack. If noticed, have replaced immediately.
3. When the restraint cord is no longer visible, the Silt Sack is full and should be emptied.
4. To remove the Silt Sack, take two pieces of 1" diameter rebar and place through the lifting loops on each side of the sack to facilitate the lifting of the Silt Sack.
5. To empty the Silt Sack, place the unit where the contents will be collected. Place the rebar through the lift straps and lift. This will lift the bottom and empty the contents. Clean out and rinse. Return the Silt Sack to its original shape and place back in the basin.
6. Silt Sacks are reusable. Once the construction cycle is complete, remove the Silt Sack from the basin and clean. Silt Sacks should be stored out of sunlight until next use.

Appendix E:

ESC and SWM Plan Approval Letter



Environmental Health and Safety
2501 Spong Hall
Norfolk, VA 23529
Phone: 757.683.4495
dalexander@odu.edu

Douglas Alexander
Director
Department of Environmental
Health and Safety
Old Dominion University
Norfolk, VA 23529

RE: Erosion & Sediment Control (ESC) and Stormwater Management (SWM) Plan Approval

To Whom It May Concern:

Thank you for preparing plans for ESC and SWM review. The plans submitted by _____ for the _____ project dated _____ were reviewed by an ODU representative for compliance and found to be in accordance with the Virginia Erosion and Stormwater Management Act, Virginia Erosion and Stormwater Management Regulations, attendant regulations, and ODU's approved Standards and Specifications for ESC and SWM. Based upon the representative's recommendation, ODU approves the plans for ESC and SWM.

Please note that approval does not relieve the operator of complying with all other federal, state, or local laws and regulations. It is the responsibility of the operator to ensure that the project is constructed in accordance with the approved plans and accompanying specifications.

Land-disturbing activities may commence after:

- A pre-construction meeting is held including the ODU Project Manager, the general construction permit operator, the RLD, and any other necessary parties
- If the project disturbance is over one acre, coverage under the Department of Environmental Quality (DEQ) Virginia Pollutant Discharge Elimination System (VPDES) Construction General Permit will be required. If coverage is required, confirmation of coverage shall be provided to ODU
- If applicable, all other required regulatory approval has been received

A copy of the approved ESC and SWM plans shall be kept on site and made available. No changes shall be made to the plans unless in accordance with ODU's Standards and Specifications.

If you have any questions, please feel free to contact me.

Regards,

Douglas Alexander
Director
Department of Environmental
Health and Safety

Appendix F: Standards and Specifications Information Sheet

**VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY
STANDARDS & SPECIFICATION (S&S) ENTITY INFORMATION SHEET**

1. Standards & Specifications Entity:	
2. S&S Coverage Verification	
a. Operator:	
b. Project name:	
c. Estimated Area to be Disturbed (acres):	
3. Plan Approval Verification	
a. Erosion & Sediment Control (ESC) Plan	
i. ESC Plan Reviewer Name and Certification Number:	
ii. ESC Plan Date:	
iii. ESC Plan Approval Date:	
b. Stormwater Management (SWM) Plan	
i. Technical Criteria Used:	
ii. SWM Plan Reviewer Name and Certification Number:	
iii. SWM Plan Date:	
iv. SWM Plan Approval Date:	
4. Comments:	

Printed Name:	Title:
Signature:	Date:

(Please sign in ink. This must be signed by an employee of the S&S entity who has oversight of this project and is aware of its coverage under their S&S.)

(Retain a copy of this form onsite and within project specific S&S files.)

**VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY
STANDARDS & SPECIFICATION (S&S) ENTITY INFORMATION SHEET
INSTRUCTIONS FOR COMPLETION (*DO NOT PRINT OR SUBMIT*)**

1. S&S Entity/Holder Name: Name as it appears on the S&S Approval Letter.

2.a. Operator: Owner, operator, developer, person, or general contractor that the S&S holder is allowing to operate under their DEQ approved S&S.

2.b. Project Name: Name of the construction activity as it appears on the registration statement.

2.c. Estimated Area to Be Disturbed: Provide the estimated area (to the nearest one-hundredth acre) to be disturbed by the construction activity. Include the estimated area of land disturbance that will occur at any off-site support activity to be covered under this general permit.

3.a.i. ESC Plan Reviewer Name and Certification Number: S&S ESC Plans are required to be reviewed and approved by a DEQ-Certified ESC Plan Reviewer. Provide the name and certification number of the qualified individual.

3.a.ii. ESC Plan Date: Provide the plan date of the approved ESC Plan.

3.a.iii. ESC Plan Approval Date: Provide the date the ESC Plan was approved by the review authority.

3.b.i. Technical Criteria Used: The technical criteria used for this project, which should be either Part V of Article 3 or Part V of Article 4 (previously Part IIB or Part IIC, respectively) per the Virginia Erosion and Stormwater Management Regulation, 9VAC25-875.

3.b.ii. SWM Plan Reviewer Name and Certification Number: S&S SWM Plans are required to be reviewed and approved by a DEQ-Certified SWM Plan Reviewer. Provide the name and certification number of the qualified individual.

3.b.iii. SWM Plan Date: Provide the plan date of the approved SWM Plan.

3.b.iv. SWM Plan Approval Date: Provide the date the SWM Plan was approved by the review authority.

(Further questions can be directed to StandardsandSpecs@deq.virginia.gov)

Appendix G: General Erosion and Sediment Control Notes

General Erosion and Sediment Control Notes

ES-1 - Unless otherwise indicated, all vegetative and structural erosion and sediment control practices shall be constructed and maintained according to minimum standards and specifications of the Virginia Stormwater Management Handbook and 9VAC25-875 Virginia Erosion and Stormwater Management Regulation.

ES-2 – The plan approving authority (ODU Director of Environmental Health and Safety) must be notified at least one week prior to the pre-construction conference, one week prior to commencement of land disturbing activity and one week prior to final inspection. The name of the certified responsible land disturber, including their certification number and contact information must be provided to the plan approving authority prior to actual engagement in land disturbing activity.

ES-3 – All erosion and sediment control measures shall be placed prior to or as a first step in clearing.

ES-4 – A copy of the approved ESC plan shall be maintained on the site at all times.

ES-5 – Prior to commencing land disturbing activities in areas other than indicated on these plans (including, but not limited to, off-site borrow or waste areas), the contractor shall submit a supplementary erosion control plan to the ODU Director of Environmental Health and Safety or representative of the Director for review and approval.

ES-6 – Include a completed and signed ESC/SWM Plan Preparer/Reviewer Checklist.

ES-7– The contractor is responsible for installation of any additional erosion control measures necessary to prevent erosion and sedimentation as determined by the plan approving authority.

ES-8 – All disturbed areas are to drain to approved sediment control measures at all times during land disturbing activities and during site development until final stabilization is achieved, after which, upon approval of the plan approving authority, the controls shall be removed. Trapped sediment and the disturbed soil areas resulting from the removal of temporary measures shall be permanently stabilized.

ES-9 – During dewatering operations, water shall be pumped into an approved filtering device.

ES-10 –The contractor shall inspect all erosion control measures at least once in every two-week period and within 48 hours following any runoff producing storm event. The operator shall inspect in accordance with the Construction General Permit requirements when applicable. Any necessary repairs or cleanup to maintain the effectiveness of the erosion control devices shall be made immediately. The contractor shall submit evidentiary of inspection reports to the owner or within the Stormwater Pollution Prevention Plan (SWPPP).

ES-11 – The contractor is responsible for the removal of sediment that has been transported onto paved or public roads. At a minimum, tracking shall be cleaned by the end of each work day.

ES-12 – Temporary or Permanent stabilization operations shall be initiated within 7 days after reaching final grade or upon suspension of grading operations for anticipated duration of greater than 14 days or upon completion of grading operations for a specific area.

ES-13 – The contractor shall be responsible for preventing surface and air movement of dust from exposed soils.

Appendix H: ESC and SWM Plan Submitter's Checklist

ESC and SWM Plan Submitter's Checklist

1. General

_____ **1.1 Complete Set of Plans and Supporting Documentation** - Include all sheets pertaining to the site grading and stormwater and any activities impacting erosion and sediment control and drainage:

- ☐ Existing Conditions
- ☐ Demolition
- ☐ Site Grading
- ☐ Erosion and Sediment Control
- ☐ Storm sewer systems
- ☐ Stormwater management facilities
- ☐ Landscaping
- ☐ On-site and off-site borrow and disposal areas that do not have separate approved ESC Plans
- ☐ Calculations

_____ **1.2 Professional's Seal** - The designer's original seal, signature, and date are required on the cover sheet of each Narrative and each set of Plan Sheets. A facsimile is acceptable for subsequent Plan Sheets.

_____ **1.3 Number of Plan Sets** - A pdf set of ESC/SWM Plans are to be submitted.

_____ **1.4 Variances** - Variances requested at the time of plan submission are governed by Section 9VAC25-875-350 of the Virginia Erosion and Stormwater Management Regulation and Old Dominion University Standards and Specifications for ESC and SWM.

_____ **1.5 Completed Plan Preparer/Reviewer Checklist** - Include a completed and signed ESC/SWM Plan Preparer/Reviewer Checklist.

_____ **1.6 Plan Compliance Table** - Include a table that lists the project disturbed area, pre/post-development impervious cover, pre/post-development open space, water quality compliance method, water quantity-channel protection compliance method, and water quantity-flood protection compliance method.

2. ESC Minimum Standards

Yes	No	NA		
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-1	Temporary and permanent stabilization been addressed in the narrative
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Practices shown on the plan
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Temporary and permanent seed specifications
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Lime and fertilizer
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Mulching
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Blankets/Matting
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Pavement/Construction Road Stabilization
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-2	Stabilization of soil stockpiles, borrow areas, and disposal areas been addressed in the narrative and on the plan
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Sediment trapping measures been provided
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-3	Establishment and maintenance of permanent vegetative stabilization been addressed
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-4	Plan specifically states that sediment-trapping facilities shall be constructed as a first step in land-disturbing activities
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-5	Plan specifically states that stabilization of earthen structures is required immediately after installation? Is this noted for each measure on the plan?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-6	Sediment traps and sediment basins specified where needed and designed to the standards and specifications
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-7	Design and temporary/permanent stabilization of cut and fill slopes been adequately addressed? Surface Roughening provided for slopes steeper than 3:1?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-8	Adequate temporary or permanent conveyances (paved flumes, channels, slope drains) been provided for concentrated stormwater runoff on cut and fill slopes
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-9	Water seeping from a slope face been addressed (e.g., subsurface drains)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-10	Adequate inlet protection provided for all operational storm drain and culvert inlets
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-11	Are adequate outlet protection and/or channel linings provided for all stormwater conveyance and receiving channels? Is there a schedule indicating:
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Dimensions of the outlet protection? Lining? Size of riprap?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		Cross section and slope of the channels? Type of lining? Size of riprap, if used?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-12	In-stream protection measures required so that channel impacts are minimized
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-13	Temporary stream crossings of non-erodible material required where applicable
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	MS-14	All applicable federal, state and local regulations pertaining to working in or crossing live watercourses being followed

- ☐ ☐ ☐ MS-15 Immediate restabilization of areas subject to in-stream construction (bed and banks) been adequately addressed
- ☐ ☐ ☐ MS-16 Have disturbances from underground utility line installations been addressed?
- ☐ ☐ ☐ No more than 500 linear feet of trench open at one time
- ☐ ☐ ☐ Effluent from dewatering filtered or passed through a sediment-trapping device
- ☐ ☐ ☐ Proper backfill, compaction, and restabilization
- ☐ ☐ ☐ MS-17 Transport of soil and mud onto public roadways properly controlled (i.e., Construction Entrances, wash racks, transport of sediment to a trapping facility, no washing before sweeping and shoveling)
- ☐ ☐ ☐ MS-18 Removal of temporary practices has been addressed
- ☐ ☐ ☐ Have the removal of accumulated sediment and the final stabilization of the resulting disturbed areas been addressed?
- ☐ ☐ ☐ MS-19 Properties and waterways downstream from development adequately protected deposition, erosion, and damage due to increases in volume, velocity and peak flow rate of stormwater runoff
- ☐ ☐ ☐ Concentrated stormwater runoff leaving the development site discharged to an man-made receiving channel, pipe or storm sewer system
- ☐ ☐ ☐ Calculations provided to verify the adequacy of all channels and pipes
- ☐ ☐ ☐ If existing natural receiving channels or previously constructed man-made channels or pipes are not adequate, provisions have been made to prevent downstream erosion
- ☐ ☐ ☐ Increased volumes of sheet flows that may cause erosion or sedimentation on adjacent property-diverted to a stable outlet, adequate channel, pipe or pipe system, or to a detention facility

3. Narrative

3.1 Project description – This section shall describe the nature and purpose of the land-disturbing activity.

Provide project specific information. Also include the following:

- ☐ Provide the area (acres to the nearest hundredth) to be disturbed. This disturbed area (limits of disturbance) shall include laydown, access and any other areas that may be disturbed during the course of the project. This area shall provide adequate space for the contractor to perform required work for excavation and grading
- ☐ Provide the existing impervious area and the increase, or decrease, in impervious area (acres).
- ☐ Estimated schedule for project. (Start/end dates, or estimated length of project in months or years)
- ☐ Ultimate developed condition of the site.

3.2 Existing site conditions – This section shall provide a description of the existing topography (% slopes), ground cover, and drainage (on-site and receiving channels).

- ☐ Discuss any existing drainage or erosion problems and how they are to be corrected.
- ☐ Provide the size of drainage areas in pre-development and post-development conditions.

3.3 Adjacent areas – This section shall provide a description of all neighboring areas such as residential developments, agricultural areas, streams, lakes, roads, etc., that may be affected by the land disturbance. Discuss any environmentally sensitive areas, including any on-site or adjacent water bodies included in the Virginia 303(d) list of impaired waters, and any possible problems during and after construction (traffic issues, dust control, increases in runoff, etc.).

3.4 Off-site areas – This section shall describe any off-site land-disturbing activities that may occur (borrow sites, disposal areas, easements, etc.). Identify the Owner of the off-site area and the locality responsible for plan review. Include a statement that any off-site land-disturbing activity associated with this project must have an approved ESC Plan. Submit documentation of the approved ESC Plan for each of these sites.

3.5 Soils – This section shall provide a description of the soils on the site, giving such information as soil name, mapping unit, erodibility, permeability, surface runoff, and a brief description of depth, texture and soil structure.

- ☐ Indicate reference for additional soil information if not included within this section.
- ☐ Provide a reference to where a copy of the soil survey map can be found within the plan set or engineering report.

3.6 Critical areas – This section shall provide a description of areas on the site that may have potentially serious erosion problems or that are sensitive to sediment impacts (e.g., critical slopes, watercourses, wet weather / underground springs, etc.). Discuss any area(s) of the project which may become critical during the project.

_____ **3.7 Erosion and sediment control measures** – This section shall provide a description of the structural and vegetative methods that will be used to control erosion and sedimentation on the site. Controls should satisfy applicable minimum standards and specifications in Chapter 7 of the latest edition of the Virginia Stormwater Management Handbook (VSMH).

_____ **3.8 Management strategies/Sequence of construction** – This section shall address management strategies, the sequence of construction, and any phasing for the installation of ESC measures. The sequence of construction shall provide specific details concerning the construction and installation and phasing of ESC and SWM measures.

_____ **3.9 Permanent stabilization** – This section shall provide a brief description, including specifications, of how the site will be stabilized after construction is completed. List any soil testing requirements. A permanent vegetative cover shall be established on denuded areas not otherwise permanently stabilized. Permanent vegetation shall not be considered established until a ground cover is achieved that is uniform, mature enough to survive and will inhibit erosion.

_____ **3.10 Maintenance of ESC measures** – This section shall provide a schedule of regular inspections, maintenance, and repair of erosion and sediment control structures should be set forth. List who will be responsible for ESC maintenance during the course of the project. VESCH control measures shall be maintained in accordance with the VESCH maintenance schedules, and non-VESCH control measures shall be maintained in accordance with the manufacturer's recommendations.

_____ **3.11 Calculations for temporary erosion and sediment control measures** – For each temporary ESC measure, provide the calculations required by the standards and specifications. All calculations showing pre-development and post-development runoff should be provided including any worksheets, assumptions, and engineering decisions.

_____ **3.12 Stormwater management** – Will the development of the site cause an increase in peak runoff rates? Will the increase in runoff cause flooding or channel degradation downstream? Reference where each piece of information can be found within the plan set or engineering report.

Describe the strategy to control stormwater runoff:

- ☐ Provide exhibits showing the drainage divides, the direction of flow, and the size (acreage) of each of the site drainage areas that discharge runoff off-site, both existing and proposed.
- ☐ Provide calculations for pre- and post-development runoff from these drainage areas.
- ☐ Ensure that Minimum Standard 19 is satisfied for each off-site receiving channel, including those that receive runoff from stormwater management facilities.
- ☐ Provide calculations for the design of each permanent stormwater management facility.
- ☐ Ensure that increased volumes of sheet flows are diverted to a stable outlet, to an adequate channel, pipe or pipe system, or to a stormwater management facility.
- ☐ Provide adequacy calculations (capacity and erosion resistance) for all on-site stormwater conveyances in accordance with the next checklist item.

_____ **3.13 Calculations** – Provide the following design calculations as applicable:

- ☐ Drainage area map with time of concentration (TC) path shown and points of analysis with worksheets.
- ☐ TC calculation/nomograph
- ☐ Locality IDF curve
- ☐ Composite runoff coefficient or RCN calculation
- ☐ Peak runoff calculations
- ☐ Stormwater conveyance channel design calculations
- ☐ Storm drain and storm sewer system design calculations
- ☐ Hydraulic Grade Line if any pipe in the system is more than 90% full for a 10-year storm
- ☐ Culvert design calculations
- ☐ Drop Inlet backwater calculations
- ☐ Curb inlet length calculations
- ☐ Water quality calculations for BMPs including worksheets

_____ **3.14 Maintenance of SWM Facilities** – Provide a table with a description of requirements for maintenance of the facility and a recommended schedule for inspections and maintenance.

_____ **3.15 Water Quality** – Is the plan in compliance with 9VAC25-875-590 water quality criteria requirements for new development and development on prior developed land?

_____ **3.16 Water Quantity** – Is the plan (including prescribed calculations) in compliance with 9VAC25-875-600 water quantity criteria requirements?

_____ **3.17 General Construction Permit** – Ensure that the stormwater management criteria outlined in the general construction permit (9VAC25-880) are met as well as, the elements presented in 9VAC25-875-850.

_____ **3.18 BMP Calculations** - Provide supporting calculations for each best management practice with a checklist; include a completed Design and Plan Review Checklist from Appendix 3 of the Virginia Stormwater Management Handbook. The Virginia Runoff Reduction Method or an equivalent method approved by the board (9VAC25-875-590) shall be used to determine water quality criteria.

_____ **3.19 Specifications for Stormwater and Stormwater Management Structures** – Provide specifications for stormwater and stormwater management structures, i.e., pipe materials, pipe bedding, and stormwater structures.

_____ **3.20 Page Numbers** – Number the pages of the Narrative and the Calculations.

_____ **3.21 General Information** – Narrative contains project specific information, and where appropriate general information has been modified to represent the project specific information and situation.

4. Site Plan

- _____ **4.1 Owner Contact Information** – On the cover sheet, provide name, address, telephone number and email of the owner representative/project manager.
- _____ **4.2 Vicinity Map** – A small map locating the site in relation to the surrounding area. Include any landmarks.
- _____ **4.3 Indicate North** – The direction of north in relation to the site.
- _____ **4.4 Limits of Disturbance** – Areas which are to be cleared and graded and areas to be protected during construction. This disturbed area shall include laydown, access and any other areas that may be disturbed during the course of the project. Provide notes on how areas will be marked and for areas NOT to be disturbed.
- _____ **4.5 Existing Contours** – The existing contours of the site shall be shown as dashed light lines and elevation labeled adequately.
- _____ **4.6 Final Contours and Elevations** – Changes to the existing contours, including final drainage patterns. Note the finished floor elevation (FFE) of all buildings on site, including basements. Proposed contour lines shall be solid and bolder than existing contour lines and the elevations labeled.
- _____ **4.7 Profile of Storm Drain System** – Proposed storm drainage components shall be provided in a profile. Pipe diameter, material, inverts, stationing, percent slope, proposed and existing grade, etc. shall be included as part of the profile.
- _____ **4.8 Existing Vegetation** – The existing tree lines, grassed areas, or unique vegetation.
- _____ **4.9 Soils Map** – The boundaries of different soil types, K factor and soil survey classifications.
- _____ **4.10 Existing Drainage Patterns** – The dividing lines and the direction of flow for the different drainage areas. Include the size (acres) of each drainage area.
- _____ **4.11 Proposed Drainage Patterns** – The dividing lines and the direction of flow for the different drainage areas. Include the size (acres) of each drainage area.
- _____ **4.12 Critical Areas** – Note all areas with potentially serious erosion problems.
- _____ **4.13 Site Development** – Show all improvements such as buildings, parking lots, access roads, utility construction, etc.
- _____ **4.14 Landscape Plan** – Include a plan showing location and plant selection for landscaped areas.

- _____ **4.15 Location of Practices** – Show locations of ESC and SWM practices to be used on the site. Use standard symbols and abbreviations from the VSMH. A legend denoting symbols, line uses and other special characters shall be provided.
- _____ **4.16 Offsite Areas** – Include any off-site land-disturbing activities (e.g., borrow sites, disposal areas, etc.) not covered by a separate approved ESC Plan. Discuss who has final authority for off-site areas and who will be responsible for stabilization.
- _____ **4.17 Detail Drawings** – Show detail drawings of all SWM and ESC practices to be implemented. Any structural practices used that are not referenced to the VSMH or local handbooks should be explained and illustrated with detail drawings. Details should be provided which are clearly dimensioned and reflect the ability to be "built" in the field according to proper design criteria. Alternative ESC/SWM measures must have proper drawings to indicate how and where they are to be constructed.
- _____ **4.18 Erosion and Sediment Control Notes** – At a minimum, include the erosion and sediment control notes found in Appendix G. Ensure that all applicable Minimum Standards not covered elsewhere in the plan have been addressed. Ensure that the requirements of Part II.A.2 of the General Construction Permit (9VAC25-880) are addressed.
- _____ **4.19 Minimum Standards** – Minimum Standard 1 through Minimum Standard 19 shall be included in the plan set.
- _____ **4.20 Legend** – Provide a complete listing of all ESC and SWM measures to be used, including the VSMH uniform code symbol and the standard and specification number. Include any other items necessary to identify pertinent features in the plan.
- _____ **4.21 Property Lines and Easements** – Show all property and easement lines. For each adjacent property, list the deed book and page number and the property owner's name and address.

Project Name: _____

Plan Preparer's Signature: _____ **Date:** _____

Appendix I:

Delegation of Authority

Old Dominion University

Delegation of Authority Form

I, _____ (name), hereby designate the person(s) listed below to serve as a representative of Old Dominion University in the capacity of _____.

Program Administrator Signature _____ Date _____

_____ Name of Person/Position

_____ DEQ Certification

_____ Company Name

_____ Address

_____ Phone Number

With my signature, I confirm that I satisfy the requirements and definition of _____ as detailed in the Old Dominion University Standards and Specifications.

"I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature _____ Date _____

Name _____